

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
116R-4	DEKALB		416	50
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

XX146400	STORM SEWER REMOVAL (CONT.)				
	FOOT	LOCATION			
		US 30			
	125	RT	825+08.00	TO	826+36.00
	10	LT	826+26.53	TO	826+29.50
	50	-	826+27.00	TO	826+36.00
	80	LT	827+07.00	TO	826+27.00
	48	RT	826+84.00	TO	826+36.00
	44	LT	829+86.00	TO	830+30.00
	112	-	830+20.20	TO	830+21.60
	9	LT	830+21.84	TO	830+30.44
	148	RT	832+69.00	TO	834+17.00
	12	LT	833+47.00	TO	833+48.00
	45	LT	833+47.00	TO	833+92.00
	6	LT	833+92.00	TO	833+97.00
	66	-	833+92.00	TO	834+17.00
	88	-	837+16.00	TO	837+16.00
	44	-	840+19.30	TO	840+19.30
	124	LT	847+07.00	TO	848+31.00
	28	LT	848+31.00	TO	848+31.00
	44	-	848+31.00	TO	848+38.70
	472	LT	848+31.00	TO	853+05.00
	45	LT	855+93.00	TO	856+35.52
				TO	
	11	LT	141+12.00	TO	141+24.00
	76	LT	140+36.00	TO	141+12.00
TOTAL	2050				

Z0014800	CULVERT TO BE CLEANED			REMARKS
	FOOT	LOCATION		
	45	793+43.90	68' RT	12" DIA. CMP
	130	802+30.30	35' RT	15" DIA. CMP
TOTAL	175			

Z0017100	DOWEL BARS			REMARKS
	EACH	LOCATION		
	88.0	799+45.00		CLASS B PATCH
TOTAL	88			

Z0023600	FILLING EXISTING CULVERTS		
	EACH	LOCATION	
	1.0	803+71	
TOTAL	1		

Z0024478	FLEXIBLE DELINEATORS			REMARKS
	EACH	LOCATION		
		STAGE II		
	7	25' spacing	795+25.00	TO 796+75.00
	4	16.6' spacing	796+75.00	TO 797+25.00
	4	16.6' spacing	798+80.00	TO 799+30.00
	5	50' spacing	799+30.00	TO 801+80.00
	15	50' spacing	802+40.00	TO 809+90.00
	4	16.6' spacing	810+00.00	TO 810+50.00
	4	16.6' spacing	811+15.00	TO 811+65.00
	5	50' spacing	811+65.00	TO 813+65.00
	4	16.6' spacing	813+95.00	TO 814+45.00
	4	16.6' spacing	815+15.00	TO 815+65.00
	5	50' spacing	815+65.00	TO 818+15.00
	4	16.6' spacing	818+15.00	TO 818+65.00
	4	16.6' spacing	819+25.00	TO 819+75.00
	33	50' spacing	819+75.00	TO 836+25.00
	4	16.6' spacing	836+57.00	TO 837+07.00
	4	16.6' spacing	837+78.50	TO 838+28.50
	1	50' spacing	838+75.00	TO 841+25.00
	9	25' spacing	839+25.00	TO 841+25.00
SUB-TOTAL	120			

Z0024478	FLEXIBLE DELINEATORS (CONT.)			REMARKS
	EACH	LOCATION		
		STAGE III		
	9	25' spacing	795+25.00	TO 797+35.00
	4	16.6' spacing	797+60.00	TO 798+10.00
	4	16.6' spacing	798+80.00	TO 799+30.00
	19	50' spacing	799+80.00	TO 808+80.00
	4	16.6' spacing	809+30.00	TO 809+80.00
	4	16.6' spacing	810+25.00	TO 810+75.00
	7	50' spacing	811+15.00	TO 814+25.00
	9	50' spacing	814+80.00	TO 818+80.00
	4	16.6' spacing	819+00.00	TO 819+50.00
	4	16.6' spacing	820+20.00	TO 820+70.00
	3	50' spacing	821+25.00	TO 822+25.00
	3	16.6' spacing	822+25.00	TO 822+75.00
	3	16.6' spacing	823+45.00	TO 823+78.00
	4	50' spacing	824+28.00	TO 825+75.00
	3	16.6' spacing	825+91.50	TO 826+25.00
	3	16.6' spacing	826+90.00	TO 827+23.50
	4	50' spacing	827+75.00	TO 829+25.00
	3	16.6' spacing	829+41.70	TO 829+75.00
	3	16.6' spacing	830+30.00	TO 830+63.30
	4	50' spacing	831+25.00	TO 832+75.00
	3	16.6' spacing	833+22.60	TO 833+56.00
	3	16.6' spacing	834+10.00	TO 834+44.50
	1	50' spacing	834+95.00	TO 835+78.50
	3	16.6' spacing	835+45.00	TO 837+12.00
	6	16.6' spacing	836+28.00	TO 837+78.00
	3	16.6' spacing	837+78.00	TO 838+11.50
	9	25' spacing	838+25.00	TO 840+25.00
SUB-TOTAL	129			

	STAGE V		
	5	25' spacing	836+30.00 TO 837+25.00
	6	50' spacing	837+75.00 TO 840+60.00
	3	16.6' spacing	840+96.00 TO 841+29.00
	3	16.6' spacing	842+00.00 TO 842+33.50
	10	50' spacing	842+80.00 TO 847+30.00
	3	16.6' spacing	847+46.80 TO 847+80.00
	3	16.6' spacing	848+45.50 TO 848+78.70
	6	50' spacing	849+30.00 TO 851+80.00
	3	16.6' spacing	852+05.50 TO 852+39.00
	3	16.6' spacing	853+18.50 TO 853+52.00
	3	50' spacing	854+00.00 TO 855+00.00
	3	16.6' spacing	855+56.00 TO 855+89.40
	3	16.6' spacing	856+33.00 TO 856+66.00
	33	50' spacing	857+15.00 TO 873+75.00
	8	25' spacing	874+25.00 TO 876+25.00
SUB-TOTAL	95		

	STAGE VI		
	5	25' spacing	836+30.00 TO 837+25.00
	20	50' spacing	837+75.00 TO 847+25.00
	3	16.6' spacing	847+75.00 TO 848+08.00
	5	16.6' spacing	848+91.00 TO 849+57.40
	6	16.6' spacing	850+30.50 TO 851+13.80
	4	50' spacing	851+75.00 TO 853+25.00
	3	50' spacing	854+15.00 TO 855+15.00
	3	16.6' spacing	855+31.80 TO 855+65.00
	3	16.6' spacing	856+45.50 TO 856+78.80
	4	50' spacing	857+28.00 TO 858+78.00
	6	50' spacing	859+60.00 TO 862+10.00
	22	50' spacing	863+25.00 TO 873+75.00
	8	25' spacing	874+25.00 TO 876+25.00
SUB-TOTAL	92		
TOTAL	436		

PLOT DATE = Fri, Dec 02 09:05:51 2005
 FILE NAME = C:\pcc\pcc\pcc\2005\1700\1700c-1.dgn
 PLOT SCALE = 5/8"=1'-0"
 USER NAME = jordanhd