

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	J16R-4	DEKALB	416	52
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

STAGE 0

STAGE 1

LOCATION	STAGE 0				STAGE 1			
	EARTH EXCAVATION (Cu Yd)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (Cu Yd)	EMBANKMENT (Cu Yd)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) (Cu Yd)	EARTH EXCAVATION (Cu Yd)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (Cu Yd)	EMBANKMENT (Cu Yd)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) (Cu Yd)
786+25.00 TO 788+00.00	67.7	50.8	50.2	0.6				
788+00.00 TO 794+00.00	421.2	315.9	116.6	199.3				
794+00.00 TO 800+00.00	1185.4	889.1	334.9	554.2				
800+00.00 TO 806+00.00					14.7	11.0	1.1	9.9
806+00.00 TO 812+00.00					264.7	198.5	566.8	-368.3
812+00.00 TO 818+00.00					385.5	289.1	167.9	121.2
818+00.00 TO 824+00.00					766.3	574.7	0.0	574.7
824+00.00 TO 829+00.00					506.3	379.7	0.0	379.7
829+00.00 TO 835+00.00								
835+00.00 TO 841+00.00					118.9	89.2	7.1	82.1
841+00.00 TO 847+00.00					332.7	249.5	21.6	227.9
847+00.00 TO 853+00.00					1.0	0.8	0.0	0.8
853+00.00 TO 859+00.00								
859+00.00 TO 865+00.00								
865+00.00 TO 871+00.00								
871+00.00 TO 876+25.00								
SOMONAUK RD 30+75.00 TO 31+97.60	50.4	37.8	5.4	32.4				
RAY ST 898+50.00 TO 899+50.00								
WALGREN ST 64+90.00 TO 69+50.00 61+07.58 TO 63+47.37	873.8	655.4	0.0	655.4				
S. VIEW ST 78+44.00 TO 79+50.00								
N. VIEW ST 80+50.00 TO 81+43.00								
GARFIELD ST 99+00.00 TO 101+35.00								
S. MAY ST 119+29.00 TO 119+50.00								
N. MAY ST 120+50.00 TO 121+57.00								
S. SYCAMORE ST. 138+72.00 TO 139+50.00								
N. SYCAMORE ST. 140+50.00 TO 141+55.00								
MAPLE ST. 160+50.00 TO 161+85.00								
S. OAK ST. 179+20.00 TO 179+50.00								
N. OAK ST. 180+50.00 TO 185+24.00								
TOTALS	2598.5	1948.9	507.1	1441.8	2390.1	1792.6	764.5	1028.1

PLOT DATE = Fri Sep 02 09:56:17 2005
 FILE NAME = C:\p\o\mets\201706\1081706ev.dgn
 PLOT SCALE = 50:0000 / IN.
 USER NAME = jbr@amg

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. / HORIZ. DATE
DRAWN BY		CHECKED BY

EARTHWORK SCHEDULE