

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	J16R-4	DEKALB	416	53
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

STAGE 2

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE
	(Cu Yd)	(Cu Yd)	(Cu Yd)	WASTE (+) SHORTAGE (-) (Cu Yd)
786+25.00 TO 788+00.00				
788+00.00 TO 794+00.00				
794+00.00 TO 800+00.00	10.0	7.5	0.3	7.2
800+00.00 TO 806+00.00	618.8	464.1	294.8	169.3
806+00.00 TO 812+00.00	2101.4	1576.1	50.4	1525.7
812+00.00 TO 818+00.00	1627.4	1220.6	18.6	1202.0
818+00.00 TO 824+00.00	984.8	738.6	14.3	724.3
824+00.00 TO 829+00.00	972.6	729.5	17.3	712.2
829+00.00 TO 835+00.00	842.4	631.8	10.8	621.0
835+00.00 TO 841+00.00	1073.4	805.1	2.0	803.1
841+00.00 TO 847+00.00	47.4	35.6	0.4	35.2
847+00.00 TO 853+00.00				
853+00.00 TO 859+00.00				
859+00.00 TO 865+00.00				
865+00.00 TO 871+00.00				
871+00.00 TO 876+25.00				
SOMONAUK RD				
30+75.00 TO 31+97.60				
RAY ST				
898+50.00 TO 899+50.00				
WALGREN ST				
64+90.00 TO 69+50.00				
61+07.58 TO 63+47.37				
S. VIEW ST				
78+44.00 TO 79+50.00				
N. VIEW ST				
80+50.00 TO 81+43.00	148.8	111.6	0.3	111.3
CARFIELD ST				
99+00.00 TO 101+35.00	394.8	296.1	3.1	293.0
S. MAY ST				
119+29.00 TO 119+50.00				
N. MAY ST				
120+50.00 TO 121+57.00	301.9	226.4	1.3	225.1
S. SYCAMORE ST.				
138+72.00 TO 139+50.00				
N. SYCAMORE ST.				
140+50.00 TO 141+55.00	443.1	332.3	1.6	330.7
MAPLE ST.				
160+50.00 TO 161+85.00	500.4	375.3	5.3	370.0
S. OAK ST.				
179+20.00 TO 179+50.00				
N. OAK ST.				
180+50.00 TO 185+24.00	1454.4	1090.8	15.4	1075.4
TOTALS	11521.6	8641.2	435.9	8205.3

STAGE 3

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE
	(Cu Yd)	(Cu Yd)	(Cu Yd)	WASTE (+) SHORTAGE (-) (Cu Yd)
786+25.00 TO 788+00.00				
788+00.00 TO 794+00.00				
794+00.00 TO 800+00.00				
800+00.00 TO 806+00.00	472.1	354.1	61.4	292.7
806+00.00 TO 812+00.00	855.2	641.4	127.1	514.3
812+00.00 TO 818+00.00	729.8	547.4	244.4	303.0
818+00.00 TO 824+00.00	682.1	511.6	201.9	309.7
824+00.00 TO 829+00.00	1095.6	821.7	25.0	796.7
829+00.00 TO 835+00.00	1089.3	817.0	111.4	705.6
835+00.00 TO 841+00.00	691.5	518.6	181.0	337.6
841+00.00 TO 847+00.00				
847+00.00 TO 853+00.00				
853+00.00 TO 859+00.00				
859+00.00 TO 865+00.00				
865+00.00 TO 871+00.00				
871+00.00 TO 876+25.00				
SOMONAUK RD				
30+75.00 TO 31+97.60				
RAY ST				
898+50.00 TO 899+50.00	281.6	211.2	1.3	209.9
WALGREN ST				
64+90.00 TO 69+50.00	1020.6	765.5	23.2	742.3
61+07.58 TO 63+47.37				
S. VIEW ST				
78+44.00 TO 79+50.00	245.7	184.3	4.5	179.8
N. VIEW ST				
80+50.00 TO 81+43.00	148.8	111.6	0.3	111.3
CARFIELD ST				
99+00.00 TO 101+35.00	394.8	296.1	3.1	293.0
S. MAY ST				
119+29.00 TO 119+50.00				
N. MAY ST				
120+50.00 TO 121+57.00	301.9	226.4	1.3	225.1
S. SYCAMORE ST.				
138+72.00 TO 139+50.00				
N. SYCAMORE ST.				
140+50.00 TO 141+55.00	443.1	332.3	1.6	330.7
MAPLE ST.				
160+50.00 TO 161+85.00	500.4	375.3	5.3	370.0
S. OAK ST.				
179+20.00 TO 179+50.00				
N. OAK ST.				
180+50.00 TO 185+24.00	1454.4	1090.8	15.4	1075.4
TOTALS	7409.4	5557.1	989.2	4567.9

PLOT DATE = Fri Sep 22 09:16:23 2005
 FILE NAME = C:\pvc\pvc\stn\201708\dl708-vr.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = jordanhd

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. _____
 HORIZ. _____

DATE _____

DRAWN BY _____
 CHECKED BY _____

EARTHWORK SCHEDULE