

| | | | | |
|---------------------|---------|----------|------------------|-----------|
| F.A.R. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 573 | J16R-4 | DEKALB | 416 | 54 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

STAGE 4

STAGE 5

| LOCATION | STAGE 4 | | | | STAGE 5 | | | |
|--|-----------------------------|--|-----------------------|---|-----------------------------|--|-----------------------|---|
| | EARTH EXCAVATION (Cu Yd) | EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (Cu Yd) | EMBANKMENT (Cu Yd) | EARTHWORK BALANCE WASTE (+) SHORTAGE (-) (Cu Yd) | EARTH EXCAVATION (Cu Yd) | EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (Cu Yd) | EMBANKMENT (Cu Yd) | EARTHWORK BALANCE WASTE (+) SHORTAGE (-) (Cu Yd) |
| 799+75.00 TO 800+00.00 | 40.9 | 30.7 | 8.1 | 22.6 | | | | |
| 800+00.00 TO 806+00.00 | 323.8 | 242.9 | 206.6 | 36.3 | | | | |
| 806+00.00 TO 812+00.00 | | | | | | | | |
| 812+00.00 TO 818+00.00 | | | | | | | | |
| 818+00.00 TO 824+00.00 | | | | | | | | |
| 824+00.00 TO 829+00.00 | | | | | | | | |
| 829+00.00 TO 835+00.00 | | | | | | | | |
| 835+00.00 TO 841+00.00 | 65.9 | 49.4 | 1.7 | 47.7 | 693.9 | 520.4 | 148.0 | 372.4 |
| 841+00.00 TO 847+00.00 | 609.4 | 457.1 | 20.3 | 436.8 | 893.5 | 670.1 | 49.5 | 620.6 |
| 847+00.00 TO 853+00.00 | 741.1 | 555.8 | 6.2 | 549.6 | 1093.5 | 820.1 | 22.9 | 797.2 |
| 853+00.00 TO 859+00.00 | 523.9 | 392.9 | 112.5 | 280.4 | 1757.9 | 1318.4 | 189.3 | 1129.1 |
| 859+00.00 TO 865+00.00 | 291.6 | 218.7 | 206.3 | 12.4 | 749.9 | 562.4 | 338.9 | 223.5 |
| 865+00.00 TO 871+00.00 | 324.5 | 243.4 | 143.6 | 99.8 | 641.5 | 481.1 | 90.0 | 391.1 |
| 871+00.00 TO 876+25.00 | 197.9 | 148.4 | 121.8 | 26.6 | 158.7 | 119.0 | 5.5 | 113.5 |
| WALNUT ST 200+50.00 TO 205+22.00 | | | | | | | | |
| COSTER PL 220+50.00 TO 224+42.00 | | | | | | | | |
| DONALD ST 240+50.00 TO 244+43.00 | | | | | | | | |
| SOUTH OF DONALD OUTLET 1+00.00 TO 8+00.00 | 227.6 | 170.7 | 66.9 | 103.8 | | | | |
| SANDWICH RD 258+50.00 TO 259+50.00 | | | | | 265.0 | 198.8 | 255.7 | -57.0 |
| REES ST 260+50.00 TO 261+25.00 | | | | | | | | |
| TOTALS | 3346.6 | 2510.0 | 894.0 | 1616.0 | 6253.9 | 4690.4 | 1099.8 | 3590.6 |

PLOT DATE = Fri Sep 02 09:16:31 2005
 FILE NAME = C:\p\o\mets\p201780\801780evr.dgn
 PLOT SCALE = 50.0000' / IN.
 USER NAME = jor-danid

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|-----------|------|---------------------------------------|
| NAME | DATE | |
| | | SCALE: VERT. HORIZ. DATE |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

DRAWN BY
 CHECKED BY
EARTHWORK SCHEDULE