

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	J16R-4	DEKALB	416	55
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STAGE 6

STAGE 2a

STAGE 7

LOCATION	STAGE 6				STAGE 2a				STAGE 7			
	EARTH EXCAVATION (Cu Yd)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (Cu Yd)	EMBANKMENT (Cu Yd)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) (Cu Yd)	EARTH EXCAVATION (Cu Yd)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (Cu Yd)	EMBANKMENT (Cu Yd)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) (Cu Yd)	EARTH EXCAVATION (Cu Yd)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (Cu Yd)	EMBANKMENT (Cu Yd)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) (Cu Yd)
799+75.00 TO 800+00.00												
800+00.00 TO 806+00.00												
806+00.00 TO 812+00.00												
812+00.00 TO 818+00.00												
818+00.00 TO 824+00.00												
824+00.00 TO 829+00.00												
829+00.00 TO 835+00.00												
835+00.00 TO 841+00.00	461.3	346.0	13.7	332.3	114.3	85.7	0.0	85.7				
841+00.00 TO 847+00.00	554.5	415.9	177.2	238.7	282.0	211.5	0.0	211.5				
847+00.00 TO 853+00.00	714.4	535.8	178.7	357.1	0.0		0.0					
853+00.00 TO 859+00.00	892.4	669.3	161.2	508.1								
859+00.00 TO 865+00.00	837.1	627.8	128.1	499.7								
865+00.00 TO 871+00.00	776.3	582.2	137.0	445.2								
871+00.00 TO 876+25.00	283.4	212.6	102.6	110.0					433.5	325.1	112.9	212.2
									107.6	80.7	83.7	-3.0
WALNUT ST 200+50.00 TO 205+22.00	1432.5	1074.4	4.0	1070.4								
COSTER PL 220+50.00 TO 224+42.00	1013.2	759.9	2.4	757.5								
DONALD ST 240+50.00 TO 244+43.00	1099.9	824.9	0.0	824.9								
SOUTH OF DONALD OUTLET 1+00.00 TO 8+00.00												
SANDWICH RD 258+50.00 TO 259+50.00												
REES ST 260+50.00 TO 261+25.00	203.0	152.3	46.4	105.9								
TOTALS	8268.0	6201.0	951.3	5249.7	396.3	297.2	0.0	297.2	541.1	405.8	196.6	209.2

TOTALS

LOCATION	EARTH EXCAVATION (Cu Yd)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (Cu Yd)	EMBANKMENT (Cu Yd)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) (Cu Yd)
STAGE 0	2598.5	1948.9	507.1	1441.8
STAGE 1	2390.1	1792.6	764.5	1028.1
STAGE 2	11521.6	8641.2	435.9	8205.3
STAGE 3	7409.4	5557.1	989.2	4567.9
STAGE 4	3346.6	2510.0	894.0	1616.0
STAGE 5	6253.9	4690.4	1099.8	3590.6
STAGE 6	8268.0	6201.0	951.3	5249.7
STAGE 7	541.1	405.8	196.6	209.2
STAGE 2a	396.3	297.2	0.0	297.2
GRAND TOTALS	42725.5	32044.1	5838.4	26205.7

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY

EARTHWORK SCHEDULE