

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	J168-4	DEKALB	416	55
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	LEFT									
	25200100	21101615	25000910	25001830	25000400	25000500	25000600	25100115	28000250	25200200
	SODDING	TOPSOIL F & P, 4"	SEEDING CLASS 1 MODIFIED ACRES	SEEDING CLASS 6 MODIFIED ACRES	NITROGEN FERTILIZER NUTRIENT LBS	PHOSPHORUS FERTILIZER NUTRIENT LBS	POTASSIUM FERTILIZER NUTRIENT LBS	MULCH METHOD 2 ACRES	TEMPORARY EROSION CONTROL SEEDING LBS	SUPPLEMENTAL WATERING UNIT
MAINLINE										
785+85.0 TO 798+40.0 West End to Somonauk			0.32		28.8	28.8	28.8	0.32	128.0	
798+40.0 TO 802+28.9 Somonauk to Mack	654.1	654.1			8.1	8.1	8.1		54.1	29.4
802+28.9 TO 810+85.7 Mack to Ray	1,371.6	1,371.6			17.0	17.0	17.0		113.4	61.7
810+85.7 TO 814+77.2 Ray to Walgren	303.2	303.2			3.8	3.8	3.8		25.1	13.6
814+77.2 TO 819+86.8 Walgren to N. View	348.4	348.4			4.3	4.3	4.3		28.8	15.7
819+86.8 TO 823+13.7 N. View to Garfield	241.6	241.6			3.0	3.0	3.0		20.0	10.9
823+13.7 TO 826+57.3 Garfield to S. May	92.9	92.9			1.2	1.2	1.2		7.7	4.2
826+57.3 TO 830+03.3 S. May to S. Sycamore	27.7	27.7			0.3	0.3	0.3		2.3	1.2
830+03.3 TO 833+75.9 S. Sycamore to Maple	75.3	75.3			0.9	0.9	0.9		6.2	3.4
833+75.9 TO 837+44.6 Maple to N. Oak	559.0	559.0			6.9	6.9	6.9		46.2	25.2
837+44.6 TO 841+62.0 Oak to Walnut	473.7	473.7			5.9	5.9	5.9		39.1	21.3
841+62.0 TO 848+11.2 Walnut to Coster	517.0	517.0			6.4	6.4	6.4		42.7	23.3
848+11.2 TO 852+79.1 Coster to Donald	405.8	405.8			5.0	5.0	5.0		33.5	18.3
852+79.1 TO 856+11.6 Donald to Rees/Sandwich	357.1	357.1			4.4	4.4	4.4		29.5	16.1
856+11.6 TO 859+70.0 Rees/Sandwich to High School	727.9	727.9			9.0	9.0	9.0		60.2	32.8
859+70.0 TO 876+25.0 High School to East End			0.81		72.9	72.9	72.9	0.81	324.0	
SOMONAUK RD										
18+49.4 TO 20+00.0 South End			0.05		4.8	4.8	4.8	0.05	21.1	
30+00.0 TO 31+97.6 North End			0.03		2.9	2.9	2.9	0.03	13.1	
RAY STREET										
898+50.4 TO 900+00.0	69.9	69.9			0.9	0.9	0.9		5.8	3.1
WAHLGREN AVE										
64+90.0 TO 70+00.0	275.4	275.4			3.4	3.4	3.4		22.8	12.4
61+07.6 TO 64+87.6 Drainage Ditch				0.16	14.4	14.4	14.4	0.16	64.0	
VIEW ST										
78+44.0 TO 80+00.0 South End	56.0	56.0			0.7	0.7	0.7		4.6	2.5
80+00.0 TO 81+42.7 North End	54.1	54.1			0.7	0.7	0.7		4.5	2.4
GARFIELD ST										
99+14.0 TO 101+34.7 North and South Ends	270.1	270.1			3.3	3.3	3.3		22.3	12.2
93+40.1 TO 97+07.2 Drainage Ditch				0.17	15.3	15.3	15.3	0.17	68.0	
MAY ST										
119+29.1 TO 120+00.0 South End	0.0	0.0			0.2	0.2	0.2		1.2	0.7
120+00.0 TO 121+56.7 North End	14.7	14.7								
SYCAMORE ST										
138+96.9 TO 140+00.0 South End	16.4	16.4			0.2	0.2	0.2		1.4	0.7
140+00.0 TO 141+55.0 North End	48.8	48.8			0.6	0.6	0.6		4.0	2.2
MAPLE ST										
160+00.0 TO 161+85.4	50.0	50.0			0.6	0.6	0.6		4.1	2.3
OAK ST										
179+09.8 TO 180+00.0 South End	23.6	23.6			0.3	0.3	0.3		1.9	1.1
180+00.0 TO 185+23.6 North End	666.2	666.2			8.3	8.3	8.3		55.1	30.0
178+03.4 TO 178+34.0 Drainage Ditch				0.02	1.8	1.8	1.8	0.02	8.0	
WALNUT ST										
200+00.0 TO 205+22.3	535.1	535.1			6.6	6.6	6.6		44.2	24.1
COSTER PL										
220+00.0 TO 224+42.3	458.6	458.6			5.7	5.7	5.7		37.9	20.6
DONALD ST										
240+00.0 TO 244+42.9	347.3	347.3			4.3	4.3	4.3		28.7	15.6
+10.3 TO 11+22.3 Drainage Ditch				0.20	18.0	18.0	18.0	0.20	80.0	
SANDWICH RD										
258+54.9 TO 260+00.0 South End	89.8	89.8			1.1	1.1	1.1		7.4	4.0
REES ST										
260+00.0 TO 261+25.0 North End	22.6	22.6			0.3	0.3	0.3		1.9	1.0
TOTALS										
	9,153.8	9,153.8	1.22	0.55	272.4	272.4	272.4	1.77	1,462.7	411.9

PLOT DATE = Fri, Sep 02 09:15:48 2005
 FILE NAME = C:\prowork\201708\081786.vwr.dgn
 PLOT SCALE = 50.0000 / 1 IN.
 USER NAME = jordanhd