CONTRACT NO 64517

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	1168-4	DEKALB	416	59
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATION	REMARKS	EXISTING SURFACE TYPE	FLARE	REMAINDER	TOTAL AREA	40200800 AGG. SURF CSE TY B 4" TEMP.	35101400 8" AGG BSE CSE TYPE B	35100100 12" AGG BSE CSE TYPE A	40600200 BITUMINOUS (PRIME COAT)	40600300 AGGREGATE (PRIME COAT)	40800040 INCIDENTAL BIT. SURFACE 2"	40800040 INCIDENTAL BIT. SURFACE 3"	42300300 PCC DRIVEWAY PAVEMENT
			SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	TON	SQ YD
MAINLINE													
789 + 27.37	LT FRONTAGE RD.	BIT & AGG	119	795	914	50			0.392	1.37	102.3		
790 + 83.75	LT PE	AGG	71	120	191	44	94		0.273		21.4		
793 + 04.50	LT PE	BIT	80	14	94	22	46		0.134		10.6		
793 + 39.09	RT PE	AGG	93	130	223	51	106		0.319		10.4		
794 + 28.71	LT CE	BIT	85	72	157	36	75		0.225		17.6		
795 + 69.17	RT MB TURNOUT	BIT	15		15	4	11		0.021		1.7		
795 + 74.79	LT CE	BIT	93	47	140	32	68		0.200		15.7		
796 + 47.09	LT PE	BIT	72	7	79	18	40		0.113		8.9		
800 + 47.24	LT CE	BIT	83	128	211	49	100		0.180		14.3		83
801 + 30.00	LT MB TURNOUT	AGG	20		20	5	13		0.029		2.2		
801 + 66.52	LT PE	AGG	36	64	100	23	48		0.090		7.2		36
804 + 04.19	LT PARK EXIT	BIT	0	71	71	17	39		0.102		8.0		
806 + 00.00	LT PARK ENTRANCE	BIT	0	60	60	14	33		0.086		6.8		
812 + 03.70	RT MB TURNOUT	AGG	27		27	7							27
815 + 63.42	LT CE	CON	53		53	13							53
815 + 70.09	RT MB TURNOUT	BIT	27		27	7							27
816 + 47.61	RT PE	AGG	24	6	30	7							30
816 + 56.25	LT PE	AGG	45	31	76	18							76
816 + 95.83	RT PE	CON	30	11	41	10							41
817 + 27.24	LT PE	AGG	25	19	44	11							44
817 + 48.54	RT PE	AGG	25	5	30	7							30
818 + 14.40	RT PE	CON & AGG	24	38	62	15	30		0.054		4.3		24
819 + 98.18	RT PE	BIT	29	24	53	13							53
820 + 53.00	RT PE	CON	25	4	29	7							29
821 + 05.54	LT PE	CON	25		25	6							25
821 + 35.34	RT MB TURNOUT	BIT	27		27	7							27
823 + 59.23	RT CE	CON	34	34	68	16							68
823 + 94.83	LT CE	BIT	41	38	79	18	38		0.050		4.3		41
824 + 32.70	RT CE	AGG	19	9	28	7							28
825 + 38.48	LT CE	BIT	25		25	6							25
825 + 88.75	RT CE	AGG	38		38	9							38
827 + 17.97	RT CE	BIT	19		19	5							19
832 + 37.71	LT CE	BIT	29	89	118	27	56		0.130		10.0		29
832 + 86.50	LT CE	BIT	30		30	7							30
833 + 80.00	RT CE	BIT	45		45	11							45
833 + 85.64	RT PARKING	BIT		1283	1283	5		967	1.830			215.50	
836 + 00.00	RT PARKING	AGG		1003	1003	4		757	1.430			168.50	
836 + 04.29	LT CE	BIT	76	171	247	57	115		0.240		19.2		76
843 + 50.00	RT PARKING LOT	BIT			212		97				23.8		
844 + 00.00	RT CE	BIT	50	77	127	29	60		0.110		8.6		50
844 + 53.22	LT PE	BIT	26	5	31	8							31
844 + 54.00	RT PARKING LOT	BIT			128		59				14.3		
845 + 00.00	RT CE	BIT	33	17	50	12							50
845 + 30.00	RT PARKING LOT	BIT			34		16				3.8		
845 + 45.40	LT PE	BIT	28	13	41	10							41
845 + 58.88	RT CE	BIT	34	16	50	12							50
845 + 78.00	RT PARKING LOT	BIT			17		8				1.9		
846 + 25.47	LT PE	BIT	25	20	45	11	23		0.030		2.2		25
846 + 88.20	RT CE	BIT	38	11	49	12							49
848 + 55.04	RT CE	BIT	84		84	20							84
850 + 01.61	RT CE	BIT	84		84	20							84
850 + 36.10	LT PE	BIT	25	27	52	12	26		0.040		3.0		25
851 + 15.10	LT PE	BIT	25	14	39	9							39
851 + 33.86	RT CE	BIT	67	40	107	25	51		0.060		4.5		67
852 + 07.66	RT CE	BIT	82	74	156	36	73		0.110		8.3		82
853 + 67.78	RT CE	BIT	50	23	73	17							73
854 + 52.70	RT CE	BIT	39	15	54	13							54
857 + 96.85	RT CE	BIT	84	178	262	60	121		0.250		19.9		84
859 + 24.81	RT CE	BIT	84	144	228	52	106		0.210		16.1		84
862 + 75.00	RT CE	BIT	240		240	55	116		0.343		26.9		
865 + 66.86	LT PE	BIT	78	45	123	29	60		0.176		13.8		
SUBTOTALS			2,685	4,992	8,068	1,106	1,728	1,724	7.2	1.4	412	384	1,976

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

ENTRANCE SCHEDULE

PLOT DATE = Fri Sep 02 09:16:07 2005
FILE NAME = P:\pe\work\d07000\d0700ent.dgn
PLOT SCALE = 50.0000 '/ IN.
USER NAME = jordenhd