CONTRACT NO64517

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
577	J168-4	DEKALB	416	60
STA. _____	TO STA. _____			
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

STATION	REMARKS	EXISTING SURFACE TYPE	FLARE	REMAINDER	TOTAL AREA	40200800 AGG. SURF CSE TY B 4" TEMP. ACCESS	35101400 8" AGG BSE CSE TYPE B	35100100 12" AGG BSE CSE TYPE A	40600200 BITUMINOUS (PRIME COAT)	40600300 AGGREGATE (PRIME COAT)	40800040 INCIDENTAL BIT. SURFACE 2" SURF.	40800040 INCIDENTAL BIT. SURFACE 3" SURF.	42300300 PCC DRIVEWAY PAVEMENT
			SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	TON	SQ YD
SIDE ROADS													
RAY ST.													
898 + 76.55 RT	PE	BIT	39	37	76	18	37		0.05		4.10		76
898 + 95.21 LT	PE	BIT	35	12	47	11	23		0.02		1.30		47
899 + 02.80 RT	PE	BIT	23	23	46	11	23		0.03		2.60		46
WALGREN AVE													
65 + 55.40 RT	CE	AGG	31	0	31	8							31
66 + 54.22 LT	PE	AGG	19	11	30	7							30
66 + 74.84 RT	CE	CONC	50	0	50	12							50
67 + 76.62 RT	PE	AGG	18	0	18	5							18
68 + 77.62 RT	CE	CONC	46	48	94	22							94
68 + 88.55 LT	CE	AGG	124	447	571	131							571
SOUTH VIEW													
78 + 69.70 RT	PE	BIT	43	61	104	24	49		0.09		6.80		43
79 + 06.43 LT	PE	BIT	20	15	35	8	18		0.02		1.70		20
NORTH VIEW													
81 + 05.21 LT	PE	BIT	34	10	44	11							44
81 + 24.16 RT	PE	CONC	28	10	38	9							38
SOUTH GARFIELD													
99 + 25.00 LT	PARKING	AGG		98	98	5		74	0.14			16.50	
99 + 32.60 RT	PARKING	AGG		77	77	4		58	0.11			12.90	
NORTH GARFIELD													
100 + 59.29 RT	CE	AGG	52	10	62	15							62
101 + 00.00 LT	PARKING	AGG	66		66	16		51	0.09			11.1	
101 + 10.75 RT	PE	AGG	25	13	38	9							38
NORTH MAY													
120 + 79.60 RT	CE	BIT	67	13	103	24	49		0.03		2.60		80
121 + 00.00 LT	PARKING	BIT	123		123	29		94	0.176			20.7	
121 + 25.00 RT	CE	CONC	29		29	7							29
121 + 44.35 RT	CE	AGG	48	10	58	3							58
SOUTH SYCAMORE													
139 + 15.65 LT	PARKING	BIT		59	59			45	0.084			9.9	
139 + 24.35 RT	PARKING	BIT		116	116			88	0.166			19.5	
NORTH SYCAMORE													
140 + 84.50 LT	CE	BIT	100	37	137	9							137
140 + 84.50 LT	PARKING LOT	BIT		233	233	3	107		0.333		26.10		
141 + 12.00 RT	PARKING	BIT	152		152	35		114	0.217			25.5	
141 + 49.87 LT	PARKING	BIT	25		25	6		20	0.036			4.2	
NORTH MAPLE													
161 + 20.63 LT	PARKING	BIT	195		195	45		147	0.279			32.8	
161 + 25.60 RT	PARKING	BIT	157		157	36		119	0.225			26.4	
161 + 60.39 RT	CE	CONC	11	5	16	4							16
161 + 53.93 LT	CE/ALLEY	CONC	33	0	33	8							33
OAK ST.													
179 + 38.51 LT	CE	AGG	24	0	24	6							24
180 + 89.15 LT	PARKING	BIT	122		122	28		92	0.174			20.5	
180 + 91.01 RT	PE	CONC	22	30	52	12							52
181 + 34.09 LT	CE	BIT	26	19	45	11							45
181 + 61.34 RT	ALLEY	AGG	29	24	53	13							53
181 + 73.48 LT	PE	BIT	17	21	38	9							38
182 + 51.71 RT	PE	CONC	13	5	18	5							18
182 + 89.07 LT	PE	BIT	15	12	27	7							27
183 + 46.14 LT	PE	BIT	16	14	30	7							30
WALNUT													
201 + 42.96 RT	PE/ALLEY	AGG	55	43	98	23							98
201 + 63.01 LT	ALLEY	AGG	24	4	28	7							28
202 + 89.10 RT	PE	BIT	14	8	22	6							22
204 + 14.13 LT	PE	AGG	16	8	24	6							24
204 + 26.69 RT	PE	AGG	13	7	20	5							20
204 + 40.31 LT	PE	AGG	18	9	27	7							27
COSTER PLACE													
221 + 00.13 RT	PE	CONC	24	24	48	11							48
221 + 39.27 LT	PE	AGG	15	11	26	6							26
222 + 11.42 RT	PE	AGG	18	7	25	6							25
222 + 67.35 LT	PE	AGG	24	16	40	10							40
223 + 15.24 RT	PE	BIT	14	3	17	4							17
223 + 34.49 RT	PE	BIT	14	3	17	4							17
DONALD													
240 + 91.43 LT	PE	CONC	22	12	34	8							34
241 + 57.89 RT	PE	AGG	22	11	33	8							33
241 + 75.45 LT	PE	AGG	13	5	18	5							18
242 + 67.98 LT	PE	AGG	14	5	19	5							19
242 + 89.01 RT	PE	BIT	13	6	19	5							19
243 + 06.44 RT	PE	BIT	14	6	20	5							20
243 + 28.53 LT	PE	AGG	18	9	27	7							27
244 + 09.31 RT	PE	AGG	17	9	26	6							26
REES													
260 + 78.64 LT	CE	AGG	45	34	79	18							79
SUBTOTALS			2,304	1,710	4,037	794	306	902	2.3	0.0	45	200	2,515
GRAND TOTALS			4,989	6,702	12,104	1,900	2,034	2,626	9.5	1.4	457	584	4,491

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

ENTRANCE SCHEDULE

PLOT DATE = Fri Sep 02 09:15:23 2005
FILE NAME = C:\p-projects\p201700\cd017006-r.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = jordavid