

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	J16R-4	DEKALB	416	64
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

DESCRIPTION	STATION		550A0340	X0322033	550A2520	550A0410	X0322125	550A2560	550A0430	X0322127	*2001337	54213675	20800150
			12" CLASS A			24" CLASS A			30" CLASS A		30" JACKED IN PLACE	CONC. FLARED END SECTION 30"	TRENCH BACKFILL
			TYPE 2 (feet)	WATERMAIN QUALITY (feet)	GASKET TYPE 2 (feet)	TYPE 2 (feet)	WATERMAIN QUALITY (feet)	GASKET TYPE 2 (feet)	TYPE 2 (feet)	WATERMAIN QUALITY (feet)			
FROM	TO												
EXISTING SS to I 39A	140+63		20										17.12
I 39A to I 38	140+63	140+36				36.0							34.32
I 39 to I 38	141+35	140+36	96.0										86.81
I 38 to MH 10	140+36	829+42					43.0						44.27
MH 10 to I 37	829+42	827+63					175.0						130.25
I 37 to MH 11	827+63	826+05					153.0						24.63
I 35 to I 36	121+14	826+75		66.0									14.90
I 36 to I 34	826+75	826+37			38.0								2.20
I 34 to MH 11	826+37	826+05					32.0						10.37
MH 11 to I 33	826+05	824+40							160.0				11.80
I 33 to MH 12	824+40	823+32							105.0				30.90
I 29 to MH 12	822+96	823+32		37.0									0.98
I 30 to I 31	101+20	101+28	39.0										9.21
I 31 to I 32	101+28	101+00		39.0									10.44
existing SS to MH 12	823+32			20.0									6.82
I 32 to MH 12	100+88	823+32						60.0					21.21
MH 12 to MH 13	823+32	823+32							50.0				13.87
I 45 to I 44	828+50	827+43		103.0									10.29
I 44 to MH 14	827+43	826+19		122.0									14.99
I 43 to I 42	826+73	826+33	38.0										4.99
I 42 to MH 14	826+33	826+19		24.0									8.69
MH 14 to I 41	826+19	824+41		175.0									30.50
I 41 to MH 13	824+41	823+32					107.0						34.66
MH 13 to I 40	823+32	822+95							37.0				21.96
I 40 to MH 16	822+95	97+21							223.0				247.87
MH 16 to MH 16A	97+21	95+80								142.0			
MH 16A to OUTLET	95+80	93+85							213.0			1.0	155.21
TOTAL			193.0	586.0	38.0	36.0	510.0	60.0	300.0	488.0	142.0	1.0	999.3

PLOT DATE = Wed Sep 14 13:56:27 2005  
 PLOT SCALE = 50.0000  
 USER NAME = Jordanhd