

F. APR. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	21T	STEPHENSON	49	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION	REMARKS
63.0	LT Sta. 467+38.0 TO 468+01.0	
63.9	RT Sta. 467+39.0 TO 468+02.0	
64.0	LT Sta. 477+12.0 TO 477+75.0	
64.0	RT Sta. 477+11.0 TO 477+75.0	
64.0	LT Sta. 498+27.0 TO 498+91.0	
65.0	RT Sta. 498+27.0 TO 498+91.0	
383.9	TOTAL	

Z0017100 DOWEL BARS

EACH	LOCATION	LANE WIDTH (ft)	REMARKS
24	LT Sta. 467+70.2	13.0	
24	RT Sta. 467+70.2	13.0	
24	LT Sta. 477+43.7	13.0	
24	RT Sta. 477+43.7	13.0	
24	LT Sta. 498+59.0	13.0	
24	RT Sta. 498+59.0	13.0	
144	TOTAL		

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION	OFFSET (ft)	REMARKS
1	LT Sta. 467+00.0	47	
1	LT Sta. 467+50.0	60	
1	LT Sta. 467+85.0	60	
1	LT Sta. 468+25.0	45	
1	LT Sta. 469+50.0	33	
1	RT Sta. 466+25.0	33	
1	RT Sta. 466+75.0	50	
1	RT Sta. 467+50.0	65	
1	RT Sta. 468+00.0	65	
1	RT Sta. 469+00.0	50	
1	RT Sta. 469+50.0	33	
1	LT Sta. 476+00.0	33	
1	LT Sta. 477+20.0	60	
1	LT Sta. 477+70.0	60	
1	LT Sta. 479+00.0	45	
1	LT Sta. 479+50.0	33	
1	RT Sta. 475+00.0	33	
1	RT Sta. 475+50.0	50	
1	RT Sta. 477+25.0	60	
1	RT Sta. 477+65.0	60	
1	RT Sta. 479+00.0	50	
1	RT Sta. 479+50.0	33	
1	LT Sta. 497+00.0	33	
1	LT Sta. 498+00.0	60	
1	LT Sta. 499+00.0	60	
1	LT Sta. 500+50.0	50	
1	LT Sta. 501+50.0	33	
1	RT Sta. 496+30.3	33	
1	RT Sta. 498+50.0	67	
1	RT Sta. 501+00.0	33	
30	TOTAL		

Z0029001 GRATED CULVERT EXTENSION, NO. 1

EACH	LOCATION	REMARKS
2	Sta. 467+70.2	
2	TOTAL	

Z0029002 GRATED CULVERT EXTENSION, NO. 2

EACH	LOCATION	REMARKS
2	Sta. 477+43.7	
2	TOTAL	

X0301794 INLET STAND PIPE

EACH	LOCATION	OFFSET (ft)	REMARKS
1	LT Sta. 477+45.9	48.0	
1	TOTAL		

X4080020 INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50

TON	LOCATION	THICKNESS (in)	REMARKS
4.5	LT Sta. 467+70.2	4.0	14 x 13 - One Lane - Temporary patch
4.5	RT Sta. 467+70.2	4.0	14 x 13 - One Lane - Temporary patch
11.1	LT Sta. 468+56.6	2.0	CE
5.8	RT Sta. 468+56.6	2.0	MB
4.5	LT Sta. 477+43.7	4.0	14 x 13 - One Lane - Temporary patch
4.5	RT Sta. 477+43.7	4.0	14 x 13 - One Lane - Temporary patch
3.8	LT Sta. 498+59.0	4.0	11.6 x 13 - One Lane - Temporary patch
3.8	RT Sta. 498+59.0	4.0	11.6 x 13 - One Lane - Temporary patch
42.5	TOTAL		

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	REMARKS
2	ENTIRE JOB	
2	TOTAL	

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	PATCH LENGTH (ft)	REMARKS
10.0	Sta. 467+63.2 TO 467+77.2	14	1 yellow skip dash
28.0	Sta. 467+63.2 TO 467+77.2	14	2 white edge lines
10.0	Sta. 477+36.7 TO 477+50.7	14	1 yellow skip dash
28.0	Sta. 477+36.7 TO 477+50.7	14	2 white edge lines
23.2	Sta. 498+53.2 TO 498+64.8	11.6	Double Yellow
23.2	Sta. 498+53.2 TO 498+64.8	11.6	2 white edge lines
122.4	TOTAL		

Z0005400 BREAKER-RUN CRUSHED STONE

TON	LOCATION	REMARKS
66.3	Sta. 467+70.2	10 x 87.3 UNDER CULVERT & END SECTIONS
66.3	Sta. 477+43.7	10 x 87.3 UNDER CULVERT & END SECTIONS
41.5	Sta. 498+59.0	7.6 x 72 UNDER CULVERT & END SECTIONS
174.1	TOTAL	

FILE NAME
 PLOT SCALE
 PLOT DATE
 OPERATOR
 REF
 REF
 REF