

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	29BR-1	DEKALB	25	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

20200100	EARTH EXCAVATION				
	CU YD	LOCATION			
	3.00	IL 23	875+14	-	876+44
	17.00	LT	876+52	-	878+14
	20.00	LT&RT			
		TOTAL			

20400800	FURNISHED EXCAVATION				
	CU YD	LOCATION			
	10.00	IL 23	876+52	-	878+14
	10.00	LT			
		TOTAL			

40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT				
	SQ YD	LOCATION			
	121	IL 23	875+45	-	875+70
	120	LT&RT	877+27	-	877+52
	241	TOTAL			

48101200	AGGREGATE SHOULDERS, TYPE B				
	TONS	LOCATION			
	30	IL 23	875+14	-	876+44
	17	LT	876+52	-	877+82
	25	RT	876+97	-	878+14
	72	TOTAL			

63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A				
	EACH	LOCATION			
	1	IL 23	876+10	-	876+43
	1	LT	875+66	-	875+99
	1	RT	876+97	-	877+30
	4	TOTAL	876+53	-	876+86

63200310	GUARDRAIL REMOVAL				
	FOOT	LOCATION			
	34	IL 23	875+65	-	875+99
	20	RT	875+77	-	875+97
	34	LT	876+09	-	876+43
	34	RT	876+53	-	876+87
	19	LT	876+99	-	877+18
	33	RT	876+97	-	877+30
	174	TOTAL			

63301210	REMOVE AND RE-ERECT STEEL PLAT BEAM GUARD RAIL, TYPE A				
	FOOT	LOCATION			
	25	IL 23	875+40	-	875+65
	12	RT	875+97	-	876+09
	12	LT	876+87	-	876+99
	25	RT	877+30	-	877+56
	75	TOTAL			

63500105	DELINEATORS				
	EACH	LOCATION			
	1	IL 23	875+47		
	1	LT	877+49		
	1	RT	878+06		
	3	TOTAL			

70400100	TEMPORARY CONCRETE BARRIER				
	FOOT	LOCATION			
	588	IL 23	873+54	-	879+41 (STAGE 1)
	588	LT			
		TOTAL			

70400200	RELOCATE TEMPORARY CONCRETE BARRIER				
	FOOT	LOCATION			
	516	IL 23	873+90	-	879+05 (STAGE 2)
	516	RT			
		TOTAL			

78001110	PAINT PAVEMENT MARKING - LINE 4" (TWO COATS)				
	FOOT	LOCATION			
	476	IL 23	871+72	-	881+22 (YELLOW SKIP DASH)
	1000	STA.	874+00	-	879+ (WHITE EDGE LINE)
	800	RT	874+50	-	878+50 (WHITE EDGE LINE)
	2276	LT			
		TOTAL			

78200410	GUARDRAIL MARKERS, TYPE A				
	EACH	LOCATION			
	4	IL 23	875+97	-	876+43
	4	LT	875+40	-	875+99
	4	RT	876+97	-	877+56
	4	LT	876+53	-	877+00
	16	TOTAL			

78201000	TERMINAL MARKER - DIRECT APPLIED				
	EACH	LOCATION			
	1	IL 23	878+06		
	1	LT	877+49		
	2	RT			
		TOTAL			

	PAINT PAVEMENT MARKING REMOVAL				
	FOOT	LOCATION			
	60	IL 23	871+72	-	874+00 STAGE 1
	60	STA	879+00	-	881+22 STAGE 1
	500	RT	874+00	-	879+00 STAGE 1
	400	LT	874+50	-	878+50 STAGE 2
	1020	TOTAL			

X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX D, N50				
	TON	LOCATION			
	32	IL23	875+45	-	876+43
	31	LT&RT	876+53	-	877+52
	63	TOTAL			

X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT				
	EACH	LOCATION			
	1	IL 23 FROM	877+50	-	878+00
		LT			
		TO	876+99	-	877+49
	1	RT			
		TOTAL			

X6330104	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, FLARED				
	EACH	LOCATION			
	1	IL 23 FROM	875+27	-	875+77
		LT			
		TO	875+47	-	875+97
	1	RT	877+18	-	877+68
		TO	877+56	-	878+06
	2	LT			
		TOTAL			

Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3				
	EACH	LOCATION			
	1	IL 23	873+54		STAGE 1
		LT	879+41		STAGE 1
	2	RT			
		TOTAL			

Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3				
	EACH	LOCATION			
	1	IL 23	873+90		STAGE 2
		RT	879+05		STAGE 2
	2	TOTAL			

PLOT DATE = Wed Aug 24 09:38:23 2005
 FILE NAME = c:\p\d\m54\29548A\82548A.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = mgjllj

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. DRAWN BY HORIZ. CHECKED BY DATE