

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
553	119BR-3	OGLE	40	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	X080-2A 80 % FED 20 % STATE	SFTY-3N 80 % FED 20 % STATE
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION STD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION STD. 701201	L SUM	1	1	
70106500	TEMPORARY BRIDGE <sup>TRAFFIC</sup> SIGNALS	EACH	1	1	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	516	516	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	492	492	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	6296	6296	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	40	40	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2	2	
X0323558	BRIDGE JOINT SYSTEM EXPANSION 1 5/8"	FOOT	36	36	
X0712400	TEMPORARY PAVEMENT	SQ YD	57	57	
X4066414	BITUMINOUS CONCRETE SURFACE COARSE, SUPERPAVE, MIC "C", N50	TON	44	44	
Z0002600	BAR SPLICERS	EACH	104	104	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2

\* SPECIALTY ITEMS

PLOT DATE = Fri Sep 02 11:42:20 2005  
 PLOT SCALE = 5/8"=1'-0"  
 USER NAME = megl11j

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. DATE:           HORIZ.
DRAWN BY		CHECKED BY

## SUMMARY OF QUANTITIES