

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
525	STS-2	WINNEBAGO	10	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Y031-1F
90% FED.
10% STATE

PAY CODE	ITEM	UNIT	TOTAL
67100100	MOBILIZATION	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	124
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1179
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	458
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	192
80400105	ELECTRIC SERVICE INSTALLATION, SPECIAL	EACH	1
81300220	JUNCTION BOX STAINLESS STEEL ATTACHED TO STRUCTURE, 6"X6"X4"	EACH	2
81400400	CONCRETE HANDHOLE	EACH	2
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C No. 10	FOOT	1612
85000300	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLTION	L SUM	1
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL No. 14 2 C	FOOT	495
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL No. 14 3 C	FOOT	1027
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL No. 14 5 C	FOOT	3090
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL No. 14 7 C	FOOT	916
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN No. 18 3 PR	FOOT	722
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE No. 6 3 C	FOOT	60
87502460	TRAFFIC SIGNAL POST, GALVANIZED STEEL 12 FT	EACH	2
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6

Y031-1F
90% FED.
10% STATE

PAY CODE	ITEM	UNIT	TOTAL
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3
87900200	DRILL EXISTING HANDHOLE	EACH	12
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	4
88500500	INDUCTION LOOP DETECTOR AMPLIFIER	EACH	6
88600100	DETECTOR LOOP TYPE 1	FOOT	592
89502380	REMOVE EXISTING HANDHOLE	EACH	2
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	2
X0322674	STROBE LIGHT	EACH	2
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, No. 6/1C (GREEN)	FOOT	664
X0324264	SIGNAL HEAD, LED, RETOFIT	EACH	12
X0324885	CONDUIT INSTALLED, 1" NON-METALLIC	FOOT	36
X0324886	CONDUIT INSTALLED, 1 1/4" NON-METALLIC	FOOT	42
X0324887	CONDUIT INSTALLED, 2 1/2" NON-METALLIC	FOOT	29
X0324888	CONDUIT INSTALLED, 4" NON-METALLIC	FOOT	388
X0656300	PAVEMENT REMOVAL AND REPLACEMENT	SQYD	5
X0962500	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1
X8801300	SIGNAL HEAD, POLYCARBONATE, ^{LED} 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1
X8801310	SIGNAL HEAD, POLYCARBONATE, ^{LED} 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4
X0324942	GROUT REMOVAL AND REPLACEMENT	EACH	4

* SPECIALTY ITEMS

PLOT DATE = Thu Sep 15 14:00:11 2005
FILE NAME = C:\projects\97287800\02\8005.dgn
PLOT SCALE = 20.0000 7 / IN.
USER NAME = FJ111

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY