

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
687	*	McDonough / Fulton	58	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* D4 CULV EXT/ REPAIR 2006

SCHEDULE OF QUANTITIES

CODE NO. 20100500

TREE REMOVAL, ACRES	
LOCATION 1	ACRE
Lt Sta. 159+00 to 161+00	0.21
LOCATION 2	
Lt. Sta. 351+60 to 353+25	0.13
Rt. Sta. 352+25 to 353+45	0.03
LOCATION 3	
Lt. Sta. 402+00 to 404+00	0.31
Rt. Sta. 402+80 to 404+25	0.11
TOTAL = 0.79	

CODE NO. 20101700

SUPPLEMENTAL WATERING	
LOCATION 1	UNIT
Lt Sta. 159+00 to 161+00	5
LOCATION 2	
Lt. Sta. 351+60 to 353+25	4
Rt. Sta. 352+25 to 353+45	1
LOCATION 3	
Lt. Sta. 402+00 to 404+00	3
Rt. Sta. 402+80 to 404+25	2
TOTAL = 15	

1 UNIT = 1,000 GAL

CODE NO.	20200100	20400800	21101615
	EARTH EXCAVATION	FURNISHED EXCAVATION	F & P TOPSOIL, 4"
	CU YD	CU YD	SQ YD
LOCATION 1			
STA. 157+00 TO 161+00	451.00	374.00	1,405.00
STA. 161+00 TO 163+00	41.00		121.00
LOCATION 2			
STA. 349+50 TO 353+50	777.00	248.00	1,855.00
LOCATION 3			
STA. 400+50 TO 405+00	2,084.00	1,330.00	3,255.00
TOTAL		3,353	1,952
		1,952	6,636

CODE NO.	28000250	25001700	25100115	25000400	25000500	25000600
	TEMPORARY EROSION CONTROL SEEDING *	SEEDING CLASS 3 (MODIFIED)	MULCH METHOD 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
	POUND	ACRE	ACRE	POUND	POUND	POUND
LOCATION 1						
Lt Sta. 157+00 to Sta.162+50	96	0.38	0.38	34	34	34
Rt Sta. 158+00 to Sta. 161+00	21	0.01	0.01	1	1	1
LOCATION 2						
Lt. Sta. 350+50 to Sta. 353+50	57	0.19	0.19	17	17	17
Rt. Sta. 349+50 to Sta. 353+50	93	0.31	0.31	28	28	28
LOCATION 3						
Lt. Sta. 401+00 to Sta. 404+25	105	0.35	0.35	32	32	32
Rt. Sta. 400+50 to Sta. 404+50	138	0.46	0.46	41	41	41
TOTAL =		510	1.70	1.70	153	153

* 3 Applications

CODE NO. 25101005

HEAVY DUTY EXCELSIOR BLANKET	
	SQ YD
LOCATION 1	
Lt Sta. 159+00 to Sta.160+50	888
Lt Sta. 160+00 to Sta. 161+00	120
LOCATION 2	
Lt. Sta. 351+50 to Sta. 353+25	656
Rt. Sta. 351+50 to Sta. 353+50	1,104
LOCATION 3	
Lt. Sta. 402+25 to Sta. 403+90	980
Rt. Sta. 402+00 to Sta. 404+25	1,549
TOTAL = 5,297	