

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
687	*	McDonough / Fulton	58	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* D4 CULV EXI/ REPAIR 2006

SCHEDULE OF QUANTITIES

CODE NO.28000300

TEMPORARY DITCH CHECK		
LOCATION 1	Spacing	UNIT EACH
Lt. Sta. 158+50 to Sta. 160+00	50 ft	3
Lt. Sta. 160+18 to Sta. 160+92	25 ft	4
Lt. Sta. 159+90, 104 ft		1
LOCATION 2		
Lt. Sta. 351+50 to Sta. 352+32	25 ft	4
Rt. Sta. 351+00 to Sta. 352+43	50 ft	4
Lt. Sta. 352+66, 88 ft		1
Rt. Sta. 352+79, 116 ft		1
LOCATION 3		
Lt. Sta. 402+00 to Sta. 403+00	50 ft	3
Lt. Sta. 403+50 to Sta. 403+80	25 ft	3
Rt. Sta. 401+50 to Sta. 403+55	50 ft	6
Rt. Sta. 403+78 to Sta. 404+25	25 ft	4
Lt. Sta. 403+35, 110 ft		1
Rt. Sta. 403+67, 146 ft		1
TOTAL = 36		

CODE NO.28000400

PERIMETER EROSION BARRIER	
LOCATION 1	UNIT FOOT
Lt. Sta. 157+50 to Sta. 158+00	50
Rt. Sta. 158+50 to Sta. 160+77	156
LOCATION 2	
Lt. Sta. 352+80 to Sta. 353+18	66
Rt. Sta. 352+80 to Sta. 353+50	120
TOTAL = 392	

CODE NO.28100107

STONE RIPRAP, CLASS A4	
LOCATION 1	UNIT SQ YD
Lt. Sta. 160+00	14
LOCATION 2	
Lt. Sta. 352+70	11
Rt. Sta. 352+70	19
LOCATION 3	
Lt. Sta. 403+28	42
Rt. Sta. 403+61	12
TOTAL = 98	

CODE NO.28100125

STONE RIPRAP, CLASS B3	
LOCATION 1	UNIT SQ YD
Lt. Sta. 158+68.70 to Sta. 159+87.85	126
Lt. Sta. 160+00 to Sta. 161+00	119
LOCATION 2	
Lt. Sta. 352+00 to Sta. 352+70	143
Rt. Sta. 350+90 to Sta. 352+70	267
LOCATION 3	
Lt. Sta. 401+75 to Sta. 403+28	184
Lt. Sta. 403+28 to Sta. 403+88	87
Rt. Sta. 401+25 to Sta. 403+61	308
Rt. Sta. 403+61 to Sta. 404+37.5	94
TOTAL = 1,328	

CODE NO.28200200

FILTER FABRIC	
LOCATION 1	UNIT SQ YD
Lt. Sta. 160+00	14
LOCATION 2	
Lt. Sta. 352+70	11
Rt. Sta. 352+70	19
LOCATION 3	
Lt. Sta. 403+28	42
Rt. Sta. 404+61	12
TOTAL = 98	

CODE NO.63000000

STEEL PLATE BEAM GUARD RAIL, TYPE A	
LOCATION 1	UNIT FOOT
Lt. Sta. 158+12.31 to Sta. 161+37.31	325
Rt. Sta. 159+00 to Sta. 160+95	200
LOCATION 2	
Lt. Sta. 351+62.5 to Sta. 353+21.7	162.5
Rt. Sta. 350+50 to Sta. 353+50	300
LOCATION 3	
Lt. Sta. 402+12.75 to Sta. 404+08	200
Rt. Sta. 401+50 to Sta. 404+00	250
TOTAL = 1,437.5	

CODE NO.48202600

BITUMINOUS SHOULDERS SUPERPAVE 8"	
LOCATION 1	UNIT SQ YD
Lt. Sta. 157+30.65 to Sta. 162+22.31	164
Rt. Sta. 158+12.72 to Sta. 160+62.5	83
LOCATION 2	
Lt. Sta. 350+78 to Sta. 352+90	71
Rt. Sta. 349+66 to Sta. 353+12.5	116
LOCATION 3	
Lt. Sta. 401+29 to Sta. 404+45	105
Rt. Sta. 400+66 to Sta. 404+75.71	137
TOTAL = 676	

CODE NO.63100045

TRAFFIC BARRIER TERMINAL, TYPE 2	
LOCATION 1	UNIT EACH
Rt. Sta. 160+95 to Sta. 161+00	1
LOCATION 2	
Lt. Sta. 353+21.7 to Sta. 353+30.5	1
LOCATION 3	
Lt. Sta. 404+08 to Sta. 404+13	1
TOTAL = 3	