

68452

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(55-2)A	MCDONOUGH	55	5
STA.		TO STA.		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES			80% FED 20% STATE C000
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
20100500	TREE REMOVAL, ACRES	ACRE	15
20200100	EARTH EXCAVATION	CU YD	220725
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2590
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	7637
* 25000210	SEEDING, CLASS 2A	ACRE	6.8
* 25000312	SEEDING, CLASS 4A	ACRE	6.2
* 25000322	SEEDING, CLASS 5A	ACRE	6.2
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1170
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1170
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1170
* 25100115	MULCH, METHOD 2	ACRE	13
25100630	EROSION CONTROL BLANKET	SQ YD	33735
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1600
28000300	TEMPORARY DITCH CHECKS	EACH	10
28000400	PERIMETER EROSION BARRIER	FOOT	3025
28000500	INLET AND PIPE PROTECTION	EACH	4
28100109	STONE RIPRAP, CLASS A5	SQ YD	556
28100125	STONE RIPRAP, CLASS B3	SQ YD	1793
28100127	STONE RIPRAP, CLASS B4	SQ YD	387
28300400	AGGREGATE DITCH	TON	1349
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2
54010807	PRECAST CONCRETE BOX CULVERT 8' X 7'	FOOT	456
54213705	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"	EACH	2
54218484	REINFORCED CONCRETE PIPE TEE, 60" PIPE WITH 36" RISER	EACH	1
542A2785	PIPE CULVERTS, CLASS A, TYPE 4 60"	FOOT	973
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	90
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	10
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
X0323260	SEDIMENT BASIN	EACH	1
X0323975	DRAINAGE STRUCTURES NO. 1	EACH	1
X0329891	SILT CURTAIN	SQ YD	266
X0348700	AGGREGATE DITCH CHECK	EACH	3
X2111000	TOPSOIL EXCAVATION	CU YD	12085
X6020015	INLETS, TYPE B, SPECIAL, TYPE 1 FRAME CLOSED LID	EACH	1

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			80% FED 20% STATE C000
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0022800	FENCE REMOVAL	FOOT	520
Z0022800	FILTER FABRIC	SQ YD	4765
Z0036000	OPEN-GRADED DRAINAGE BLANKET	CU YD	6530
Z0054500	ROCK FILL	TON	13388
Z0065100	SETTLEMENT PLATFORMS	EACH	1
Z0076600	TRAINEES	HOURL	1000
* Z0077000	VERTICAL PLASTIC DRAINAGE WICKS	FOOT	80047

* SPECIALTY ITEMS
 O YOBO

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL. ROUTE 336

DATE 8/29/05
 DRAWN BY DLC
 CHECKED BY KMC

SUMMARY OF QUANTITIES (05) 8/17/2005 8:21:27 AM