

SUMMARY OF QUANTITIES

LOCATION OF WORK: F. A. P. 840
US RTE 45 & WINDSOR RD.

CONTRACT NO. 70476				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
804	25B.15	CHAMPAIGN	.19	3

CODE NO.	ITEM	CONSTRUCTION TYPE CODE:	TOTAL UNIT	URBAN QUANTITY	FAP 804	FAP 804	FAP 804
					90% FEDERAL 10% STATE 1000-1A	90% FEDERAL 5% STATE 5% CITY Y031-1F	100% CITY Y030-1E
20200500	EARTH EXCAVATION (WIDENING)		CU YD	160.0	160.0	160.0	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"		SQ YD	483.0	483.0	483.0	
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"		SQ YD	483.0	483.0	483.0	
42001300	PROTECTIVE COAT		SQ YD	554.0	554.0	554.0	
44000500	COMBINATION CURB AND GUTTER REMOVAL		FOOT	546.0	546.0	546.0	
44003100	MEDIAN REMOVAL		SQ FT	1,161.0	1,161.0	1,161.0	
44003800	MEDIAN SURFACE REMOVAL		SQ FT	1,745.0	1,745.0	1,745.0	
60619122	CONCRETE MEDIAN, TYPE SB-6 (DOWELLED)		SQ FT	640.0	640.0	640.0	
67000500	ENGINEERS FIELD OFFICE TYPE B		CAL MO	3.0	3.0	3.0	
67100100	MOBILIZATION		L SUM	1.0	1.0	1.0	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601		L SUM	1.0	1.0	1.0	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701		L SUM	1.0	1.0	1.0	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801		L SUM	1.0	1.0	1.0	
70103815	TRAFFIC CONTROL SURVEILLANCE		CAL DA	9.0	9.0	9.0	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS		SQ FT	125.0	125.0	125.0	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"		FOOT	2,955.0	2,955.0	2,955.0	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"		FOOT	443.0	443.0	443.0	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"		FOOT	223.0	223.0	223.0	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"		FOOT	131.0	131.0	131.0	
* 78008300	POLYUREA PAVEMENT MARKING TYPE II - LETTERS & SYMBOLS		SQ FT	125.0	125.0	125.0	
* 78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"		FOOT	2,955.0	2,955.0	2,955.0	
* 78008330	POLYUREA PAVEMENT MARKING TYPE II - LINE 6"		FOOT	443.0	443.0	443.0	
* 78008350	POLYUREA PAVEMENT MARKING TYPE II - LINE 12"		FOOT	223.0	223.0	223.0	
* 78008370	POLYUREA PAVEMENT MARKING TYPE II - LINE 24"		FOOT	131.0	131.0	131.0	
78300100	PAVEMENT MARKING REMOVAL		SQ FT	125.0	125.0	125.0	
78300105	PAVEMENT MARKING REMOVAL		FOOT	1,577.0	1,577.0	1,577.0	
80500205	SERVICE INSTALLATION, TYPE B (MODIFIED)		EACH	1.0		1.0	
81012300	CONDUIT IN TRENCH, 1" DIA., PVC		FOOT	146.0		146.0	
81012600	CONDUIT IN TRENCH, 2" DIA., PVC		FOOT	36.0		36.0	
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC		FOOT	49.0		49.0	
81030100	CONDUIT SPLICE		EACH	3.0		3.0	
81400100	HANDHOLE		EACH	1.0		1.0	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK		FOOT	85.0		85.0	
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10		FOOT	1,504.0			1,504.0
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET		EACH	1.0		1.0	
86600020	GULFBOX JUNCTION REMOVAL		EACH	1.0		1.0	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C		FOOT	392.0		392.0	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C		FOOT	1,427.0		1,427.0	