

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
804	25B.IS	CHAMPAIGN	19	10

EARTH EXCAVATION WIDENING	STATION	TO	STATION	QUANTITY
	7+27.49		9+64.05	98.6 CU. YD.
	10+43.76		11+80.29	60.6 CU. YD.
			TOTAL	159.2 CU. YD.

COMB. CONC. CURB & GUTTER REM.	STATION	TO	STATION	QUANTITY
	9+46.32		9+62.05	43.4 FT.
	8+29.84		9+40.15	229.4 FT.
	10+47.94		11+80.29	272.9 FT.
			TOTAL	545.7 FT.

MEDIAN REMOVAL	STATION	TO	STATION	QUANTITY
	7+27.49		8+29.84	1133.8 SQ. FT.
	9+57.64		9+62.05	15.9 SQ. FT.
	10+45.76		10+48.03	10.7 SQ. FT.
			TOTAL	1160.4 SQ. FT.

MEDIAN SURFACE REMOVAL	STATION	TO	STATION	QUANTITY
	8+29.84		9+40.15	746.1 SQ. FT.
	9+46.32		9+57.64	65.2 SQ. FT.
	10+48.03		11+80.30	932.9 SQ. FT.
			TOTAL	1744.2 SQ. FT.

SUB-BASE GRAN. MAT. TYPE B, 4"	STATION	TO	STATION	QUANTITY
	7+27.49		9+64.05	298.8 SQ. YD.
	10+43.76		11+80.29	183.8 SQ. YD.
			TOTAL	482.6 SQ. YD.

PCC BASE COURSE WID., 8"	STATION	TO	STATION	QUANTITY
	7+27.49		9+64.05	298.8 SQ. YD.
	10+43.76		11+80.29	183.8 SQ. YD.
			TOTAL	482.6 SQ. YD.

PROTECTIVE COAT	STATION	TO	STATION	QUANTITY
	7+27.49		9+64.05	98.8 SQ. YD.
	10+43.76		11+80.29	183.8 SQ. YD.
	10+62.34		11+80.30	70.1 SQ. YD.
	10+58.99		10+63.24	0.9 SQ. YD.
			TOTAL	553.6 SQ. YD.

CONC. MEDIAN TYPE SB-6 DOW.	STATION	TO	STATION	QUANTITY
	10+62.34		11+80.30	630.9 SQ. FT.
	10+58.99		10+63.24	8.7 SQ. FT.
			TOTAL	639.6 SQ. FT.

ITEM	WEST LEG	EAST LEG	TOTAL
12" DIAGONAL (YELLOW)	111.6	0.0	111.6 FT.
12" DIAGONAL (WHITE)	84.8	26.9	111.7 FT.
4" DOUBLE (YELLOW)	593.1	0.0	593.1 FT.
4" DOUBLE (WHITE)	408.0	321.5	729.5 FT.
4" SOLID (YELLOW)	0.0	254.6	254.6 FT.
4" SOLID (WHITE)	55.0	0.0	55.0 FT.
6" CROSS WALK (WHITE)	244.1	198.5	442.6 FT.
24" STOP BAR (WHITE)	61.8	69.1	130.9 FT.
LEFT TURN ARROW (15.6 SQ. FT. PER ARROW)	62.4	62.4	124.8 SQ. FT.

REMOVE EXISTING CONCRETE FOUNDATION	LOCATION	EACH
	STA. 78+94; 48' LT.	1
	STA. 79+31.5; 66' RT.	1
	STA. 79+46.3; 78' RT.	1
	STA. 79+55.5; 98' RT.	1
	STA. 79+98; 65' RT.	1
	STA. 80+45.5; 80' LT.	1
	STA. 80+96; 53' RT.	1
	TOTAL	7 EACH

GULFBOX JUNCTION REMOVAL	LOCATION	EACH
	STA. 76+03; 57' RT.	1

REMOVE EXISTING HANDHOLE	LOCATION	EACH
	STA. 80+03; 87' RT.	1

HANDHOLE	LOCATION	EACH
	STA. 76+03; 57' RT.	1