

RIPRAP SCHEDULE

LOCATION		STONE RIPRAP CLASS A3	STONE RIPRAP CLASS A4	FILTER FABRIC FOR USE WITH RIPRAP
STATION TO STATION	SIDE	(SQ YD)	(SQ YD)	(SQ YD)
LOCATION 1				
STA 1006+19.29 TO STA 1006+51.24	LT	43		
STA 1006+21.21 TO STA 1006+51.32	RT	43		
STA 1013+48.69 TO STA 1013+79.16	LT	43		
STA 1013+48.69 TO STA 1013+78.92	RT	43		
LOCATION 3				
STA 153+27.56 TO STA 153+45.26	RT	24		
STA 156+12.54 TO STA 156+30.94	LT		20	20
TOTAL		196	20 *	20 *

* NOT A TOTAL QUANTITY

TREE REMOVAL SCHEDULE

LOCATION	TREE REMOVAL (6 TO 15 UNITS)	TREE REMOVAL (ACRES)
STATION TO STATION	(UNIT)	(ACRES)
LOCATION 1		
1006+00.00 TO STA 1013+70.00	10	0.5
LOCATION 2		
STA 223+00.00 TO STA 1159+10.00		0.25
LOCATION 3		
STA 155+80.00 TO STA 157+10.00		0.25
TOTAL		1

STRUCTURE REMOVAL

LOCATION	REMOVAL OF EXISTING STRUCTURE NO. 1	REMOVAL OF EXISTING STRUCTURE NO. 2	REMOVAL OF EXISTING STRUCTURE NO. 3	REMOVAL OF EXISTING STRUCTURE NO. 4
STATION TO STATION	(EACH)	(EACH)	(EACH)	(EACH)
LOCATION 1				
STA 1009+73.88	1			
LOCATION 2				
STA 223+51.00		1		
LOCATION 3				
STA 156+36.00			1	
LOCATION 4				
STA 139+97.20 TO STA 140+49.66				1
TOTAL		1	1	1

RIGHT OF WAY MARKERS SCHEDULE

LOCATION			FURNISHING AND ERECTING RIGHT OF WAY MARKERS (EACH)
STATION	OFFSET (FOOT)	SIDE	(EACH)
LOCATION 2			
STA 219+50.00	45.0	RT	1
STA 219+50.00	55.0	RT	1
STA 222+00.00	55.0	RT	1
STA 223+00.00	80.0	RT	1
STA 1160+00.00	80.0	LT	1
STA 1158+00.00	60.0	LT	1
STA 219+50.00	45.0	LT	1
STA 220+00.00	75.0	LT	1
STA 221+00.00	45.0	LT	1
STA 222+50.00	45.0	LT	1
STA 223+00.00	75.0	LT	1
STA 224+00.00	75.0	LT	1
STA 224+50.00	45.0	LT	1
LOCATION 3			
	35.0	RT	1
STA 153+50.00	55.0	RT	1
STA 155+00.00	55.0	RT	1
STA 156+50.00	80.0	RT	1
STA 158+05.00	60.0	RT	1
STA 158+56.70	70.0	RT	1
STA 160+00.00	70.0	RT	1
STA 160+40.00	35.0	RT	1
STA 155+80.00	60.0	LT	1
STA 156+20.00	100.0	LT	1
STA 156+50.00	100.0	LT	1
STA 157+10.00	60.0	LT	1
TOTAL			25

GUARDRAIL SCHEDULE

LOCATION	STEEL PLATE BEAM GUARDRAIL TYPE A	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 6	STEEL PLATE BEAM GUARDRAIL REMOVAL	GUARDRAIL MARKERS TYPE A	BARRIER WALL MARKERS TYPE B	TERMINAL MARKERS DIRECT APPLIED	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT
STATION TO STATION	SIDE	(FOOT)	(EACH)	(EACH)	(FOOT)	(EACH)	(EACH)	(EACH)
LOCATION 1								
STA 1006+43.01 TO STA 1011+93.08	RT	450.0	2		5		2	
STA 1007+54.93 TO STA 1013.29.95	LT	475.0	2		5		2	
LOCATION 2								
STA 220+26.00 TO STA 1159+84.09	RT	487.5	2	33	5		2	
STA 221+51.00 TO STA 1159+67.09	LT	379.5	2		5		2	
LOCATION 4								
STA 137+60.43 TO STA 142+20.93	RT	187.5		201	4	1	2	2
STA 138+47.93 TO STA 143+08.43	LT	187.5		201	4	1	2	2
TOTAL		2167.0	8	435	28	2	12	4

CONCRETE OUTLET SCHEDULE

LOCATION	CLASS SI CONCRETE (OUTLET)	
STATION TO STATION	SIDE	(CU YD)
LOCATION 1		
STA 1005+62.35 TO STA 1006+21.21	RT	3.8
STA 1005+62.35 TO STA 1006+19.29	LT	3.6
STA 1013+78.92 TO STA 1014+37.64	RT	3.8
STA 1013+79.16 TO STA 1014+37.64	LT	3.7
LOCATION 3		
STA 152+65.86 TO STA 153+27.56	LT	4.0
TOTAL		18.9

PAVEMENT MARKING SCHEDULE

LOCATION	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 5"		WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING - LINE 5"		RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	SKIP DASH YELLOW 4 APPS (FOOT)	SOLID WHITE 3 APPS (FOOT)	SKIP DASH YELLOW 3 APPS (FOOT)		SOLID WHITE (FOOT)	SKIP DASH YELLOW (FOOT)		
STATION TO STATION	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
LOCATION 1								
STA 1006+00.00 TO STA 1014+00.00	304	4800	600	2368	1600	200	10	10
LOCATION 2								
STA 220+00.00 TO STA 1158+50.00	288	4486	570	2219	1495	190	10	10
LOCATION 3								
STA 153+03.50 TO STA 160+00.00	272	4179	540	2072	1393	180	9	9
LOCATION 4								
STA 135+50.00 TO STA 142+90.00	288	4440	570	2199	1480	190	10	10
SUBTOTAL		1152	17905	2280	8858	5968	39	39
TOTAL		1152	20185	8858	6728	760	39	39

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP ROUTE 310 (US 67/IL 267)
 SECTION 81B-1
 MORGAN COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY BANDY
 CHECKED BY STEUART