

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SCHUYLER	139	6

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

\* OTHER ROUTE 1 (WEINBERG KING STATE PARK)  
 \*\* WEIN KING ST PK INT RDS 2

SUMMARY OF QUANTITIES		UNITS	TOTAL QUANTITY	CONSTR. CODE
PAY CODE NUMBER	PAY ITEM DESCRIPTION		100% STATE	I000
40600300	AGGREGATE (PRIME COAT)	TON	18	18
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	67	67
40600990	TEMPORARY RAMP	SQ YD	13.9	13.9
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	425	425
48101200	AGGREGATE SHOULDERS, TYPE B	TON	408	408
50105200	REMOVE EXISTING CULVERTS	EACH	9	9
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	134	134
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	388	388
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	138	138
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6	6
54215550	METAL END SECTIONS 15"	EACH	20	20
54215553	METAL END SECTIONS 18"	EACH	4	4
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	5	5
60100925	PIPE DRAINS 8"	FOOT	772	772

PLOT DATE = 8/30/2005  
 FILE NAME = c:\p1\work\72996\contract 2\p1\htenqdgn  
 PLOT SCALE = 1/8"=1'-0"  
 REFERENCE = #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.  
 HORIZ.  
 DATE

DRAWN BY BDK  
 CHECKED BY JCN