

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SCHUYLER	139	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* OTHER ROUTE 1 (WEINBERG KING STATE PARK)				
** WEIN KING ST PK INT RDS 2				

EARTHWORK SCHEDULE

LOCATION (STATION TO STATION)	EARTH EXCAV. (CU YD)	EMBANK. (CU YD)	EMBANK. X 1.25 (CU YD)	WASTE (BOR.) (CU YD)	ACC. W / (B) (CU YD)	FURN. EXC. (SPL) (CU YD)
<u>R. V. CAMPGROUND ACCESS RD</u>						
STA 90+50.00 TO STA 112+00.00	2570	2499	3124	(553)	(553)	443
STA 112+00.00 TO STA 122+00.00	1899	7841	9801	(7, 902)	(8, 455)	6, 321
STA 122+00.00 TO STA 131+00.00	3959	2549	3186	773	(7, 682)	(618)
SUB-TOTAL =	8429	12889	16111	(7, 682)	(7, 682)	6, 146
<u>HUNTER PARKING AREA NO. 1</u>						
STA 0+00.00 TO STA 2+60.00	58	10	13	46	46	(36)
<u>IL 101</u>						
STA 119+25 TO STA 121+00	13	93	116	(103)	(103)	83
<u>HUNTER ACCESS ROAD</u>						
STA 509+00.00 TO STA 511+25.00	36	23	28	8	8	(6)
STA 518+25.00 TO STA 519+00.00	44	3	4	41	48	(32)
STA 523+50.00 TO STA 524+00.00	33	11	14	19	68	(16)
STA 527+75.00 TO STA 531+00.00	145	584	731	(586)	(518)	469
STA 534+50.00 TO STA 537+50.00	33	6	7	26	(492)	(21)
STA 546+25.00 TO STA 547+00.00	29	7	9	19	(473)	(16)
STA 554+00.00 TO STA 554+75.00	43	10	13	30	(442)	(24)
STA 557+50.00 TO STA 559+25.00	130	14	17	112	(330)	(90)
STA 564+00.00 TO STA 564+75.00	72	23	29	43	(287)	(34)
STA 567+25.00 TO STA 570+00.00	46	54	67	(21)	(308)	17
SUB-TOTAL =	610	735	919	(308)	(308)	247
TOTAL =	9110	13727	17159	(8, 048)	(8, 048)	6, 439

TRENCH BACKFILL SCHEDULE

LOCATION	TRENCH DEPTH (FOOT)	DIA. OF PIPE (INCH)	TRENCH LENGTH (FOOT)	TRENCH BACKFILL (CU YD)
<u>R. V. CAMPGROUND ROAD</u>				
STA 107+25.00	3.0	24	26.0	4.9
STA 112+10.00	4.0	24	24.0	8.0
STA 113+75.00	2.7	24	26.0	3.7
STA 118+08.00	1.8	8	18.0	2.0
STA 122+15.00	2.5	8	18.0	3.2
<u>HUNTER PARKING AREA NO. 1</u>				
STA 1+75.00	2.3	8	24.0	3.8
STA 2+61.00	1.5	15	58.0	3.0
<u>HUNTER ACCESS ROAD</u>				
STA 500+22.00	2.0	18	54.0	4.9
STA 501+08.68	2.0	15	24.0	2.6
STA 509+85.00	2.2	15	18.0	2.4
STA 518+75.00	2.8	15	18.0	3.6
STA 523+75.00	2.3	15	18.0	2.6
STA 529+60.00	3.6	18	18.0	5.3
STA 534+75.00	3.2	15	18.0	4.5
STA 546+75.00	2.8	15	18.0	3.6
STA 554+50.00	2.6	15	18.0	3.2
STA 564+50.00	2.2	15	18.0	2.4
STA 567+50.00	2.2	15	18.0	2.4
TOTAL =				66.3

PLOT DATE = 8/24/2005
 PLOT SCALE = 1/8"=1'-0"
 REFERENCE = REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY BDK
CHECKED BY JCN