CONTRACT NO. 72996

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SCHUYLER	139	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* OTHER ROUTE 1 (WEINBERG KING STATE PARK)
** WEIN KING ST PK INT RDS 2

ESTIMATED QUANTITIES FOR TEMPORARY EROSION CONTROL

PAY ITEMS	UNIT	TOTAL QUANTITY
EARTH EXCAVATION FOR EROSION CONTROL	CU YD	100
TEMPORARY EROSION CONTROL SEEDING	POUND	2000
TEMPORARY DITCH CHECKS	EACH	10
INLET AND PIE PROTECTION	EACH	10
FENCE (EROSION CONTROL)	FOOT	5500
AGGREGATE (EROSION CONTROL)	TON	25

PREPARATION OF BASE AND AGGREGATE BASE REPAIR

LOCATION	PREP. OF BASE	AGG. BASE REAIR	
		EST. AVG. THICK.	EST. QUANT.
	(SQ YD)	(INCH)	(TON)
R. V. CAMPGROUND ROAD			
RT STA 91+50 TO RT STA 92+60	85	1	5
LT STA 93+25 TO LT STA 95+25	156	1	9
RT STA 96+40 TO RT STA 100+05	203	1	12
LT STA 100+50 TO LT STA 103+75	217	1	12
RT STA 104+95 TO RT STA 106+70	117	1	7
LT STA 107+50 TO LT STA 112+70	405	1	23
TOTAL =	1183	-	67

REMOVE EXISTING CULVERTS

LOCATION	QUANTITY (EACH)
R. V. CAMPGROUND ROAD	
STA 107+25.00	1
STA 112+10.00	1
STA 112+75.00	1
STA 113+75.00	1
HUNTER PARKING AREA NO. 1	
STA 1+75.00	1
STA 2+61.00	1
HUNTER ACCESS ROAD	
STA 500+22.00	1
STA 500+84.50	1
STA 509+85.00	1
TOTAL =	9

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.
DATE
DRAWN BY BDK
CHECKED BY JCN

PLOT DATE = 8/24/2005
FILE NAME = c:\projects\ed5982\contract 2 v8\ahtsch.dgn
PLOT SCALE = 1000.4337 ' / IN.
REFERENCE = WHDF8