

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS
-	**	SCHUYLER	139 12
STA.		TO STA.	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT	
* OTHER ROUTE 1 (WEINBERG KING STATE PARK)			
** WEIN KING ST PK INT RDS 2			

TREE REMOVAL SCHEDULE

LOCATION ( STA, OFFSET or STA TO STA)	TREE REMOVAL 6" TO 15" D	TREE REMOVAL > 15" DIA	TREE REMOVAL ( ACRE)
	( UNIT)	( UNIT)	( ACRE)
72.67' RT. 118+86.81	8	-	-
73.91' RT. 118+87.22	6	-	-
19.92' RT. 120+11.05	6	-	-
100.67' RT. 120+37.03	6	-	-
99.36' RT. 120+37.15	8	-	-
40.43' RT. 120+47.63	7	-	-
41.48' RT. 120+49.32	8	-	-
39.18' RT. 120+48.18	6	-	-
<u>RV CAMPGROUND ROAD CONT.</u>			
37.80' RT. 120+49.47	7	-	-
38.29' RT. 120+50.53	5	-	-
1.06' LT. 120+76.63	10	-	-
0.61' RT. 120+75.77	7	-	-
1.34' RT. 120+75.90	6	-	-
0.62' LT. 122+09.09	14	-	-
76.92' LT. 122+26.20	-	24	-
73.98' LT. 122+33.37	-	22	-
70.57' RT. 122+82.30	12	-	-
<u>HUNTER ACCESS ROAD</u>			
28.70' RT. 545+50.67	8	-	-
<u>HUNTER ACCESS ROAD</u> ( STA TO STA)			
21.36' to 20.21' RT. 518+56.74 to 518+91.15	-	-	0.007
19.66' to 18.97' RT. 523+63.16 to 523+87.72	-	-	0.004
18.52' to 17.38' RT. 529+38.14 to 529+97.69	-	-	0.040
14.19' to 15.40' RT. 534+60.59 to 534+87.48	-	-	0.005
14.97' to 16.70' LT. 546+63.27 to 546+89.38	-	-	0.004
14.93' to 16.02' RT. 546+63.66 to 546+86.29	-	-	0.004
SUB-TOTAL	124	46	0.065
TOTAL =	241	46	0.341
+ 20% GROWTH FACTOR (SINCE TIME OF SURVEY)	48.2	9.2	-
TOTAL =	289.2	55.2	0.341

TREE REMOVAL SCHEDULE

LOCATION ( STA, OFFSET or STA TO STA)	TREE REMOVAL 6" TO 15" D	TREE REMOVAL > 15" DIA	TREE REMOVAL ( ACRE)
	( UNIT)	( UNIT)	( ACRE)
<u>RV CAMPGROUND ROAD</u>			
29.54' to 437.6' LT. 106+76.06 to 107+37.20	-	-	0.031
37.76' to 32.66' RT. 106+96.95 to 107+61.67	-	-	0.032
43.94' to 70.94' RT. 111+36.97 to 112+21.36	-	-	0.042
59.64' to 67.73' RT. 123+05.98 to 123+76.55	-	-	0.109
66.68' to 43.76' RT. 124+94.97 to 125+54.77	-	-	0.018
44.19' to 53.23' RT. 125+60.95 to 127+04.61	-	-	0.002
55.48' to 70.34' RT. 127+58.14 to 128+89.10	-	-	0.042
28.62' RT. 112+35.94	8	-	-
26.79' RT. 112+51.15	11	-	-
24.77' RT. 112+72.17	9	-	-
0.53' LT. 114+50.11	10	-	-
19.77' LT. 115+38.39	10	-	-
13.97' RT. 117+43.97	14	-	-
18.01' RT. 117+95.36	10	-	-
65.69' RT. 118+45.04	7	-	-
67.74' RT. 118+45.27	8	-	-
66.65' RT. 118+45.93	8	-	-
73.44' RT. 118+64.39	8	-	-
74.75' RT. 118+65.08	7	-	-
73.47' RT. 118+85.01	7	-	-
SUB-TOTAL	117	-	0.276

NOTE: SEE SPECIAL PROVISION FOR TREE REMOVAL  
TREE REMOVAL WILL BE PAID AS LUMP SUM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT.      DRAWN BY BDK		CHECKED BY JCN
DATE                  HORIZ.		

PLOT DATE = 8/24/2005  
 PLOT SCALE = 1/8" = 100'  
 REFERENCE = #REF#