CONTRACT NO. 72996

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SCHUYLER	139	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* OTHER ROUTE 1 (WEINBERG KING STATE PARK)
** WEIN KING ST PK INT RDS 2

LOCATION - PLACEMENT (STATION TO STATION)	AREA (SQ YD)	STONE DUMPED RIPRAP CL, A-3 (TON)	HEAVY DUTY EXCELS. BLANKET (SQ YD)
R. V. CAMPGROUND ROAD			
LT 98+50 TO LT 106+40 (12' WIDE)	1053	-	1053
RT 99+00 TO RT 106+70 (12' WIDE)	2360	-	2360
LT 106+40 TO LT 107+45	215	107.5	-
RT 106+70 TO RT 107+65	193	96.7	-
LT 107+15 (TOP OF END SECTION)	10	-	10
RT 107+35 (TOP OF END SECTION)	10	-	10
LT 111+95 TO LT 112+30	80	40.0	-
RT 111+95 TO RT 112+30	127	63.3	-
LT 112+10 (TOP OF END SECTION)	10	-	10
RT 112+10 (TOP OF END SECTION)	10	-	10
LT 113+80 (TOP OF END SECTION)	10	-	10
RT 113+65 (TOP OF END SECTION)	10	-	10
RT 113+65 (OUTLET WATER WAY, 12' WIDE)	87	-	87
78.0' RT STA 118+00.00 (AROUND HDWL)	10	-	10
17.0' LT STA 118+10.00 (AROUND INLET)	11	-	11
17.0' LT STA 119+80.00 (AROUND INLET)	11	-	11
17.0' LT STA 120+80.00 (AROUND INLET)	11	-	11
17.0' LT STA 121+50.00 (AROUND INLET)	11	-	11
80.0' RT STA 121+50.00 (AROUND HDWL)	10	-	10
17.0' LT STA 122+25.00 (AROUND INLET)	11	-	11
SUB-TOTAL		307.5	3635

LOCATION - PLACEMENT (STATION TO STATION)	AREA (SQ YD)	STONE DUMPED RIPRAP CL, A-3 (TON)	HEAVY DUTY EXCELS. BLANKET (SQ YD)
24.0' LT STA 122+90.00 (AROUND INLET)	11	-	11
88.0' RT STA 123+75.00 (AROUND HDWL)	10	-	10
17.0' RT STA 124+25.00 (AROUND INLET)	11	-	11
17.0' RT STA 124+75.00 (AROUND INLET)	11	-	11
17.0' LT STA 129+00.00 (AROUND INLET)	11	-	11
21.0' LT STA 129+70.00 (AROUND HDWL)	10	-	10
HUNTER PARKING AREA NO. 1			
STA 1+75.00 (AROUND END SECTIONS)	21	-	30
STA 2+61.00 (AROUND END SECTIONS)	30	-	30
HUNTER ACCESS ROAD			
STA 500+22.00 (AROUND END SECTIONS)	30	-	30
LT 501+08.68 (AROUND END OF CULVERT)	20	-	20
STA 509+85.00 (AROUND END SECTIONS)	25	-	25
STA 518+75.00 (AROUND END SECTIONS)	25	-	25
STA 523+75.00 (AROUND END SECTIONS)	25	-	25
STA 529+60.00 (AROUND END SECTIONS)	25	25	25
STA 534+75.00 (AROUND END SECTIONS)	25	-	25
STA 546+75.00 (AROUND END SECTIONS)	25	-	25
STA 554+50.00 (AROUND END SECTIONS)	25	-	25
STA 564+50.00 (AROUND END SECTIONS)	25	12	25
RT 567+50.00 (AROUND END OF CULVERT)	20	-	20
SUB-TOTAL =		37	394
TOTAL =		345	4029

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.
DATE

DRAWN BY BDK
CHECKED BY JCN

PLOT DATE = 8/24/2005
FILE NAME = c:\projects\ed50182\contract 2 v8\shsch.dgn
PLOT SCALE = 188.4337 ' / IN.
REFERENCE = WEF*