

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SCHUYLER	139	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* OTHER ROUTE 1 (WEINBERG KING STATE PARK)				
** WEIN KING ST PK INT RDS 2				

PAVEMENT MARKING SCHEDULE

LOCATION	PREF.	PREF.	PREF.	PREF.
	PAVT. MK.	PAVT. MK.	PAVT. MK.	PAVT. MK.
	LINE 5" (YELLOW) (FOOT)	LINE 8" (YELLOW) (FOOT)	L & S (WHITE) (SQ FT)	L & S (YELLOW) (SQ FT)
<u>R. V. CAMPGROUND ROAD</u>				
STA 90+70.00 TO STA 131+04.83	675	100	0.0	91.0
PARKING AREA NO. 1	175	50	4.6	0.0
PARKING AREA NO. 2	125	50	4.6	0.0
PARKING AREA NO. 3	125	50	4.6	0.0
PARKING AREA NO. 4	125	50	4.6	0.0
TOTAL =	1225	300	18.4	91.0
NOTE: LETTERS & SYMBOLS SMALL DIRECTIONAL ARROW = 6.5 SQ FT HANDICAP SYMBOL = 4.6 SQ FT				

CONCRETE PARKING BLOCK SCHEDULE

PARKING AREAS	EST. NO. OF NEW (EACH)
<u>R. V. CAMPGROUND ROAD</u>	
PARKING AREA NO. 1	7
PARKING AREA NO. 2	5
PARKING AREA NO. 3	5
PARKING AREA NO. 4	5
RV CAMP PADS	27
TOTAL =	49

PIPE DRAIN & INLET SCHEDULE

LOCATION	PIPE DRAIN 8" (FOOT)	INLET T-A (EACH)	T-8 GRATE (EACH)	CONC HDWL FOR P. D. (EACH)
<u>R. V. CAMPGROUND ROAD</u>				
78.0' RT STA 118+00.00				1
78.0' RT STA 118+00.00 TO 17.0' LT STA 118+10.00	95.0			
17.0' LT STA 118+10.00		1	1	
17.0' LT STA 119+80.00		1	1	
17.0' LT STA 119+80.00 TO 17.0' LT STA 120+80.00	100.0			
17.0' LT STA 120+80.00		1	1	
17.0' LT STA 120+80.00 TO 17.0' LT STA 121+50.00	70.0			
17.0' LT STA 121+50.00		1	1	
17.0' LT STA 121+50.00 TO 78.0' RT STA 121+50.00	97.0			1
80.0' RT STA 121+50.00				
17.0' LT STA 121+50.00 TO 17.0' LT STA 122+25.00	75.0			
17.0' LT STA 122+25.00		1	1	
17.0' LT STA 122+25.00 TO 24.0' LT STA 122+90.00	65.0			
24.0' LT STA 122+90.00		1	1	
88.0' RT STA 123+75.00				1
88.0' RT STA 123+75.00 TO 17.0' RT STA 124+25.00	110.0			
17.0' RT STA 124+25.00		1	1	
17.0' RT STA 124+25.00 TO 17.0' RT STA 124+75.00	58.0			
17.0' RT STA 124+75.00		1	1	
17.0' LT STA 129+00.00		1	1	
17.0' LT STA 129+00.00 TO 21.0' LT STA 129+70.00	70.0			
21.0' LT STA 129+70.00				1
<u>HUNTER PARKING AREA NO. 1</u>				
STA. 1+75.00	32	1	1	1
TOTAL =	772.0	10	10	5

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY BDK  
CHECKED BY JCN