

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
609	***	ST. CLAIR	46	9
STA. TO STA.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
*** SEC. 76-3BR				
CONTRACT NO. 76268				

TEMPORARY PAINT PAVEMENT MARKING LINE 24"

FOOT	LOCATION
12	STA. 134+20 RT (STAGE 1)
12	STA. 142+93 LT (STAGE 1)
12	STA. 134+20 RT (STAGE 2)
12	STA. 142+93 LT (STAGE 2)
48	TOTAL

WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
289	STA. 134+20 LT TO STA. 142+93 LT (EDGE LINE) (STAGE 1)
231	STA. 134+20 RT TO STA. 141+20 RT (EDGE LINE) (STAGE 1)
24	STA. 134+20 RT (STOP BAR) (STAGE 1)
24	STA. 142+93 LT (STOP BAR) (STAGE 1)
196	STA. 137+00 LT TO STA. 142+93 LT (EDGE LINE) (STAGE 2)
242	STA. 135+60 RT TO STA. 142+93 RT (EDGE LINE) (STAGE 2)
24	STA. 134+20 RT (STOP BAR) (STAGE 2)
24	STA. 142+93 LT (STOP BAR) (STAGE 2)
1054	TOTAL

TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
450	STA. 136+40 TO STA. 140+90 (STAGE 1)
450	TOTAL

RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
275	STA. 137+27 TO STA. 140+02 (STAGE 2)
275	TOTAL

SIGN PANEL - TYPE 1

SQ FT	LOCATION
5	STA. 138+14, 23' RT
5	STA. 139+18, 23' LT
10	TOTAL

TELESCOPING STEEL SIGN SUPPORT

FOOT	LOCATION
12	STA. 138+14, 23' RT
12	STA. 139+18, 23' LT
24	TOTAL

THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
365	STA. 134+20 LT TO STA. 137+85 LT (EDGE LINE - WHITE, SOLID)
365	STA. 134+20 RT TO STA. 137+85 RT (EDGE LINE - WHITE, SOLID)
365	STA. 134+20 TO STA. 137+85 (CENTERLINE - YELLOW, SOLID)
92	STA. 134+20 TO STA. 137+85 (CENTERLINE - YELLOW, DASH)
346	STA. 139+47 LT TO STA. 142+93 LT (EDGE LINE - WHITE, SOLID)
346	STA. 139+47 RT TO STA. 142+93 RT (EDGE LINE - WHITE, SOLID)
346	STA. 139+47 TO STA. 142+93 (CENTERLINE - YELLOW, SOLID)
87	STA. 139+47 TO STA. 142+93 (CENTERLINE - YELLOW, DASH)
2312	TOTAL

POLYUREA PAVEMENT MARKING TYPE I - LINE 4"

FOOT	LOCATION
162	STA. 137+85 LT TO STA. 139+47 LT (EDGE LINE - WHITE, SOLID)
162	STA. 137+85 RT TO STA. 139+47 RT (EDGE LINE - WHITE, SOLID)
162	STA. 137+85 TO STA. 139+47 (CENTERLINE - YELLOW, SOLID)
41	STA. 137+85 TO STA. 139+47 (CENTERLINE - YELLOW, DASH)
527	TOTAL

RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION
3	STA. 136+00 TO STA. 137+60
4	STA. 139+20 TO STA. 141+60
7	TOTAL

RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)

EACH	LOCATION
1	STA. 138+40
1	TOTAL

GUARDRAIL MARKERS, TYPE A

EACH	LOCATION
1	STA. 136+69 RT
1	STA. 137+40 LT
1	STA. 137+49 RT
1	STA. 139+80 LT
1	STA. 139+89 RT
5	TOTAL

BARRIER WALL MARKERS, TYPE C

EACH	LOCATION
1	STA. 138+20 LT
1	STA. 138+29 RT
1	STA. 139+00 LT
1	STA. 139+09 RT
4	TOTAL

TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION
1	STA. 136+08.41 RT
1	STA. 136+83.31 LT
1	STA. 140+36.31 LT
1	STA. 140+48.81 RT
4	TOTAL

PAVEMENT MARKING REMOVAL

FOOT	LOCATION
110	STA. 137+00 LT TO STA. 140+34 LT (EDGE LINE - SOLID) (STAGE 1)
40	STA. 136+00 TO STA. 137+00 (CENTERLINE - SOLID & DASH) (STAGE 1)
40	STA. 136+65 RT TO STA. 137+85 (EDGE LINE - SOLID) (STAGE 2)
70	STA. 139+53 RT TO STA. 141+63 RT (EDGE LINE - SOLID) (STAGE 2)
260	TOTAL

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION
8	STA. 135+60 TO STA. 141+90
8	TOTAL

BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70

TON	LOCATION
91	STA. 135+60 TO STA. 137+79.39
94	STA. 139+51.73 TO STA. 141+90
185	TOTAL

LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70

TON	LOCATION
37	STA. 135+60 TO STA. 141+90
37	TOTAL

IMPACT ATTENUATOR REMOVAL

EACH	LOCATION
1	STA. 137+27 LT
1	STA. 140+02 LT
2	TOTAL

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE) TEST LEVEL 2

EACH	LOCATION
1	STA. 136+40 RT
1	STA. 140+90 RT
2	TOTAL

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE) TEST LEVEL 2

EACH	LOCATION
1	STA. 137+27 LT
1	STA. 140+02 LT
2	TOTAL

PLAN	SURVEYED	DATE
NO. _____	BY _____	_____
NOTE BOOK	CHECKED	DATE
NO. _____	BY _____	_____
NO. _____	BY _____	_____
NO. _____	BY _____	_____

PROFILE	SURVEYED	DATE
NO. _____	BY _____	_____
NOTE BOOK	CHECKED	DATE
NO. _____	BY _____	_____
NO. _____	BY _____	_____
NO. _____	BY _____	_____

FILE NAME = \$FILES\$
 PLOT SCALE = \$PLOTSCALE\$
 PLOT DATE = \$PLOTDATE\$
 OPERATOR = \$OPERATOR\$

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP 609 (IL RTE. 163)
SECTION 76-3BR
ST. CLAIR COUNTY

SCALE: VERT.
HORIZ.
DATE 10/15/04

DRAWN BY: SUTHEARD
DESIGNED BY: SUTHEARD
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
PROFESSIONAL ENGINEERING
PROJECT NO. 76-3BR
SECTION 76-3BR
CONTRACT NO. 76268

COMPUTER FILE NO.
SUM163BR
PROJECT 02076
7/22/05-MDS