

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
754	4RS-2, 4BR	CALHOUN	87	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 76269

EARTHWORK SCHEDULE	EARTH EXCAVATION	EARTH EXCAVATION ADJ. FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE	GRANULAR EMBANKMENT (SPECIAL)
STATION to STATION	CU YD	CU YD	CU YD	CU YD	CU YD
03+05.8 05+67.0	30.7	23.0	242.7	-219.7	399.3
06+50.0 12+90.0	72.0	54.0	1133.2	-1079.2	1,829.6
06+68.13 RT CE	67.0	50.2		50.2	
NE QUAD - PARK ST & N. COUNTY RD.	25.0	18.8		18.8	
18.20 19+80.0	12.2	9.1	117.1	-108.0	106.7
PRE-STAGE I CONST.	60.0	45.0		45.0	
STAGE I CONST.	7.1	5.3		5.3	363.6
TOTAL	274.0	205.4	1,493.0	-1,287.6	2,699.2

FURNISHED EXCAVATION = EARTH EXCAVATION ADJ. FOR SHRINKAGE - EMBANKMENT = 1,288 CY

PRE-STAGE I CONSTRUCTION SCHEDULE	PAVED SHOULDER REMOVAL	AGGREGATE BASE COURSE TYPE B, 8"	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE, IL-19.0 N50, 4" DEPTH
STATION to STATION	SQ YD	TON	TON
4+00.0 5+97.5 RT EDGE	43.9	111.7	24.2
6+19.7 8+84.0 RT EDGE	58.7	203.1	45.5
7+58.1 8+84.0 LT EDGE	28.0	64.5	14.4
3+99.0 TEMP. ENTRANCE			13.5
9+16.0 TEMP. ENTRANCE			10.0
TEMP. ENTRANCE FRENCH ST.			4.6
TOTAL	130.6	379.3	112.2

STAGE I CONSTRUCTION SCHEDULE	PAVED SHOULDER REMOVAL	AGGREGATE BASE COURSE TYPE B, 8"	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE, IL-19.0 N50, 4" DEPTH	PAVEMENT REMOVAL	TEMPORARY SHEET PILING	IMPACT ATTENUATORS, TEMPORARY	TEMPORARY CONCRETE BARRIER	PAINT PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 12"
STATION to STATION	SQ YD	TON	TON	SQ YD	SQ FT	EACH	FOOT	SQ FT	FOOT	FOOT	FOOT
2+50.0 4+70.0 CTR								147.0			
4+00.0 6+20.0 RT									220.0		
4+00.0 8+84.0 RT								161.3			
4+26.0 4+85.0 LT	13.1	34.5	7.7						59.0		
4+85.0 CTR						1					
4+85.0 5+67.0 LT			28.6								
4+85.0 5+97.5 CTR				13.0	1466.4						
4+85.0 7+58.1 CTR							273.1			273.1	
6+19.7 7+58.1 CTR				16.0	1582.4						
6+19.7 8+94.0 RT							274.3			153.3	
6+50.0 7+58.1 LT			37.7								
7+58.1 CTR						1					
7+58.1 8+84.0 LT									126.0		
7+73.0 8+84.0 RT									111.0		
7+73.0 9+65.0 CTR								128.0			
8+38.0 8+84.0 CTR									46.0		
7 STOP BARS											90.0
TOTAL	13.1	34.5	74.0	29.0	3048.8	2	547.4	436.3	562.0	426.4	90.0

STAGE II CONSTRUCTION SCHEDULE	IMPACT ATTENUATORS, RELOCATE	RELOCATE TEMPORARY CONCRETE BARRIER	PAINT PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"
STATION to STATION	EACH	FOOT	SQ FT	FOOT	FOOT
3+70.0 4+85.0 LT			32.0		
4+00.0 4+85.0 RT				85.0	
4+25.0 8+38.2 LT				413.2	
4+25.0 4+70.0 LT SIDE STAGE I			15.0		
4+85.0 CTR	1				
4+85.0 7+58.1 CTR		273.1			273.1
7+58.1 CTR	1				
7+58.1 8+84.0 LT			42.0		
7+58.1 8+38.1 RT				80.0	
7+73.0 8+38.1 LT SIDE STAGE I			22.0		
TOTAL	2	273.1	111.0	578.2	273.1

STAGE III CONSTRUCTION SCHEDULE	PAVEMENT REMOVAL
STATION to STATION	SQ YD
4+85.0 5+67.0 LT	145.8
6+50.0 7+58.1 LT	192.2
TOTAL	338.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.S. ROUTE 754 (IL 100/Park St.)
 SECTION 4RS-2, 4BR
 CALHOUN COUNTY
 DRAWN BY DBH
 DATE MAY, 2004 CHECKED BY LLQ