

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
754	4RS-2, 4BR	CALHOUN	87	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 76269

GUARDRAIL SCHEDULE			TRAFFIC BARRIER TERMINAL, TYPE 2 EACH	TRAFFIC BARRIER TERMINAL, TYPE 6 EACH	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT) EACH	STEEL PLATE BEAM GUARDRAIL TYPE A FOOT	TERMINAL MARKER DIRECTLY APPLIED FOOT	GUARDRAIL REMOVAL FOOT	BARRIER WALL MARKERS EACH	GUARDRAIL MARKERS, TYPE A EACH
STATION	to STATION	SIDE								
4+82	5+32	RT.			1		1			1
5+21	5+40	LT.	1 (10' R)			12.5				1
5+32	5+63	RT.		1						1
5+40	5+71	LT.		1						1
5+44	5+98	RT.						50.8		
5+45	5+98	LT.						50.3		
6+20	6+58	LT.						38		
6+46	6+77	RT.		1						1
6+55	6+86	LT.		1						1
6+77	7+27	RT.			1		1			1
6+86	7+36	LT.			1		1			1
PARAPET		RT.							1	
PARAPET		LT.							1	
TOTAL			1	4	3	12.5	3	139.1	2	8

MISCELLANEOUS REMOVAL SCHEDULE			BITUMINOUS SURFACE REMOVAL, 2" SQ YD	PIPE CULVERT REMOVAL FOOT	PLUG EXISTING CULVERTS EACH	TREE REMOVAL UNIT	CONCRETE RETAINING WALL REMOVAL FOOT	DRIVEWAY PAVEMENT REMOVAL SQ YD	PAVEMENT REMOVAL SQ YD	CONCRETE HEADWALL REMOVAL EACH	REMOVING INLETS EACH
STATION	to STATION	SIDE									
0+38.1	3+05.8	LT. & RT.	963								
3+05.8	4+10	LT. & RT.							327.6		
3+10	4+91	RT.						267.4			
3+10	4+32	LT.						270.7			
6+27		13' RT. TO 33' RT.					36				
6+31	7+36	LT.		105							
7+13		29' RT. TO 65' RT.		20							1
7+57	7+98	LT.		41	1						
8+11	8+61	LT.		50						2	
8+83	9+24	LT.		41		30					
9+76		RT.					62				
11+36.4	11+97.7	LT.									
11+70	12+90	LT. & RT.							263.0		
18+20	18+45	LT. & RT.	57								
18+45	19+20	LT. & RT.							157.6		
TOTAL			1020	257	1	30	98	538.1	748.2	2	1

ADJUSTMENT SCHEDULE		RELOCATE SIGN PANEL ASSEMBLY TYPE A EACH
STATION		
8+81	28' LT	1
8+82	21' LT	1
9+23	15' RT	1
10+20	13' RT	1
10+86	20' LT	1
11+99	13' LT	1
TOTAL		6

PAVEMENT MARKING SCHEDULE				THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT	THERMOPLASTIC PAVEMENT MARKING - LINE 12" FOOT	THERMOPLASTIC PAVEMENT MARKING - LINE 24" FOOT	PAINT PAVEMENT MARKING - LINE 4" FOOT	POLYUREA PAVEMENT MARKING TYPE I - LINE 4" FOOT	RAISED REFLECTIVE PAVEMENT MARKERS EACH
STATION	TO STATION	SIDE							
0+53	2+66	LT		213					
0+38.10	2+66	CTR		455.8					4
0+53	2+66	RT		213					
3+22.5	5+39	LT		216.5					
3+22.5	5+37	CTR		429					
3+35.7	5+35	RT		199.3					4
5+39	6+82	LT						143	
5+37	6+80	CTR						286	
5+35	6+78	RT						143	
6+82	8+50	LT		168					
6+80	8+68	CTR		376					
6+78	12+90	RT		612					3
9+43	12+90	RT		347					
8+47	12+90	CTR		832					
18+20	19+66	NO. CO. RD.							6
CROSSWALKS				292					
PARK ST & FRENCH ST					166				
PARK ST & NO. CO. RD.					73				
STOP BARS									
PARK ST. & FRENCH ST.						48			
PARK ST. & NO. CO. RD.						22			
PARKING SPACES ALONG PARK ST.							140		
TOTAL				4353.6	239	70	140	572	17

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.S. ROUTE 754 (IL 100/Park St.)
 SECTION 4RS-2, 4BR
 CALHOUN COUNTY
 DRAWN BY WJS
 CHECKED BY LLO
 DATE MAY, 2004