



F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
754	4RS-2, 4BR	CALHOUN	87	25
STA. 18+45	TO STA. 20+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- CONTRACT NO. 76269  
 7 STA. 18+70.50, 12' RT INLET, TYPE A, TYPE 3 FR & GR INVERT 434.34, FLOW LINE 436.84  
 8 STORM SEWER, TYPE I, WATER MAIN QUALITY PIPE, 12" x 22' SLOPE 0.64%  
 9 STA. 18+70.50, 12' LT INLET, TYPE A, TYPE 3 FR & GR INVERT 434.20, FLOW LINE 436.84  
 10 STORM SEWER, TYPE I, WATER MAIN QUALITY PIPE, 15" x 110' SLOPE 0.47%  
 11 STA. 19+78.70, 18' LT INLET, TYPE B, TYPE 3 FR & GR INVERT 433.70, FLOW LINE 438.98  
 12 STORM SEWER, 12" x 12' CLASS A, TYPE I SLOPE 1.33%  
 13 STA. 19+80, 30' LT INLET, TYPE A, TYPE 8 GRATE INVERT 433.84, FLOW LINE 435.67 INLET AND PIPE PROTECTION  
 14 STORM SEWER, TYPE 2, WATER MAIN QUALITY PIPE, 18" x 40' SLOPE 0.64%  
 15 STA. 20+20.0, 15.8' LT INLET, TYPE B, TYPE 3 FR & GR INVERT 433.45, FLOW LINE 439.36  
 16 STORM SEWER, TYPE 2, WATER MAIN QUALITY PIPE, 18" x 20' SLOPE 0.64%  
 17 STORM SEWER, 18" x 97' CLASS A, TYPE I SLOPE 0.64%  
 18 STA 21+30.7, 12.2' LT 18" PRECAST RCFCES DSFL 432.71

