

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
754	4RS-2, 4BR	CALHOUN	87	58
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 76269

- (c) As soon as reasonable access is available (such as trees cleared) to all locations where water drains away from the project, sediment basins, riprap ditch checks, temporary ditch checks, inlet and pipe protection, and/or erosion control fence shall be installed as called out in this plan and directed by the Engineer.
- (d) Bare and sparsely vegetated ground in highly erodible areas as determined by the Engineer shall be temporarily seeded at the beginning of construction where no construction activities are expected within seven days.
- (e) Immediately after tree removal is completed, areas which are highly erodible as determined by the Engineer, shall be temporarily seeded when no construction activities are expected within seven days.
- (f) At locations where a significant amount of water drains into the construction zone from outside areas (adjacent landowners), erosion control fence, temporary ditch checks, or riprap ditch checks will be utilized to locally divert water, reduce flow rates, and collect outside siltation inside the right-of-way line. Erosion control items will not be allowed to be installed to cause flooding to upstream private property which could cause crop damages or other undesirable conditions.
2. Establishment of these temporary erosion control measures will have additional benefits to the project. Desirable grass seed will become established in these areas and will spread seeds onto the construction site until permanent seeding/mowing and overseeding can be complete.

- (i) The temporary erosion control systems shall be removed as directed by the Engineer after use is no longer needed or no longer functioning. The costs of this removal shall be included in the unit bid price for the temporary erosion control system. No additional compensation will be allowed.

Description of Structural Practices After Final Grading:

1. Temporary erosion control systems shall be left in place with proper maintenance until permanent erosion control is in place and working properly and all proposed turf areas seeded and established with a proper stand.
2. Once permanent erosion control systems as proposed in the plans are functional and established, temporary items shall be removed, cleaned up, and disturbed turf reseeded. Temporary riprap ditch checks will be allowed to remain in place where approved by the Engineer.

Maintenance after Construction:

1. Construction is complete after acceptance by I.D.O.T. Maintenance up to this date will be by the Contractor.

MISCELLANEOUS:

1. Temporary ditch checks shall be located at every 1.5 feet fall/rise in ditch grade.
2. Temporary ditch checks, aggregate uses grading no. 3 - remove at end of construction.
3. Erosion control blanket shall be a minimum of 10 feet wide and centered in ditch.
4. Temporary erosion control seeding seeds all disturbed areas at 100 lbs per acre.
5. Mulch method 1 as applied to temporary seeding shall conform to section 251 of the Standard Specifications. Mulch will not be paid for separately but shall be included in the price for temporary seeding.
6. Construct perimeter erosion control at beginning of construction, remove at end of construction.
7. All erosion control products furnished shall be specifically recommended by the manufacturer for the use specified in the erosion control plan. Prior to the approval and use of the product, the Contractor shall submit to the Engineer a notarized certification by the producer stating the intended use of the product and that the physical properties required for this application are met or exceeded. The Contractor shall provide manufacturer installation procedures to facilitate the Engineer in construction inspection.

Description of Stabilization Practices During Construction:

1. During roadway construction, areas outside the construction slope limits as outlined previous herein shall be protected from damaging effects of construction. The Contractor shall not use this area for staging (except as designated on the plans or directed by the Engineer), parking of vehicles or construction equipment, storage of materials, or other construction related activities.
 - (a) Within the construction limits, are areas which may be susceptible to erosion as determined by the Engineer shall remain undisturbed until full construction is underway to prevent unnecessary soil erosion.
 - (b) Top soil and earth stockpiles shall be temporarily seeded if they are to remain unused for more than fourteen days.
 - (c) As construction proceeds, the Contractor shall institute the following as directed by the Engineer:
 - i. Place temporary erosion control facilities as shown on the plans.
 - ii. Temporary seed erodible bare earth on a weekly basis to minimize the amount of erodible surface area within the construction limits.
 - iii. Construct roadside ditches and provide temporary erosion control systems.
 - iv. Temporary divert water around proposed culvert locations.
 - v. Build necessary embankment at culvert locations and then excavate and place culvert.
 - vi. Continue building up the embankment to the proposed grade while at the same time place permanent erosion control such as riprap ditch lining and conduct final shaping to the slopes
 - (d) The Contractor shall immediately follow major earth moving operations with final grading equipment. After the major earth spread operation has moved to a new location, final grading shall be completed within fourteen days. If grading is not completed within fourteen days, all major earth moving operations will be stopped, as directed by the Engineer, until disturbed areas are final graded and seeded.
 - (e) Excavated areas and embankments shall be permanently seeded when final graded. If not, they shall be temporarily seeded if no construction activity in the area is planned for 7 days.
 - (f) Construction equipment shall be stored and fueled only at designated locations. All necessary measures shall be taken to contain any fuel or pollution run-off in compliance with EPA water quality regulations. Leaking equipment or supplies shall be immediately repaired or removed from the site.
 - (g) The Resident Engineer shall inspect the project daily during activities and weekly or after rains of 1/2 inch or greater or equivalent snowfall and during the winter shutdown period. The project shall additionally be inspected by the Construction Field Engineer on a bi-weekly basis to determine that erosion control efforts are in place and effective and if other erosion control work is necessary.
 - (h) Sediment collected during construction by the various temporary erosion control systems shall be disposed of on the site on a regular basis as directed by the Engineer. The cost of this maintenance will be included in the unit bid price for earth excavation.

EROSION CONTROL SCHEDULE

STATION	LOCATION	RIPRAP CLASS 5 (SQ YD)	FILTER FABRIC (SQ YD)	PERIMETER EROSION BARRIER (FOOT)	TEMPORARY DITCH CHECKS (EACH)	INLET AND PIPE PROTECTION (EACH)
04+85	LT.					1
07+40	C. E. RT.					1
07+50	LT.				1	
08+00	RT.				1	
09+19	RT.			100		
09+68	RT.	37.3	37.3			
19+36	NO. CO. RD. LT.				1	1
19+61	NO. CO. RD. LT.				1	
19+80	NO. CO. RD. LT.					1
BRIDGE		909	909	300		
TO BE LOCATED BY ENGINEER					4	2
TOTAL		946.3	946.3	400	8	6

SEE SEEDING SCHEDULE - NOT INCLUDED IN EROSION CONTROL SCHEDULE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
STORM WATER POLLUTION PREVENTION PLAN
 F.A.S. 754 (IL 100 / Park Street)
 SECTION 4RS-2, 4BR
 CALHOUN COUNTY
 DATE: AUGUST, 2005
 DRAWN BY WJS
 CHECKED BY MTL

PROJECT: FILE: .DGN