

SUMMARY OF QUANTITIES

PROJECT	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
609	76-1BR-2	ST. CLAIR	13	3
STA.		TO STA.		
CONTRACT NO. 76862				

SUMMARY OF QUANTITIES			URBAN 801. FED. 201. STATE TOTAL		CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	QUANTITIES	BRIDGE X080-2A		
				SN 082-0213		
20400800	FURNISHED EXCAVATION	CU YD	50	50		
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5		
25100105	MULCH, METHOD 1	ACRE	0.5	0.5		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100		
40600300	BITUMINOUS MATERIAL (PRIME COAT)	TON	0.2	0.2		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	416	416		
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	11	11		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	6	6		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1		
50102400	CONCRETE REMOVAL	CU YD	18.7	18.7		
50104000	BRIDGE RAIL REMOVAL	FOOT	255	255		
50300225	CONCRETE STRUCTURES	CU YD	18.7	18.7		
50300800	PROTECTIVE COAT	SQ YD	450	450		
50300260	BRIDGE DECK GROOVING	SQ YD	405	405		
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	8	8		
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	4092	4092		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7810	7810		
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	255	255		
51500100	NAME PLATES	EACH	1	1		
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	125	125		
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	25	25		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	619	619		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	18	18		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	500	500		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	7	7		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6		
X0320887	POLYMER CONCRETE	CU FT	2.3	2.3		
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	67	67		
X0324952	DETOUR SIGNING	L. SUM	1	1		
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	20	20		
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	20	20		
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	456	456		
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	38	38		

*SPECIALTY ITEMS

MAPS 4
8/24/2005
C:\projects\ed012005\plan\pl012005.dgn
REF-
REF-