

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	7HBR-1&TVBR	WHITESIDE	146	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT #84883				

**SCHEDULE OF PIPE CULVERT AND INLET QUANTITIES**

- 50104400 CONCRETE HEADWALL REMOVAL
- 542A0229 PIPE CULVERTS, CLASS A, TYPE 1 24"
- 54213447 END SECTIONS 12"
- 54213669 PRECAST REIN. CONC. FLARED END SECTIONS, 24"
- 54248515 CONCRETE COLLAR
- 60100945 PIPE DRAINS 12"
- 60900330 TYPE D INLET BOX, STANDARD 609001
- 61000115 TYPE E INLET BOX, STANDARD 610001
- 60900515 CONCRETE THRUST BLOCK
- 28100107 STONE RIPRAP, CLASS A4
- 28200200 FILTER FABRIC

LOCATION	CONCRETE HEADWALL REMOVAL	PIPE CULVERT CLASS A TYPE 1, 24"	PRECAST REIN. CONC. FLARED END SECTION 24"	INLET BOX TYPE D	INLET BOX TYPE E	PIPE DRAINS 12"	END SECTIONS 12"	CONCRETE THRUST BLOCK	STONE RIP RAP CLASS 4A	FILTER FABRIC	CONCRETE COLLAR
	EACH	FOOT	EACH	EACH	EACH	FOOT	EACH	EACH	SQ YD	SQ YD	EACH
45+12.3					1	64.0	1	1	5.6	5.6	
45+14.1					1	44.0	1	1	5.6	5.6	
49+91.49				1		61.5	1	1	5.6	5.6	
50+13.49				1		61.5	1	1	5.6	5.6	
52+22.17				1		58.5	1	1	5.6	5.6	
52+44.17				1		59.5	1	1	5.6	5.6	
69+61.03	2	6	2								2
<b>TOTAL</b>	<b>2</b>	<b>6</b>	<b>2</b>	<b>4</b>	<b>2</b>	<b>349.0</b>	<b>6</b>	<b>6</b>	<b>33.6</b>	<b>33.6</b>	<b>2</b>

**SCHEDULE OF GUARDRAIL REMOVAL**

63200310 GUARDRAIL REMOVAL	
LOCATION	FEET
44+94.9 TO 46+46.6, LT.	161
44+86.5 TO 46+26.8, RT.	141
48+10.8 TO 50+23.3, LT.	213
47+90.3 TO 50+08.7, RT.	219
52+26.9 TO 53+65.5, LT.	139
52+13.3 TO 53+63.3, RT.	151
<b>TOTAL</b>	<b>1024</b>

**SCHEDULE OF PC CONCRETE PAVING QUANTITIES**

- 35300300 PORTLAND CEMENT CONCRETE BASE COURSE 8"
- 42000411 PORTLAND CEMENT CONCRETE PAVEMENT, 9 1/2" (JOINTED)
- 42001300 PROTECTIVE COAT
- 42001420 BRIDGE APPROACH CONNECTOR (PCC)
- 42100210 CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE, 9 1/2"
- 42100810 PAVEMENT REINFORCEMENT 9 1/2"

LOCATION	PCC BASE COURSE 8"	PCC PAV'T 9 1/2" (JOINTED)	PROTECTIVE COAT	BRIDGE APPROACH CONNECTOR	CRC PCC PAVEMENT 9 1/2"	PAVEMENT REINFORCEMENT 9 1/2"
	SQ YD	SQ YD	SQ YD		SQ YD	SQ YD
NORTH RAMP	990					
SOUTH RAMP	1154					
44+94.88 TO 45+20.00			67		67	67
45+20.00 TO 46+06.03			392	391.9		
48+31.03 TO 49+85.95			706	705.7		
52+49.71 TO 53+08.99			303	303.4		
53+08.99 TO 53+49.71			122		122	122
53+49.71 TO 55+00.00		620	620			
<b>TOTAL</b>	<b>2144</b>	<b>620</b>	<b>2210</b>	<b>1401</b>	<b>189</b>	<b>189</b>

**SCHEDULE OF CURB & GUTTER AND MEDIAN**

- 60608600 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06
- 60618300 CONCRETE MEDIAN SURFACE, 4 IN
- 60622400 CONCRETE MEDIAN, TYPE SM-6.06

LOCATION	COMB. CONC. CURB AND GUTTER TYPE M-6.06	CONCRETE MEDIAN SURFACE, 4 IN	CONC. MEDIAN TYPE SM-6.06
	FOOT	SQ FT	SQ FT
NORTH RAMP	129	695	
SOUTH RAMP	208	1609	
55+52.0 TO 60+32.0			2400
<b>TOTAL</b>	<b>337</b>	<b>2304</b>	<b>2400</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE 08/25/2005

DRAWN BY SWEET  
 CHECKED BY ZELINSKAS