

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	7HBR-1&7VBR	WHITESIDE	146	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT #84883				

63500105 DELINEATORS	
LOCATION	EACH
53+51.9, RT; AT GUARDRAIL	1
54+23.7 LT; AT GUARDRAIL	1
69+61.03 RT; AT CULVERT END	1
69+61.03 LT; AT CULVERT END	1
TOTAL	4

Z0055100 RUMBLE RESURFACING	
LOCATION	SY
62+87.0 TO 63+12.0	30.6
TOTAL	30.6

60624600 CORRUGATED MEDIAN	
LOCATION	SQ FT
54+52.0 TO 55+52.0, 2' TO 5'	350
60+32.0 TO 61+32.0, 5' TO 2'	350
TOTAL	700

SCHEDULE OF SHOULDERS							
48101200	AGGREGATE SHOULDERS, TYPE B						
48202310	BITUMINOUS SHOULDERS SUPERPAVE, 5 1/2"						
48300410	PORTLAND CEMENT CONCRETE SHOULDERS, 9 1/2"						
X4066414	BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX C, N 50						
LOCATION	AGGREGATE SHOULDERS TYPE B, 8"		BITUMINOUS SHOULDERS SUPERPAVE 5 1/2"		PCC SHOULDERS 9 1/2"	BIT. CONC. SURF. COURSE SUPERPAVE MIX C, N 50	
	WIDTH	TON	WIDTH	SQ YD	SQ YD	WIDTH	TON
55+00.0 TO 56+31.2 LT	4'	40					
201+13.4 TO 201+63.2 LT	4'	18					
60+53.7 TO 70+50 LT	5'	390					
70+50 TO 70+95.0 LT	8'	25					
301+50 TO 302+00 LT	4'	18					
58+31.1 TO 70+50 RT	5'	478					
70+50 TO 70+95.0 RT	8'	25					
55+00.0 TO 201+13.4 LT			4'	119		4'	17
201+63.2 TO 61+01.28 LT			4'	202		4'	29
61+01.28 TO 70+50.0 LT			3'	316		3'	45
55+00.0 TO 302+50.0 RT			4'	142		4'	20
301+50.0 TO 59+07.43 RT			4'	124		4'	18
59+07.43 TO 70+50.0 RT			3'	381		3'	54
44+94.88 TO 45+20.00 LT & RT					48		
53+08.99 TO 55+00.00 LT & RT					330		
TOTAL		994		1284		378	183

SCHEDULE OF PAVEMENT MARKING QUANTITIES								
78001110	PAINT PAVEMENT MARKING - LINE 4"							
78001140	PAINT PAVEMENT MARKING - LINE 8"							
78001150	PAINT PAVEMENT MARKING - LINE 12"							
78001180	PAINT PAVEMENT MARKING - LINE 24"							
78100100	RAISED REFLECTIVE PAVEMENT MARKER							
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)							
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL							
LOCATION	PAINT					RAISED		
	WHITE 4" CONT.	YELLOW 4" CONT.	WHITE 8" CONT.	WHITE 12" CONT.	WHITE 24" CONT.	REFLECTIVE PAVEMENT MARKER REMOVAL	REFLECTIVE PAVEMENT MARKER	REFLECTIVE PAVEMENT MARKER (BRIDGE)
	FEET	FEET	FEET	FEET	FEET	EACH	EACH	EACH
44+94 LT TO 201+63 LT	2646							
201+63 RT TO 70+95 LT	2910							
44+94 RT TO 302+00 RT	2656							
302+00 LT TO 70+95 RT	3012							
44+94 TO 70+95		10404				67	41	9
200+61 TO 201+63		408						
300+92 TO 302+00		432						
SOUTH RAMP		386	602	112	58			
NORTH RAMP		264	539	88	62			
TOTAL	11224	11894	1141	200	120	67	41	9

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DATE 08/25/2005

DRAWN BY SWEET
CHECKED BY ZELINSKAS