

FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
729	34Z-4	VERMILION	285	10
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY	URBAN	ROADWAY PCC RECONSTRUCTION US 136 STA 90+268.000 TO STA 91+658.000 N. WALNUT ST. STA 4+009.000 TO STA 4+115.000 80% FEDERAL 20% STATE J000-2A	ROADWAY LIGHTING NON-PARTICIPATING US 136 STA 90+268.000 TO STA 91+658.000 100% DANVILLE Y030-1E	ROADWAY PCC RECONSTRUCTION N WALNUT ST STA 4+009.000 TO STA 4+115.000 100% DANVILLE J000-2A	TRAFFIC SIGNALS WALNUT ST INTERSECTION 80% FEDERAL 10% STATE 10% DANVILLE Y031-1F	TRAFFIC SIGNALS VERMILION INTERSECTION 80% FEDERAL 10% STATE 10% DANVILLE Y031-1F	TRAFFIC SIGNALS HAZEL ST INTERSECTION 80% FEDERAL 10% STATE 10% DANVILLE Y031-1F	TRAFFIC SIGNALS JACKSON ST INTERSECTION 80% FEDERAL 10% STATE 10% DANVILLE Y031-1F	TRAFFIC SIGNALS PARK ST INTERSECTION 80% FEDERAL 13% STATE 7% DANVILLE Y031-1F	TRAFFIC SIGNALS BUCHANAN ST INTERSECTION 80% FEDERAL 10% STATE 10% DANVILLE Y031-1F	SIDEWALK REMOVAL AND RECONSTRUCTION (3' SECTION) VERMILION ST 100% DANVILLE SFTY-1B
M8770730	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 7.92 METER	EACH	1											
M8770735	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 8.53 METER	EACH	1						1					
M8770740	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 9.14 METER	EACH	1							1				
M8770745	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 9.75 METER	EACH	3								1			2
M8770750	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 10.36 METER	EACH	8					2	2	1	1	2		
M8770755	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 10.97 METER	EACH	2					1						1
M8770760	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 11.58 METER	EACH	3					1			1			1
M8780100	CONCRETE FOUNDATION, TYPE A	METER	22.9					3.7	3.6	4.5	2.8	4.6	3.7	
M8780200	CONCRETE FOUNDATION, TYPE D	METER	6.6					1.1	1.1	1.1	1.1	1.1	1.1	
M8780400	CONCRETE FOUNDATION, TYPE E 750MM DIAMETER	METER	9.0						6	3				
MX030399	CONCRETE STEP REMOVAL	SQ M	8		8									
MX032094	COAXIAL CABLE IN CONDUIT	METER	1,337.0					251	225	277	138	226	220	
MX032529	SEGMENTAL CONCRETE BLOCK WALL	SQ M	107.2		107.2									
MX032540	VANE DRAINS	METER	178		178									
MX032783	RETAINING WALL REMOVAL	SQ M	18		18									
MX032867	REMOVE AND RESET ORNAMENTAL FENCE	METER	29.6		29.6									
MX873027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	METER	819.0					160	137	104	124	145	149	
MX878030	CONCRETE FOUNDATION, TYPE E 900MM DIAMETER	METER	58.0					13.6	6.8	6.8	10.4	6.8	13.6	
M2000990	AGGREGATE FOR TEMPORARY ACCESS	M TON	127		127									
M2068200	STEEL CASINGS 750MM	METER	33.0		33.0									
X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	6					1	1	1	1	1	1	
X0322178	REMOVE EXISTING LIGHT POLE FOUNDATION	EACH	52			52								
X0323405	METAL SECURITY GATE	EACH	1		1									
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	112		112									
X8801300	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	6							2	1	3	2	
X8801310	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	26					5	4	3	4	4	6	
X8801350	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	3							1			2	
X8801400	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	11					4	4	1	2			
X8801415	SIGNAL HEAD ,POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3							1		2		
X8801435	SIGNAL HEAD ,POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	3							1			2	
X8801437	SIGNAL HEAD ,POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	11					4	4	1	2			
X8810395	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	24					8	4	2		2	8	
X8810495	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	10						2	3	4	1		
XX005710	PAINT NEW TRAFFIC SIGNAL POST	EACH	16			16								
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1									

\*SPECIALTY ITEMS