

FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
729	342-4	VERMILION	285	21
FED. ROAD DIST. NO.		ILLINOIS/FED. AID PROJECT		

FILLING INLETS

STR NO	STATION	OFFSET M	SIDE	EACH
302	90+381.375	8.29	RT	1
303	90+374.205	13.23	LT	1
304	90+383.963	12.92	LT	1
305	90+387.479	8.98	LT	1
307	90+436.942	8.24	LT	1
309	90+483.300	14.29	LT	1
311	90+493.059	12.37	LT	1
318	90+510.065	9.15	RT	1
319	90+540.356	8.18	LT	1
321	90+574.193	7.92	LT	1
324	90+575.500	8.99	LT	1
326	90+634.536	8.29	LT	1
327	90+661.431	8.22	LT	1
330	90+713.784	8.07	RT	1
331	90+712.079	8.19	LT	1
338	90+847.432	8.38	LT	1
341	90+850.468	15.32	RT	1
344	90+865.019	14.12	LT	1
348	90+931.983	8.91	RT	1
349	90+931.874	8.34	LT	1
356	90+987.431	7.93	RT	1
360	91+033.636	8.06	LT	1
363	91+081.738	8.21	RT	1
367	91+100.692	7.96	LT	1
368	91+133.957	7.98	RT	1
371	91+145.342	10.33	LT	1
372	91+157.792	12.65	LT	1
373	91+201.550	9.43	RT	1
374	91+205.447	13.04	RT	1
380	91+538.834	7.44	LT	1
381	91+540.018	7.89	LT	1
383	91+542.790	9.80	RT	1
388	91+631.258	7.37	LT	1
389	91+628.940	7.55	RT	1
N WALNUT				
315	4+106.567	8.14	LT	1
393	4+105.232	6.36	LT	1
N JACKSON				
337	10+513.325	6.83	LT	1
N WASHINGTON				
350	12+013.171	4.61	LT	1
351	12+012.448	4.63	RT	1
COLLEGE ST				
354	12+987.431	4.43	RT	1
355	12+986.742	4.57	LT	1
TOTAL				41

REMOVING MANHOLES

STR NO	STATION	OFFSET M	SIDE	EACH
308	90+456.204	4.89	LT	1
310	90+489.810	4.98	LT	1
325	90+632.474	7.06	LT	1
333	90+723.339	8.79	LT	1
364	91+085.691	6.80	RT	1
N WALNUT				
313	4+057.412	1.42	RT	1
390	4+106.099	10.39	RT	1
391	4+103.805	0.58	RT	1
TOTAL				8

FILLING MANHOLES

STR NO	STATION	OFFSET M	SIDE	EACH
300	90+319.123	8.82	RT	1
316	90+496.917	8.59	RT	1
322	90+573.635	4.58	LT	1
328	90+662.954	6.51	LT	1
339	90+847.309	7.10	LT	1
340	90+847.946	15.26	RT	1
357	90+991.407	6.69	RT	1
358	90+993.435	6.35	RT	1
369	91+152.242	6.79	RT	1
377	91+221.033	6.28	RT	1
385	91+630.961	9.32	LT	1
387	91+633.114	5.85	RT	1
TOTAL				12

REMOVE AND REPLACE EXISTING MANHOLES

STR NO	STATION	OFFSET M	SIDE	1.8m DIA A-1-C	1.2m DIA A-1-C
168	90+378.000	4.98	LT	1	
92	90+943.000	7.26	LT		1
TOTAL				1	1

REMOVING INLETS

STR NO	STATION	OFFSET M	SIDE	EACH
332	90+716.568	12.87	LT	1
334	90+730.307	12.82	LT	1
342	90+866.192	15.17	RT	1
361	91+038.281	12.61	LT	1
362	91+051.653	13.93	LT	1
365	91+086.645	12.58	RT	1
376	91+219.251	12.27	RT	1
N WALNUT				
312	4+054.908	5.03	LT	1
392	4+101.088	5.48	RT	1
TOTAL				9

PERMANENT SURVEY MARKERS, (SPECIAL)

STATION	EACH
POT 90+429.187	1
POT 90+602.998	1
POT 90+987.078	1
POT 91+213.010	1
PC 91+506.214	1
TOTAL	5

PROTECTIVE COAT

ITEM	AREA SQ M
PCC PAVEMENT 200MM (JOINTED)	5818.0
PCC PAVEMENT 230MM (JOINTED)	25585.0
PCC DRIVEWAY PAVEMENT 200MM	353.0
PCC SIDEWALK 125MM	7685.0
CONCRETE CURB (SPECIAL)	13.4
CONCRETE CURB, TYPE B	6.3
CONCRETE CURB, TYPE B (SPECIAL)	176.5
COMB. CONCRETE C & G B15.30	289.0
COMB. CONCRETE C & G B15.45	28.5
COMB. CONCRETE C & G B15.60	2166.1
COMB. CONCRETE C & G B22.30	7.7
COMB. CONCRETE C & G B22.60	67.8
COMB. CONCRETE C & G, B (SPECIAL)	40.5
CONCRETE MEDIAN SURFACE 100MM	69.0
PAVEMENT PATCHING (SPECIAL)	3407.0
TOTAL	45712.7
USE	45713

FILLING EXISTING VAULTS

STATION	OFFSET M	SIDE	EACH
91+285.500	10.2	LT	1
TOTAL			1

FILLING EXISTING WINDOW WELLS

STATION	OFFSET M	SIDE	EACH
90+741.200	12.3	LT	1
90+755.000	12.3	LT	1
TOTAL			2

PAVEMENT SCHEDULE

STATION TO STATION	SIDE	SUBBASE GRANULAR MATERIAL		P.C.C. PAVEMENT		
		TYPE A 300MM	TYPE B 100MM	200 MM JOINTED	230 MM (JOINTED)	
		SQ M				
90+268.000	90+388.900	LT	1181.4		1088.1	
90+268.000	90+388.900	RT	1186.6		1088.1	
90+388.900	90+956.037	LT	5471.4		5104.2	
90+388.900	90+428.482	RT	464.1		427.5	
90+428.482	90+469.197	RT	550.7		513.0	
90+469.197	90+956.037	RT	4201.0		4341.0	
90+966.115	91+575.417	LT	5891.0		5428.7	
90+966.115	91+556.534	RT	5824.4		5403.8	
91+575.417	91+658.000	LT	695.8		656.6	
91+566.534	91+658.000	RT	820.9		736.3	
CLARK ST	LT & RT		46.0	33.5		
FRANKLIN ST	LT & RT		223.8	190.4		
NORTH WALNUT ST	LT & RT		1497.6	1347.6		
SOUTH WALNUT ST	LT & RT		494.1	453.0		
NORTH VERMILION ST	LT & RT		304.7	261.0		
SOUTH VERMILION ST	LT & RT		247.6	205.0		
NORTH HAZEL ST	LT & RT		175.7	155.8		
SOUTH HAZEL ST	LT & RT		287.1	239.2		
NORTH JACKSON ST	LT & RT		528.6	474.1		
SOUTH JACKSON ST	LT & RT		366.6	322.1		
NORTH WASHINGTON ST	LT & RT		566.2	482.4		
COLLEGE ST	LT & RT		302.7	249.5		
MCDONALD ST	LT & RT		230.3	199.9		
QUINCY ST	LT & RT		189.7	145.2		
LAUHOFF ST	LT & RT		284.4		237.3	
PARK ST	LT & RT		338.7	298.0		
ELIZABETH ST	LT & RT		285.3	235.0		
CORRINE ST	LT & RT		319.2	271.0		
NORTH BUCHANAN ST	LT & RT		634.4	255.3	560.4	
SOUTH BUCHANAN ST	LT & RT		287.9			
TOTALS			26287.2	5818.0	25585.0	
USE			26287	5818	25585	

SCHEDULES OF QUANTITIES