



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 7, 2005

SUBJECT: FAS Route 642 (CH 18)
Project HPD-ACSR-1037(4)
Section 99-00124-01-PV
Coles County
Contract No. 91292
Item 19
November 18, 2005 Letting
Addendum (C)

TO PROSPECTIVE BIDDERS:

To clarify information it is necessary to revise the following:

Plans – Sheet 6, Added Note #4 to bottom of page.

Plans – Sheet 14, Summary of Quantities:

1. Changed Total Quantity for pay item 42000301 "Portland Cement Concrete Pavement 8" (Jointed) and changed quantity in the X571-2A sequence 1 column.
2. Changed Total Quantity and X571-2A sequence 1 column quantity for pay item 42001420, "Bridge Approach Pavement Connector (PCC)".
3. Added pay item 42100100, "Continuously Reinforced Concrete Pavement 8".
4. Added pay item 42100700, "Pavement Reinforcement".
5. Changed Total Quantity and quantity in X571-2A sequence 1 column for pay item 48202600, "Bituminous Shoulders Superpave 8".

Plans – Sheet 15, Revised pay item 550A0030, "Storm Sewers, Class A, Type 1 8" to read pay item 550B0030, "Storm Sewers, Class B, Type 1 8".

Plans – Sheet 26, Added PCC Connector Pavement and CRC Pavement to drawing.

Plans – Sheet 50, Changed 8" Class A Storm Sewer to Class B.

Plans – Sheet 85 Added clarifications to General Note #10.

Plans – Sheet 105 Revised bridge approach pavement connector drawings.

Proposal – Schedule of Prices, Revised and added pay items in response to changes as noted on pages 14 and 15 of plans.

Proposal – Second page of BDE Index, Added check to BDE 80145.

Proposal - Page 6, Added clarification to Embankment special provisions.

Proposal - Page 163a., Added BDE special provision 80145, "Suspension of Slipformed Parapets".

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

November 7, 2005
Page 2

Since the proposal sheets are printed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger, P.E.", with the initials "P.E." written in a smaller font to the right of the signature.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

STATE JOB # - C-95-078-03
 PPS NBR - 5-01100-0300

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 91292

ECMS002 DTGECM03 ECMR003 PAGE 1
 RUN DATE - 11/07/05
 RUN TIME - 203551

COUNTY NAME	CODE	DIST	SECTION NUMBER	PROJECT NUMBER	ROUTE
COLES	029	05	99-00124-01-PV	HPD-ACSR-1037/004/000	FAS 642

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS	CENTS	TOTAL PRICE DOLLARS	CTS
XX002909	CLASS SI CONC	CU YD	2.300	=			
XX004056	MECH ST EARTH RET WL	SQ FT	17,341.000	=			
XX006411	US 45 DETOUR	L SUM	1.000	=			
XX006412	COARSE AGG EMBANK SP	CU YD	3,266.000	=			
XX006413	GRDRL AGG EROS CONTRL	CU YD	243.000	=			
XX006414	PCC BASE COURSE 8 SP	SQ YD	86.000	=			
XZ193300	SURVEY MARKER T1 SPL	EACH	1.000	=			
X0321100	GEOTEX RETAIN WALL	SQ FT	804.000	=			
X0322024	TRENCH DRAIN	EACH	1.000	=			
X3550600	BIT BC SUPER 9	SQ YD	2,219.000	=			
X4066426	BC SC SUPER "D" N70	TON	771.000	=			
X6020073	INLETS TA T8G TEMP	EACH	1.000	=			
X7015005	CHANGEABLE MESSAGE SN	CAL DA	14.000	=			
Z0000990	AGG FOR TEMP ACCESS	TON	150.000	=			
Z0002600	BAR SPLICERS	EACH	80.000	=			

⚠ Addendum 11-2-05, Deleted pay item XX006231, Water

FAS 642
 99-00124-01-PV
 COLES

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 91292

ECMS002 DTGECM03 ECMR003 PAGE 2
 RUN DATE - 11/07/05
 RUN TIME - 203551

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	CTS
				DOLLARS	CENTS		
Z0007601	BLDG REMOV NO 1	L SUM	1.000	=			
Z0007602	BLDG REMOV NO 2	L SUM	1.000	=			
Z0007603	BLDG REMOV NO 3	L SUM	1.000	=			
Z0007604	BLDG REMOV NO 4	L SUM	1.000	=			
Z0030900	INSPECTION WELLS	EACH	16.000	=			
Z0037300	PAVT GROOVING	SQ YD	279.000	=			
Z0038700	PERMNT BENCH MARKS	EACH	2.000	=			
Z0047300	PROTECTIVE SHIELD	SQ YD	473.000	=			
Z0048665	RR PROT LIABILITY INS	L SUM	1.000	=			
Z0049801	R&D FRIABL ASB BLD 1	L SUM	1.000	=			
Z0049904	R&D NON-FR ASB BLD 4	L SUM	1.000	=			
20200100	EARTH EXCAVATION	CU YD	162,453.000	=			
20400800	FURNISHED EXCAV	CU YD	91,921.000	=			
20700400	POROUS GRAN EMB SPEC	CU YD	362.000	=			
20800150	TRENCH BACKFILL	CU YD	163.000	=			

FAS 642
99-00124-01-PV
COLES

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 91292

ECMS002 DTGECM03 ECMR003 PAGE 3
RUN DATE - 11/07/05
RUN TIME - 203551

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
21301052	EXPLOR TRENCH 52	FOOT	5,565.000	=			
25000200	SEEDING CL 2	ACRE	34.100	=			
25000350	SEEDING CL 7	ACRE	34.100	=			
25000400	NITROGEN FERT NUTR	POUND	3,065.000	=			
25000500	PHOSPHORUS FERT NUTR	POUND	3,065.000	=			
25000600	POTASSIUM FERT NUTR	POUND	3,065.000	=			
25000700	AGR GROUND LIMESTONE	TON	68.000	=			
25000750	MOWING	ACRE	34.100	=			
25100115	MULCH METHDD 2	ACRE	68.100	=			
25100630	EROSION CONTR BLANKET	SQ YD	19,743.000	=			
28000250	TEMP EROS CONTR SEED	POUND	3,290.000	=			
28000300	TEMP DITCH CHECKS	EACH	64.000	=			
28000400	PERIMETER EROS BAR	FOOT	4,314.000	=			
28000500	INLET & PIPE PROTECT	EACH	25.000	=			
28100107	STONE RIPRAP CL A4	SQ YD	18.000	=			

FAS 642
99-00124-01-PV
COLES

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 91292

ECMS002 DTGECM03 ECMR003 PAGE 4
RUN DATE - 11/07/05
RUN TIME - 203551

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
28200200	FILTER FABRIC	SQ YD	18.000	=			
30200650	PROCESS MOD SOIL 12	SQ YD	29,761.000	=			
30201500	LIME	TON	670.000	=			
31101200	SUB GRAN MAT B 4	SQ YD	2,502.000	=			
31200100	STAB SUB-BASE 4	SQ YD	29,761.000	=			
35100100	AGG BASE CSE A	TON	137.000	=			
40200800	AGG SURF CSE B	TON	154.000	=			
40600100	BIT MATLS PR CT	GALLON	1,260.000	=			
40600300	AGG PR CT	TON	18.000	=			
40600980	BIT SURF REM BUTT JT	SQ YD	160.000	=			
40600990	TEMPORARY RAMP	SQ YD	112.000	=			
40800010	BIT MATLS PR CT	GALLON	133.000	=			
40800040	INCIDENTAL BIT SURF	TON	152.000	=			
42000301	PCC PVT 8 JOINTED	SQ YD	27,578.000	=			
42001165	BR APPR PAVT	SQ YD	138.000	=			

△* Addendum 10-31-05
 △* Addendum 11-7-05, quantity change
 △* Addendum

FAS 642
99-00124-01-PV
COLES

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 91292

ECMS002 DTGECM03 ECMR003 PAGE 5
RUN DATE - 11/07/05
RUN TIME - 203551

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE
				DOLLARS	CENTS	
42001300	PROTECTIVE COAT	SQ YD	28,080.000	=		
42001400	BR APPROACH PAVT SPL	SQ YD	141.000	=		
42001420	BR APPR PVT CON (PCC)	SQ YD	61.000	=		
42100100	CONT REINF PCC PVT 8	SQ YD	60.000	=		
42100700	PAVT REINFORCEMENT 8	SQ YD	60.000	=		
42300400	PCC DRIVEWAY PAVT 8	SQ YD	5,527.000	=		
44000100	PAVEMENT REM	SQ YD	10,615.000	=		
44000200	DRIVE PAVEMENT REM	SQ YD	4,707.000	=		
44000500	COMB CURB GUTTER REM	FOOT	1,458.000	=		
44002500	GUT OUTLET REM	EACH	2.000	=		
44002805	ISLAND REMOVAL	SQ FT	415.000	=		
44003100	MEDIAN REMOVAL	SQ FT	992.000	=		
44004250	PAVED SHLD REMOVAL	SQ YD	130.000	=		
44004300	PAVT BREAKING	SQ YD	2,822.000	=		
44100300	PAVT REPLACE SPL	SQ YD	86.000	=		

3* Addendum 11-7-05

FAS 642
99-00124-01-PV
COLES

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 91292

ECMS002 DTGECM03 ECMR003 PAGE 6
RUN DATE - 11/07/05
RUN TIME - 203551

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	CTS
				DOLLARS	CENTS		
44200089	PAVT PATCH T1 8	SQ YD	36.000				
44200094	PAVT PATCH T2 8	SQ YD	15.000				
44300200	STRIP REF CR CON TR	FOOT	2,730.000				
48101500	AGGREGATE SHLDS B 6	SQ YD	4,564.000				
48201000	BIT SHOULDERS	TON	47.000				
48202600	BIT SHLD SUPER 8	SQ YD	7,940.000				
48300300	PCC SHOULDERS 8	SQ YD	142.000				
50104400	CONC HDWL REM	EACH	2.000				
50105220	PIPE CULVERT REMOV	FOOT	1,261.000				
50200100	STRUCTURE EXCAVATION	CU YD	618.000				
50300100	FLOOR DRAINS	EACH	8.000				
50300225	CONC STRUCT	CU YD	767.000				
50300255	CONC SUP-STR	CU YD	486.800				
50300260	BR DECK GROOVING	SQ YD	1,337.000				
50300300	PROTECTIVE COAT	SQ YD	1,672.000				

3* Addendum 11-7-05

FAS 642
99-00124-01-PV
COLES

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 91292

ECMS002 DTGECM03 ECMR003 PAGE 7
RUN DATE - 11/07/05
RUN TIME - 203551

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	2,400.000				
50800105	REINFORCEMENT BARS	POUND	250.000				
50800205	REINF BARS, EPOXY CTD	POUND	202,620.000				
51100100	SLOPE WALL 4	SQ YD	825.000				
51201900	FUR STL PILE HP14X89	FOOT	2,687.000				
51202700	DRIVE STL PILE	FOOT	2,687.000				
51203900	TEST PILE ST HP14X89	EACH	2.000				
51500100	NAME PLATES	EACH	1.000				
54200430	P CUL 1 RCCP 15	FOOT	8.000				
54200433	P CUL 1 RCCP 18	FOOT	144.000				
54200439	P CUL 1 RCCP 24	FOOT	296.000				
54200451	P CUL 1 RCCP 36	FOOT	80.000				
54201291	P CUL 2 RCCP 36	FOOT	98.000				
54204861	P CUL 7 RCCP 36	FOOT	160.000				

FAS 642
99-00124-01-PV
COLES

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 91292

ECMS002 DTGECM03 ECMR003 PAGE 8
RUN DATE - 11/07/05
RUN TIME - 203551

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
54207171	P CUL 1 RC-E EQRS 36	FOOT	292.000				
54207783	P CUL 1 CS/A EQ RS 18	FOOT	43.000				
54207789	P CUL 1 CS/A EQ RS 24	FOOT	283.000				
54207801	P CUL 1 CS/A EQ RS 36	FOOT	55.000				
5421D012	P CUL CL D 1 12 TEMP	FOOT	222.000				
5421D024	P CUL CL D 1 24 TEMP	FOOT	70.000				
54213657	PRC FLAR END SEC 12	EACH	1.000				
54213660	PRC FLAR END SEC 15	EACH	1.000				
54213663	PRC FLAR END SEC 18	EACH	6.000				
54213669	PRC FLAR END SEC 24	EACH	5.000				
54213681	PRC FLAR END SEC 36	EACH	8.000				
54214731	PRCF END S EL EQRS 36	EACH	8.000				
54215547	MET END SEC 12	EACH	17.000				
54215763	MET END SEC EQV RS 18	EACH	2.000				
54215769	MET END SEC EQV RS 24	EACH	12.000				

FAS 642
99-00124-01-PV
COLES

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 91292

ECMS002 DTGECM03 ECRM003 PAGE 9
RUN DATE - 11/07/05
RUN TIME - 203551

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
54215781	MET END SEC EQV RS 36	EACH	2.000				
550A0050	STORM SEW CL A 1 12	FOOT	486.000				
550A0120	STORM SEW CL A 1 24	FOOT	233.000				
550A0410	STORM SEW CL A 2 24	FOOT	317.000				
550B0030	STORM SEW CL B 1 8	FOOT	71.000				
550B0160	STORM SEW CL B 1 36	FOOT	1,144.000				
55100500	STORM SEWER REM 12	FOOT	197.000				
60100945	PIPE DRAINS 12	FOOT	1,032.000				
60218500	MAN TA 4 DIA T3F&G	EACH	1.000				
60221100	MAN TA 5 DIA T1F CL	EACH	3.000				
60221700	MAN TA 5 DIA T8G	EACH	2.000				
60223100	MAN TA SPL 5D T1F CL	EACH	1.000				
60235700	INLETS TA T3F&G	EACH	2.000				
60500060	REMOV INLETS	EACH	7.000				
60600095	CLASS SI CONC OUTLET	CU YD	4.000				

FAS 642
99-00124-01-PV
COLES

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 91292

ECMS002 DTGECM03 ECMR003 PAGE 10
RUN DATE - 11/07/05
RUN TIME - 203551

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE
				DOLLARS	CENTS	
60603500	COMB CC&G TB6.06	FOOT	11.000	=		
60603800	COMB CC&G TB6.12	FOOT	1,044.000	=		
60605000	COMB CC&G TB6.24	FOOT	453.000	=		
60605500	COMB CC&G TB6.24 VWGF	FOOT	18.000	=		
60614600	PAVED DITCH SPEC	FOOT	50.000	=		
60618300	CONC MEDIAN SURF 4	SQ FT	89.000	=		
60900515	CONC THRUST BLOCKS	EACH	18.000	=		
61000115	TY E INLET BOX 610001	EACH	14.000	=		
61000120	TE INLT BX 610001 SPL	EACH	9.000	=		
61100605	MISC CONCRETE	CU YD	16.000	=		
61101005	STORM SEW PROT A 4	FOOT	120.000	=		
61101007	STORM SEW PROT A 6	FOOT	120.000	=		
61101009	STORM SEW PROT A 8	FOOT	120.000	=		
61101011	STORM SEW PROT A 10	FOOT	120.000	=		
61101013	STORM SEW PROT A 12	FOOT	120.000	=		

FAS 642
99-00124-01-PV
COLES

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 91292

ECMS002 DTGECM03 EGMRR003 PAGE 11
RUN DATE - 11/07/05
RUN TIME - 203551

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
61101020	STORM SEW PROT A 18	FOOT	120.000	=			
61101026	STORM SEW PROT A 24	FOOT	120.000	=			
61133100	FLD TILE JUN VAULT 2D	EACH	8.000	=			
63000000	SPBGR TY A	FOOT	3,413.000	=			
63100085	TRAF BAR TERM T6	EACH	4.000	=			
63100169	TR BAR TRM T1 SPL FLR	EACH	4.000	=			
63500105	DELINEATORS	EACH	32.000	=			
66101120	BIT SHLD CURB	FOOT	3,459.000	=			
66600105	FUR ERECT ROW MARKERS	EACH	46.000	=			
67000400	ENGR FIELD OFFICE A	CAL MO	16.000	=			
67000600	ENGR FIELD LAB	CAL MO	16.000	=			
67100100	MOBILIZATION	L SUM	1.000	=			
70100460	TRAF CONT-PROT 701306	L SUM	1.000	=			
70100500	TRAF CONT-PROT 701326	L SUM	1.000	=			
70300100	SHORT-TERM PAVT MKING	FOOT	500.000	=			

FAS 642
99-00124-01-PV
COLES

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 91292

ECMS002 DTGECM03 ECMR003 PAGE 12
RUN DATE - 11/07/05
RUN TIME - 203551

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	CTS
				DOLLARS	CENTS		
70300220	TEMP PVT MK LINE 4	FOOT	4,925.000	=			
70301000	WORK ZONE PAVT MK REM	SQ FT	1,808.000	=			
70400100	TEMP CONC BARRIER	FOOT	165.000	=			
72000100	SIGN PANEL T1	SQ FT	149.000	=			
72000200	SIGN PANEL T2	SQ FT	67.000	=			
72800100	TELES STL SIN SUPPORT	FOOT	550.000	=			
78000100	THPL PVT MK LTR & SYM	SQ FT	156.000	=			
78000200	THPL PVT MK LINE 4	FOOT	12,791.000	=			
78000600	THPL PVT MK LINE 12	FOOT	263.000	=			
78001110	PAINT PVT MK LINE 4	FOOT	11,755.000	=			
78005100	EPOXY PVT MK LTR-SYM	SQ FT	437.000	=			
78005110	EPOXY PVT MK LINE 4	FOOT	24,030.000	=			
78005150	EPOXY PVT MK LINE 12	FOOT	1,011.000	=			
78005180	EPOXY PVT MK LINE 24	FOOT	63.000	=			
78100100	RAISED REFL PAVT MKR	EACH	156.000	=			

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
78200100	MONODIR PRIS BAR REFL	EACH	8.000 X	=			
78200300	PRISMATIC CURB REFL	EACH	6.000 X	=			
78200410	GUARDRAIL MKR TYPE A	EACH	15.000 X	=			
78201000	TERMINAL MARKER - DA	EACH	4.000 X	=			
78300100	PAVT MARKING REMOVAL	SQ FT	2,515.000 X	=			
78300200	RAISED REF PVT MK REM	EACH	156.000 X	=			
TOTAL				\$			

NOTE:

1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

File Name	Pg.#		Special Provision Title	Effective	Revised
80155	116	X	Payrolls and Payroll Records	Aug. 10, 2005	
80130	118	X	Personal Protective Equipment	July 1, 2004	
80134			Plastic Blockouts for Guardrail	Nov. 1, 2004	
80073	119	X	Polymer Modified Emulsified Asphalt	Nov. 1, 2002	
80119			Polyurea Pavement Marking	April 1, 2004	
80124	120	X	Portable Changeable Message Signs	Nov. 1, 1993	April 2, 2004
* 80139	121	X	Portland Cement	Jan. 1, 2005	Nov. 1, 2005
80083	122	X	Portland Cement Concrete	Nov. 1, 2002	
80036			Portland Cement Concrete Patching	Jan. 1, 2001	Jan. 1, 2004
419	123	X	Precast Concrete Products	July 1, 1999	Nov. 1, 2004
80120			Precast, Prestressed Concrete Members	April 1, 2004	
80084			Preformed Recycled Rubber Joint Filler	Nov. 1, 2002	
80015			Public Convenience and Safety	Jan. 1, 2000	
80121			PVC Pipeliner	April 1, 2004	April 1, 2005
80122			Railroad, Full-Actuated Controller and Cabinet	April 1, 2004	
34261	124	X	Railroad Protective Liability Insurance	Dec. 1, 1986	May 1, 1988
80105			Raised Reflective Pavement Markers (Bridge)	Aug. 1, 2003	
80011	125	X	RAP for Use in Bituminous Concrete Mixtures	Jan. 1, 2000	April 1, 2002
* 80151	129	X	Reinforcement Bars	Nov. 1, 2005	
80032			Remove and Re-Erect Steel Plate Beam Guardrail and Traffic Barrier Terminals	Jan. 1, 2001	Jan. 1, 2005
80085			Sealing Abandoned Water Wells	Nov. 1, 2002	
80131			Seeding and Sodding	July 1, 2004	Aug. 1, 2005
* 80152			Self-Consolidating Concrete for Cast-In-Place Construction	Nov. 1, 2005	
* 80132	131	X	Self-Consolidating Concrete for Precast Products	July 1, 2004	Nov. 1, 2005
80096			Shoulder Rumble Strips	Jan. 1, 2003	
80140			Shoulder Stabilization at Guardrail	Jan. 1, 2005	
80135	133	X	Soil Modification	Nov. 1, 2004	April 1, 2005
80070	139	X	Stabilized Subbase and Bituminous Shoulders Superpave	April 1, 2002	Aug. 1, 2005
80127	145	X	Steel Cost Adjustment	April 2, 2004	July 1, 2004
* 80153	149	X	Steel Plate Beam Guardrail	Nov. 1, 2005	
80143	150	X	Subcontractor Mobilization Payments	April 2, 2005	
80086	151	X	Subgrade Preparation	Nov. 1, 2002	
80136			Superpave Bituminous Concrete Mixture IL-4.75	Nov. 1, 2004	
80010	152	X	Superpave Bituminous Concrete Mixtures	Jan. 1, 2000	April 1, 2004
80039	159	X	Superpave Bituminous Concrete Mixtures (Low ESAL)	Jan. 1, 2001	April 1, 2004
* 80075			Surface Testing of Pavements	April 1, 2002	Nov. 1, 2005
3 80145	163a	X	Suspension of Slipformed Parapets	June 11, 2004	
80092	164	X	Temporary Concrete Barrier	Oct. 1, 2002	Nov. 1, 2003
80087	167	X	Temporary Erosion Control	Nov. 1, 2002	
80008			Temporary Module Glare Screen System	Jan. 1, 2000	
80106			Temporary Portable Bridge Traffic Signals	Aug. 1, 2003	
80098	169	X	Traffic Barrier Terminals	Jan. 1, 2003	
57291	170	X	Traffic Control Deficiency Deduction	April 1, 1992	Jan. 1, 2005
20338			Training Special Provisions	Oct. 15, 1975	
80107			Transient Voltage Surge Suppression	Aug. 1, 2003	
80123	171	X	Truck Bed Release Agent	April 1, 2004	
* 80154			Turf Reinforcement Mat	Nov. 1, 2005	
80149	172	X	Variable Spaced Tining	Aug. 1, 2005	
80048	173	X	Weight Control Deficiency Deduction	April 1, 2001	Aug. 1, 2002
80090			Work Zone Public Information Signs	Sept. 1, 2002	Jan. 1, 2005
80125			Work Zone Speed Limit Signs	April 2, 2004	April 15, 2004
* 80126			Work Zone Traffic Control	April 2, 2004	Nov. 1, 2005
80097	175	X	Work Zone Traffic Control Devices	Jan. 1, 2003	Nov. 1, 2004
80071	177	X	Working Days	Jan. 1, 2002	

3 Addendum 11-7-05

PCC BASE COURSE, 8" (SPECIAL)

This work shall consist of constructing 8 inches of PCC base course in holes left from median removal and island removal at the C.H. 18 and US 45 intersection as shown on the plans in order to facilitate temporary two way traffic on the north portion of the existing C.H. 18 pavement. The work shall include any earth excavation required and shall also include construction of 4 inches of subbase granular material. This work shall be paid for at the contract unit price per square yard for PCC BASE COURSE, 8" (SPECIAL) and no additional compensation will be allowed.

EMBANKMENTS OVER TEN FEET HIGH

Embankments shall be constructed to the lines and dimensions shown on the plan and profile sheets in accordance with Section 205 of the Standard Specifications. In addition, embankments over ten feet high shall be placed as early as possible (~~no later than fall~~) to the lines and elevations shown on the plans and allowed to settle ~~over the winter months~~ before beginning paving operations. Locations for this special embankment placement are from station 109+50 to station 135+50 of C.H. 18. Any settlement that occurs will be corrected ~~in the spring~~. This work will be included in the contract unit prices for the various excavation items and no further compensation will be allowed. The waiting period will not be cause for extension of the contract time. * 3

EMBANKMENT UNDER MSE RETAINING WALL SYSTEM

Embankment placed as foundation material under the MSE System from station 123+83.05 to station 135+50.05 left shall be placed in accordance with Article 205 of the Standard Specifications. In addition, the earth material be cohesive and the embankment shall have a minimum bearing capacity of 1.5 tons per sq. ft. Areas of this special embankment requirement are shown in the Retaining Wall Detail drawing in the plans.

Work required for this special embankment construction, will not be paid for separately, but shall be included in the contract unit prices for the various excavation items and no further compensation will be allowed. *Plan earthwork quantities are already adjusted to compensate for select fill at the MSE wall being paid for with the MSE wall.* * 3
POROUS GRANULAR EMBANKMENT (SPECIAL)
Effective: April 5, 2005

Description. This work shall consist of furnishing, and placing porous granular embankment (special) material for backfilling excavation for structures according to Section 207 except as modified herein.

Materials. The gradation of the porous granular material shall be limited to CA 5 or CA 7.

Basis of Payment. This work will be paid for at the contract unit price per Cubic Yard (Cubic Meter) for POROUS GRANULAR EMBANKMENT (SPECIAL).

* 3 Addendum 11-7-05

SUSPENSION OF SLIPFORMED PARAPETS (BDE)

Effective: June 11, 2004

The slipforming option, as stated in Article 503.17(e)(1) of the Standard Specifications will not be allowed on this project.

80145

3
Added 11-7-05

163a.