

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED/ST	FED/ST	FD/ST/CITY	FED/ST	CITY	FED/ST
				0004 ROADWAY	0021 LIGHTING	0021 TRAFFIC SIGNAL	0021 SIDEWALK	0021 PRE-EMPTION EQUIPMENT	0031 LAND-SCAPING
				(80/20)	(80/20)	(80/10/10)	(80/20)		(100% CITY)
* M8860100	DETECTOR LOOP, TYPE I	METER	261			261			
* MB731850	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR NO. 6 IC	METER	323			323			
	<del>DRILLING AND SETTING SOLDIER PILES</del>	<del>CU M</del>	<del>90</del>				<del>90</del>		
* MX873030	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	METER	82			82			
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	10360	10360					
28000510	INLET FILTERS	EACH	37						37
<del>MX030418</del>	<del>STORM SEWER, WATER MAIN TYPE 3 450 mm</del>	<del>METER</del>	<del>24</del>	<del>24</del>					
* X8230505	LIGHTING CONTROLLER, SPECIAL	EACH	1			1			
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	2	2					
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	10	10					
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	15	15					
X4023000	TEMPORARY ACCESS (ROAD)	EACH	12	12					
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1			1			
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED, WITH COUNT DOWN TIMER	EACH	6			6			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	37	37					
* Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	10		10				
* MX816074	UNIT DUCT, 600V, 3-1/C #4 AND 1/C #6 GROUND, (XLP-TYPE RHW) 30 MM DIA., SCHEDULE 40 POLYETHYLENE	METER	440		440				
<del>MX030130</del>	<del>STORM SEWER (WATER MAIN REQUIREMENTS) 500MM</del>	<del>METER</del>	<del>10</del>	<del>10</del>					
MX030396	FILL EXISTING STORM SEWER	CU M	6	6					
MX030064	STORM SEWER (WATER MAIN REQUIREMENTS) 450 MM	METER	24	24					
MX030199	TEMPORARY PAVEMENT	SQ M	707	707					
MX030203	TEMPORARY PAVEMENT REMOVAL	SQ M	707	707					

\* Specialty Items

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004	0021	0021	0021	0021	0031
				ROADWAY	LIGHTING	TRAFFIC SIGNAL	SIDEWALK	PRE-EMPTION EQUIPMENT	LAND-SCAPING
M3550450	HOT-MIX ASPHALT BASE COURSE, 150 MM	SQ M	45	45					
M4240000	DETECTABLE WARNINGS	SQ M	41.2			41.2			
MB101060	CONDUIT PUSHED, 65 MM DIA., GALVANIZED STEEL	M	13			13			
<del>MX033724</del>	<del>GROUND ROD, 16MM DIA., 3 METER</del>	<del>EACH</del>	<del>13</del>			<del>13</del>			
B6200120	UNINTERRUPTIBLE POWER SUPPLY	EACH	1			1			
M542A120	GRATING FOR CONCRETE FLARED END SECTION 600MM	EACH	1	1					
M4205200	PROTECTIVE COAT	SQ M	2469	2469					
M7290200	METAL POST - TYPE B	M	29.3			29.3			
M7040100	TEMPORARY CONCRETE BARRIER	M	114.3	114.3					
M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	M	114.3	114.3					
* X7810010	REFLECTOR MARKERS, TYPE B	EACH	8	8					
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1					
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1					
82500610	LIGHTING CONTROLLER, SINGLE DOOR, CONSOLE TYPE	EACH	1			1			

Rev. 11-7-11  
 Rev. 9-7-11  
 Rev. 7-26-11

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 IL. 50 AT COURT STREET