

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004	0021	0021	0021		0021	0031	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004	0021	0021	0021		0021	0031
				ROADWAY	LIGHTING	TRAFFIC SIGNAL	SIDEWALK		PRE-EMPTION EQUIPMENT	LAND-SCAPING					ROADWAY	LIGHTING	TRAFFIC SIGNAL	SIDEWALK		PRE-EMPTION EQUIPMENT	LAND-SCAPING
				(80/20)	(80/20)	(80/10/10)	(80/20)		(100% CITY)	(80/20)					(80/20)	(80/20)	(80/10/10)	(80/20)		(100% CITY)	(80/20)
M7030210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	17	17							M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	30		30					
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	13,279	13,279							M8380095	BREAKAWAY DEVICE, TRANSFORMER BASE, 381MM BOLT CIRCLE	EACH	10		10					
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	225	225							M8731210	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	METER	553			553				
M7030260	TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	50	50							M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	METER	470			470				
M7030280	TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	32	32							M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	237			237				
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	1147	1147							M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	524			524				
M7200100	SIGN PANEL - TYPE 1	SQ M	9.27				9.27				M8731300	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	METER	561			561				
M7200200	SIGN PANEL - TYPE 2	SQ M	2.78				2.78				M8731800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	METER	50			50				
M7800100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	17	17							M8750510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 4.85 METER	EACH	4			4				
M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100MM	METER	2196	2196							<del>M8770030</del>	<del>STEEL MAST ARM ASSEMBLY AND POLE, 7.31 METER</del>	<del>EACH</del>	<del>1</del>			<del>1</del>				
M7800115	THERMOPLASTIC PAVEMENT MARKING - LINE 150MM	METER	225	225							<del>M8770045</del>	<del>STEEL MAST ARM ASSEMBLY AND POLE, 9.14 METER</del>	<del>EACH</del>	<del>1</del>			<del>1</del>				
M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	METER	50	50							<del>M8770055</del>	<del>STEEL MAST ARM ASSEMBLY AND POLE, 10.38 METER</del>	<del>EACH</del>	<del>1</del>			<del>1</del>				
M7800140	THERMOPLASTIC PAVEMENT MARKING - LINE 600MM	METER	58	58							<del>M8770075</del>	<del>STEEL MAST ARM ASSEMBLY AND POLE, 12.80 METER</del>	<del>EACH</del>	<del>1</del>			<del>1</del>				
M8100060	CONDUIT IN TRENCH, 50MM DIA., GALVANIZED STEEL	METER	177				177				M8770755	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 10.97 METER	EACH	1			1				
M8100070	CONDUIT IN TRENCH, 65MM DIA., GALVANIZED STEEL	METER	22				22				M8770760	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 11.58 METER	EACH	1			1				
M8100100	CONDUIT IN TRENCH, 100MM DIA., GALVANIZED STEEL	METER	3				3				M8770770	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 12.80 METER	EACH	2			2				
M8101050	CONDUIT PUSHED, 50MM DIA., GALVANIZED STEEL	METER	81				81				M8780100	CONCRETE FOUNDATION, TYPE A	METER	5			5				
M8101070	CONDUIT PUSHED, 75MM DIA., GALVANIZED STEEL	METER	100		100						M8780150	CONCRETE FOUNDATION, TYPE C	METER	1.2			1.2				
M8101090	CONDUIT PUSHED, 100MM DIA., GALVANIZED STEEL	METER	74				74				<del>M8780200</del>	<del>CONCRETE FOUNDATION, TYPE D</del>	<del>METER</del>	<del>12</del>			<del>12</del>				
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	195				195				M8780400	CONCRETE FOUNDATION, TYPE E 750MM DIAMETER	METER	19			19				
M8170060	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	METER	50		50						MX032057	STORM SEWER REMOVAL	METER	9							
M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	535		340		195				MX032178	TEMPORARY INFORMATION SIGNING	SQ M	16.6							
M8300820	LIGHT POLE, ALUMINUM, 10.5M M.H., 3.0M MAST ARM	EACH	10		10																

*\*Specialty Items*

Rev. 11-7-11  
Rev. 7-26-11

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
IL. 50 AT COURT STREET

5/7/2011

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED/ST	FED/ST	FD/ST/CITY	FED/ST	CITY	FED/ST
				0004 ROADWAY	0021 LIGHTING	0021 TRAFFIC SIGNAL	0021 SIDEWALK	0021 PRE-EMPTION EQUIPMENT	0031 LAND-SCAPING
				(80/20)	(80/20)	(80/10/10)	(80/20)		(100% CITY)
* M8860100	DETECTOR LOOP, TYPE I	METER	261			261			
* MB731850	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR NO. 6 IC	METER	323			323			
	<del>DRILLING AND SETTING SOLDIER PILES</del>	<del>CU M</del>	<del>90</del>				<del>90</del>		
* MX873030	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	METER	82			82			
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	10360	10360					
28000510	INLET FILTERS	EACH	37						37
<del>MX030418</del>	<del>STORM SEWER, WATER MAIN TYPE 3 450 mm</del>	<del>METER</del>	<del>24</del>	<del>24</del>					
* X8230505	LIGHTING CONTROLLER, SPECIAL	EACH	1			1			
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	2	2					
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	10	10					
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	15	15					
X4023000	TEMPORARY ACCESS (ROAD)	EACH	12	12					
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1			1			
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED, WITH COUNT DOWN TIMER	EACH	6			6			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	37	37					
* Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	10		10				
* MX816074	UNIT DUCT, 600V, 3-1/C #4 AND 1/C #6 GROUND, (XLP-TYPE RHW) 30 MM DIA., SCHEDULE 40 POLYETHYLENE	METER	440		440				
<del>MX030130</del>	<del>STORM SEWER (WATER MAIN REQUIREMENTS) 500MM</del>	<del>METER</del>	<del>10</del>	<del>10</del>					
MX030396	FILL EXISTING STORM SEWER	CU M	6	6					
MX030064	STORM SEWER (WATER MAIN REQUIREMENTS) 450 MM	METER	24	24					
MX030199	TEMPORARY PAVEMENT	SQ M	707	707					
MX030203	TEMPORARY PAVEMENT REMOVAL	SQ M	707	707					

\* Specialty Items

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004	0021	0021	0021	0021	0031
				ROADWAY	LIGHTING	TRAFFIC SIGNAL	SIDEWALK	PRE-EMPTION EQUIPMENT	LAND-SCAPING
M3550450	HOT-MIX ASPHALT BASE COURSE, 150 MM	SQ M	45	45					
M4240000	DETECTABLE WARNINGS	SQ M	41.2				41.2		
MB101060	CONDUIT PUSHED, 65 MM DIA., GALVANIZED STEEL	M	13			13			
<del>MX033724</del>	<del>GROUND ROD, 16MM DIA., 3 METER</del>	<del>EACH</del>	<del>13</del>			<del>13</del>			
B6200120	UNINTERRUPTIBLE POWER SUPPLY	EACH	1			1			
M542A120	GRATING FOR CONCRETE FLARED END SECTION 600MM	EACH	1	1					
M4205200	PROTECTIVE COAT	SQ M	2469	2469					
M7290200	METAL POST - TYPE B	M	29.3			29.3			
M7040100	TEMPORARY CONCRETE BARRIER	M	114.3	114.3					
M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	M	114.3	114.3					
* X7810010	REFLECTOR MARKERS, TYPE B	EACH	8	8					
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1					
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1					
82500610	LIGHTING CONTROLLER, SINGLE DOOR, CONSOLE TYPE	EACH	1			1			

Rev. 11-7-11  
 Rev. 9-7-11  
 Rev. 7-26-11

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 IL. 50 AT COURT STREET