

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE						
				ROADWAY 0004	STRUCTURES 0011	LIGHTING 0021	TRAFFIC SIGNALS			
							GALENA & IL ROUTE 56 RAMP-C 0021	GALENA & IL ROUTE 56 RAMP A/B 0021	INTERCONNECT 0021	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	50	50	-	-	-	-	-	-
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	473	473	-	-	-	-	-	-
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	220	220	-	-	-	-	-	-
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	779	779	-	-	-	-	-	-
50102400	CONCRETE REMOVAL	CU YD	52.1	-	52.1	-	-	-	-	-
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1	-	1	-	-	-	-	-
50157300	PROTECTIVE SHIELD	SQ YD	1360	-	1360	-	-	-	-	-
50200100	STRUCTURE EXCAVATION	CU YD	312	-	312	-	-	-	-	-
50300225	CONCRETE STRUCTURES	CU YD	108.1	-	108.1	-	-	-	-	-
50300255	CONCRETE SUPERSTRUCTURE	CU YD	981	-	981	-	-	-	-	-
50300260	BRIDGE DECK GROOVING	SQ YD	2259	-	2259	-	-	-	-	-
50300300	PROTECTIVE COAT	SQ YD	3145	-	3145	-	-	-	-	-
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	24950	-	24950	-	-	-	-	-
50500505	STUD SHEAR CONNECTORS	EACH	8211	-	8211	-	-	-	-	-
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	241930	-	241930	-	-	-	-	-
50800515	BAR SPLICERS	EACH	1255	-	1255	-	-	-	-	-
51100100	SLOPE WALL 4 INCH	SQ YD	991	-	991	-	-	-	-	-
51500100	NAME PLATES	EACH	1	-	1	-	-	-	-	-
52000110	PREFORMED JOINT STRIP SEAL	FOOT	202	-	202	-	-	-	-	-
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	26	-	26	-	-	-	-	-
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	26	-	26	-	-	-	-	-
52100520	ANCHOR BOLTS, 1"	EACH	104	-	104	-	-	-	-	-
52100530	ANCHOR BOLTS, 1 1/4"	EACH	26	-	26	-	-	-	-	-
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	6	6	-	-	-	-	-	-
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	17	17	-	-	-	-	-	-
58700300	CONCRETE SEALER	SO FT	987	-	987	-	-	-	-	-
59000200	EPOXY CRACK INJECTION	FOOT	154	-	154	-	-	-	-	-
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	154	-	154	-	-	-	-	-

EMERGENCY  
VEHICLE  
PREEMPTION  
100%  
VILLAGE OF  
SUGAR GROVE  
0021

\* SPECIALTY ITEM

\* Specialty Items

Rev. 11-9-11

FILE NAME = P:\2010\ME10012.P1B156-16.Galena\CADD\Shs\03-D160K76-sht-Galena-500.dgn  
PLOT SCALE = 1/8" = 1'-0"  
USER NAME = Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148  
630.705.0110 voice, 630.839.2566 fax  
www.mps-il.com  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 8/30/2011	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**GALENA BOULEVARD**

**SUMMARY OF QUANTITIES**

SCALE: NTS SHEET NO. 2 OF 6 SHEETS STA. TO STA.

F.A.P. RTE. 573	SECTION 61HB-1-R	COUNTY KANE	TOTAL SHEETS 110	SHEET NO. 4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60K76	