

SUMMARY OF QUANTITIES

| CODE NO. | ITEM DESCRIPTION | UNIT | URBAN TOTAL QUANTITY | CONSTRUCTION TYPE CODE | | | | | | |
|-----------------------|---|-----------------|----------------------|------------------------|--------------|--------------|-----------------------------|-------------------------------|--------------|------------------------------|
| | | | | ROADWAY | STRUCTURES | LIGHTING | TRAFFIC SIGNALS | | | EMERGENCY VEHICLE PREEMPTION |
| | | | | | | | GALENA & IL ROUTE 56 RAMP-C | GALENA & IL ROUTE 56 RAMP A/B | INTERCONNECT | |
| 0004 | 0011 | 0021 | 0021 | 0021 | 0021 | 0021 | 0021 | | | |
| * 87704516 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 48 FT. AND 30 FT. | EACH | 1 | - | - | - | - | 1 | - | - |
| * 87800100 | CONCRETE FOUNDATION, TYPE A | FOOT | 48 | - | - | - | 24 | 24 | - | - |
| * 87800150 | CONCRETE FOUNDATION, TYPE C | FOOT | 8 | - | - | - | 4 | 4 | - | - |
| * 87800400 | CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER | FOOT | 20 | - | - | - | 20 | - | - | - |
| * 87800415 | CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER | FOOT | 42 | - | - | - | 13 | 29 | - | - |
| * 88030020 | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED | EACH | 12 | - | - | - | 6 | 6 | - | - |
| * 88030050 | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED | EACH | 10 | - | - | - | 6 | 4 | - | - |
| * 88030210 | SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED | EACH | 2 | - | - | - | 1 | 1 | - | - |
| * 88030240 | SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED | EACH | 2 | - | - | - | - | 2 | - | - |
| * 88200210 | TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM | EACH | 12 | - | - | - | 6 | 6 | - | - |
| * 88500100 | INDUCTIVE LOOP DETECTOR | EACH | 15 | - | - | - | 7 | 8 | - | - |
| * 88600100 | DETECTOR LOOP, TYPE I | FOOT | 895 | - | - | - | 385 | 510 | - | - |
| * 88700200 | LIGHT DETECTOR | EACH | 4 | - | - | - | - | - | - | 4 |
| * 88700300 | LIGHT DETECTOR AMPLIFIER | EACH | 2 | - | - | - | - | - | - | 2 |
| X2070304 | POROUS GRANULAR EMBANKMENT, SPECIAL | CU YD | 312 | - | 312 | - | - | - | - | - |
| Δ X5539700 | STORM SEWERS TO BE CLEANED | FOOT | 410 | 410 | - | - | - | - | - | - |
| X7010216 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 1 | - | - | - | - | - | - |
| * X8180060 | AERIAL CABLE, 3-1/C NO. 2, ALUMINUM, WITH MESSENGER WIRE | FOOT | 150 | - | - | 150 | - | - | - | - |
| * X8730250 | ELECTRIC CABLE IN CONDUIT NO. 20 3/4, TWISTED, SHIELDED | FOOT | 760 | - | - | - | - | - | - | 760 |
| Z0001050 | AGGREGATE SUBGRADE 12" | SQ YD | 793 | 793 | - | - | - | - | - | - |
| Z0001899 | JACK AND REMOVE EXISTING BEARINGS | EACH | 65 | - | 65 | - | - | - | - | - |
| Z0001903 | STRUCTURAL STEEL REMOVAL | POUND | 7980 | - | 7980 | - | - | - | - | - |
| Z0003500 | BEAM STRAIGHTENING | EACH | 3 | - | 3 | - | - | - | - | - |
| Z0004552 | APPROACH SLAB REMOVAL | SQ YD | 574 | - | 574 | - | - | - | - | - |
| Z0007112 | CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES | L SUM | 1 | - | 1 | - | - | - | - | - |
| Z0010501 | CLEANING AND PAINTING STEEL BRIDGE NO. 1 | L SUM | 1 | - | 1 | - | - | - | - | - |
| Z0012754 | STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES) | SQ FT | 292 | - | 292 | - | - | - | - | - |

EMERGENCY VEHICLE PREEMPTION
100% VILLAGE OF SUGAR GROVE
0021

Δ NON-PARTICIPATING (1001.STATE)
* Specialty Items

FILE NAME : P:\2010\ME10012_PTB156-16_Galena\CADD\Shets\03-D160K76-sht-Galena-500.dgn
SCALE : 1/8" = 1'-0"
DATE : 8/30/2011



200 22ND Street, Suite 216, Lombard, IL 60148
630.785.8110 voice, 630.839.2566 fax
www.mps-il.com

MILLENNIA PROFESSIONAL SERVICES

| | |
|------------------|-----------|
| DESIGNED - CJD | REVISED - |
| DRAWN - CJD | REVISED - |
| CHECKED - TWN | REVISED - |
| DATE - 8/30/2011 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GALENA BOULEVARD

SUMMARY OF QUANTITIES

| | | | | |
|--------------------|------------------|-------------|------------------|-------------|
| F.A.P. RTE. 573 | SECTION 61HB-1-R | COUNTY KANE | TOTAL SHEETS 110 | SHEET NO. 8 |
| CONTRACT NO. 60K76 | | | Rev. 11-9-11 | |

SCALE: NTS SHEET NO. 6 OF 6 SHEETS STA. TO STA.

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT