

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, LIST OF STATE STANDARDS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	SITE PLAN
5	SUGGESTED STAGE IA CONSTRUCTION
6	SUGGESTED STAGE IB CONSTRUCTION
7	SUGGESTED STAGE II CONSTRUCTION
8	SUGGESTED STAGE IIIA CONSTRUCTION
9	SUGGESTED STAGE IIIB CONSTRUCTION
10	DETOUR PLAN - STAGE IIIB
11	NIGHT TIME DETOUR PLAN - STAGE II & STAGE IIIB
11A	NIGHTLY DETOUR PLAN - STAGE II
11B	STATE STREET RAMP DETOUR
S.N. 016-0036	
12	GENERAL PLAN & ELEVATION
13	DECK CONCRETE PATCHING
13A	PIER E12 REPAIRS
S.N. 016-1045	
14	GENERAL PLAN & ELEVATION
15	DECK CONCRETE PATCHING
16	PIER ES3 REPAIRS
17	PIER ES6 REPAIRS
18	PIER ES7 REPAIRS
S.N. 016-1048	
19	GENERAL PLAN & ELEVATION
20	DECK CONCRETE PATCHING
S.N. 016-1052	
21	GENERAL PLAN & ELEVATION
22	DECK CONCRETE PATCHING
S.N. 016-1055	
23	GENERAL PLAN & ELEVATION
24	DECK CONCRETE PATCHING
S.N. 016-1075	
25	GENERAL PLAN & ELEVATION
26	DECK CONCRETE PATCHING
27	PIER E15 REPAIRS
28	PIER E16 REPAIRS
29	BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS
30	EXISTING PLANS - PIERS ES1, ES2 & ES3
31	EXISTING PLANS - PIER ES6
32	EXISTING PLANS - PIER ES7
33	EXISTING PLANS - PIER E12
34	EXISTING PLANS - PIERS E14 & E15
35	EXISTING PLANS - PIERS E16 & E17
36	FREEWAY ENTRANCE AND EXIT RAMP CLOSURE DETAIL
37	TRAFFIC CONTROL DETAILS FOR FREEWAY SINGLE & MULTI-LANE WEAVE
38	TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES
39	TRAFFIC CONTROL DETAILS FOR FREEWAY CENTER LANE CLOSURE SHOULDER LANE
40	MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS
41	MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS

LIST OF STATE STANDARDS

STANDARD NO.	DESCRIPTION
701400-05	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-06	LANE CLOSURE, FREEWAY/EXPRESSWAY
701411-07	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS > 45 MPH
701422-03	LANE CLOSURE, MULTILANE, FOR SPEEDS >= 45 MPH TO 55 MPH
701446-02	TWO LANE CLOSURE FREEWAY/EXPRESSWAY
701901-01	TRAFFIC CONTROL DEVICES
704001-06	TEMPORARY CONCRETE BARRIER
780001-02	TYPICAL PAVEMENT MARKINGS

GENERAL NOTES:

- THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM I.D.O.T. FIELD MAINTENANCE ENGINEERS.
- THE CONTRACTOR MUST USE EXTREME CAUTION DURING FULL DEPTH DECK SLAB REPAIR AND MUST NOT NICK, CUT OR DAMAGE, IN ANY WAY, ANY OF THE STEEL BEAMS. THE EXISTING REINFORCEMENT BARS SHALL BE CLEANED. IF ANY OF THESE REINFORCEMENT BARS ARE DAMAGED THEY MUST BE REPLACED WITH AN APPROVED BAR SPLICER OR ANCHORAGE SYSTEM. THE COST OF THIS WORK IS INCLUDED WITH DECK SLAB REPAIR (FULL DEPTH, TYPE II).
- THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4151 AT LEAST 72 HOURS PRIOR TO INSTALLATION OF THE TEMPORARY TRAFFIC CONTROL DEVICES.
- THERE ARE ELECTRICAL CONDUITS AND/OR FIBERGLASS DRAIN PIPES ATTACHED TO THE BOTTOM OF THE BRIDGE DECK. THE CONTRACTOR MAY MODIFY THE FORMING AND MUST EXERCISE EXTREME CAUTION DURING FULL DEPTH REPAIR BREAK OUT AND SHALL TEMPORARILY SUPPORT THE CONDUITS AND/OR DRAIN PIPES IF NEED BE, AT NO ADDITIONAL COST TO THE DEPARTMENT.
- WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR MUST EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC.
- PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE BID FOR THE WORK.
- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL C.U.A.N. AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES (48 HOURS NOTIFICATION IS REQUIRED).
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- TO COORDINATE ACCESS TO THE McCORMICK PLACE PARKING LOT CALL DARREN PETER AT (312) 296-5984.
- DURING ANY WORK WITHIN THE McCORMICK PLACE PARKING LOT, THE CONTRACTOR MUST COORDINATE WITH THE McCORMICK PLACE PARKING LOT AUTHORITY AS TO AVOID ANY AND ALL CONFLICTS DURING THIS CONTRACT.
- DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
- ANY DAMAGES TO THE CONDUITS OR PIPES CAUSED BY THE CONTRACTOR'S OPERATIONS SHALL BE REPLACED OR REPAIRED BY THE CONTRACTOR AT HIS/HER EXPENSE.
- ALL PROPOSED RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE) SHALL BE LOW PROFILE.
- THE CONTRACTOR SHALL COORDINATE AND/OR MODIFY THE WORK SCHEDULE AS DIRECTED BY THE DEPARTMENT TO ACCOMMODATE SPECIAL EVENTS.
- THE CONTRACTOR SHALL PLACE TEMPORARY CONCRETE BARRIER ADJACENT TO TEMPORARY SHORING AND CRIBBING TO PROVIDE A BARRIER FROM PARKING LOT TRAFFIC. AN ESTIMATED THREE (3) SECTIONS OF TEMPORARY CONCRETE BARRIER WILL BE NEEDED AT EACH SHORING AND CRIBBING LOCATIONS.
- THE CONTRACTOR SHALL USE PP3 CONCRETE FOR ALL DECK PATCHES.
- AS PART OF THIS PROJECT, ALL BRIDGE DECKS SHALL BE RE-STRIPED AND RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE REMOVED AND REPLACED.
- THE CONTRACTOR WILL BE ALLOWED ADDITIONAL TEMPORARY LANE CLOSURES TO MEASURE AND SAWCUT PATCHING AREAS AND TO LAYOUT WEAVE LOCATIONS.
- TO COORDINATE TRAFFIC CONTROL WITH McCORMICK PLACE CALL EUGENE HARTISON AT (312) 791-6081.

FILE NAME = I:\2008\1-55\STRUCTURAL\sheet\0160037-02-index of sheets.dgn

	USER NAME = IDOT	DESIGNED - J.C.N./B.N.S.	REVISED - ADDENDUM 1 11-04-2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, LIST OF STATE STANDARDS AND GENERAL NOTES F.A.I. RTE. I-55 OVER U.S. 41 / LAKE SHORE DRIVE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.0000' / 1"	CHECKED - B.N.S./J.C.N.	REVISED -			55	2011-031-BR	COOK	41	2
	PLOT DATE = 11/9/2011	DRAWN - F.M.	REVISED -			ILLINOIS FED. AID PROJECT				
		DATE - OCTOBER 12, 2011	REVISED -			CONTRACT NO. 60P37				
						SHEET NO. 52 OF 541 SHEETS				