



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 1, 2022

SUBJECT: FAU 9450 (Wastena Street)
Section 11-00064-00-FP (Benton)
Franklin County
Contract No. 99671
Item 099
November 18, 2022 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Table of Contents**
- 2. Revised Pages 2 & 5 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

SPECIAL PROVISIONS INDEX

ITEM	PAGE
DESCRIPTION OF WORK	1
COOPERATION WITH UTILITIES	1
EXISTING ROAD SIGNS	2
EXISTING MAILBOXES	2
TRANSITIONS	3
CONTRACT TIME	3
TREE REMOVAL	3
TRAFFIC CONTROL PLAN	3
DROP-OFF NEAR EDGE OF TRAVELED WAY	3
AVAILABILITY OF ELECTRONIC PLANS	4
INLETS, SPECIAL, NO. 1	4
INLETS, SPECIAL, NO. 2	4
TRAFFIC CONTROL AND PROTECTION (SPECIAL)	4
EROSION CONTROL MAINTENANCE	5
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	5
STORMWATER POLLUTION PREVENTION PLAN	6
LR 107-4 INSURANCE	14
LR 1030-2 LOCAL QUALITY ASSURANCE/ QUALITY MANAGEMENT QC/QA	15
STORM SEWERS, TYPE 2, WATER MAIN PROTECTION	17

Underground utilities have been plotted from available surveys and records and, therefore, their locations must be considered approximate only. There also may be utilities for which the locations are unknown. Verification of locations of underground utilities, shown or not shown, will be the responsibility of the Contractor. The following utility companies have facilities within the project limits which will require adjustment:

Name and Address of Utility	Type	Locations	Estimated Date Adjustment Completed
City of Benton	Water & sewer	Scattered	As Needed
Frontier	Telephone	Scattered	As Needed
Amerin CIPS	Electric & Gas	Scattered	As Needed
Sparklight	Cable TV	Scattered	As Needed
Southeastern Illinois Electric Co-Op	Electric	Scattered	As Needed

Additional utility information may be obtained by calling the "Joint Utility Location Information for Excavators" phone number, 800-892-0123. This project is located in the City of Benton, IL

EXISTING ROAD SIGNS: All road signs within the construction limits shall be removed and delivered to the Village for their use. The work will not be paid for separately, but shall be considered as incidental to the contract.

EXISTING MAILBOXES: All mailboxes within or near the construction limits that interfere with construction operation shall be removed and set back in a temporary location which does not interfere with the mail delivery. As soon as construction operations permit, the mailboxes shall be erected at their permanent location as directed by the Engineer. Heights of mail boxes and proximity to curbs, inlets and

REVISED 10/31/2022

eastern part of the job (Wilson Street to McLeansboro Street). As work begins for the day the barricades shall be set and the traffic signs shall be placed (at the locations as shown on the plans). After the day's work the road shall be reopened for the night.

Work shall be coordinated with the City of Benton, the Benton Grade School District and the Benton Consolidated High School.

The contractor shall schedule operations to maintain access to all residential and commercial facilities.

This item shall include a Portable Changeable Message Sign placed near the starting point and ending point of the project, each operating for thirty (30) calendar days before the project starting day, and as needed for traffic control during the construction period.

Payment shall be at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION (SPECIAL).

EROSION CONTROL MAINTENANCE: This work shall consist of maintaining temporary erosion control along the project as shown on the plans. Erosion Control shall be in accordance with the Standard Specifications for Road and Bridge Construction in Illinois.

Ditch Checks, Inlet and Pipe Protection and maintaining perimeter Silt Fence shall be maintained by either repairing item and/or cleaning out silt deposits, or by replacing erosion control item to ensure a minimum amount of silt leaves the construction site.

After project completion and seeding has germinated, the perimeter silt fence shall be removed when directed to the Resident Engineer. The cost for removal and disposal of the silt fence shall be included in the cost of silt fence installation.

BASIS OF PAYMENT: The work will not be paid for separately, but shall be considered as incidental to the bid items for the erosion control plan.

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70

Description: The mix used for this pay item shall be a IL-19.0, N70 mix and placed according to Section 406 of the Standard Specifications, except a lift thickness of 2" will be allowed. Density requirements shall be to the satisfaction of the Engineer.

STORM WATER POLLUTION PREVENTION PLAN: The Storm Water Pollution Prevention Plan (SWPPP) is required for this project. The Contractor shall prepare the SWPPP and, prior to the start of construction the Contractor shall complete the Notice of Intent (NOi) and forward it to the Owner for submittal to IEPA. Any costs of preparation and submittal shall the Contractor's responsibility.