# SCHEDULE OF QUANTITIES

**44000400 GUTTER REMOVAL**

| LOCATION | | | | | FOOT |
|---|---|---|---|---|---|
| STA 190+00 | TO | 193+36 | RT | US 6 | 336 |
| STA 209+69 | TO | 217+40 | LT | US 6 | 771 |
| STA 209+85 | TO | 217+20 | RT | US 6 | 735 |
| STA 3+67 | TO | 10+40 | LT | IL 84 | 676 |
| STA 5+21 | TO | 9+05 | RT | IL 84 | 396 |
| | | | | TOTAL | 2914 |

**44004250 PAVED SHOULDER REMOVAL**

| LOCATION | | | | | SQ YD |
|---|---|---|---|---|---|
| STA 190+00 | TO | 204+84 | RT | US 6 | 583 |
| STA 190+00 | TO | 203+35 | LT | US 6 | 454 |
| STA 205+07 | TO | 217+75 | RT | US 6 | 671 |
| STA 205+14.9 | TO | 206+82 | LT | US 6 | 157 |
| STA 209+69 | TO | 217+75 | LT | US 6 | 467 |
| STA 8+62.61 | TO | 11+75 | RT | IL 84 | 251 |
| STA 10+09.23 | TO | 11+75 | LT | IL 84 | 129 |
| | | | | TOTAL | 2712 |

**50100300 REMOVAL OF EXISTING STRUCTURES NO. 1**

| LOCATION | | EACH | COMMENTS |
|---|---|---|---|
| STA 198+68 | US 6 | 1 | SEE SPECIAL PROVISIONS FOR DETAILS |
| | TOTAL | 1 | |

**50100400 REMOVAL OF EXISTING STRUCTURES NO. 2**

| LOCATION | | EACH | COMMENTS |
|---|---|---|---|
| STA 203+25 | US 6 | 1 | SEE SPECIAL PROVISIONS FOR DETAILS |
| | TOTAL | 1 | |

**50100500 REMOVAL OF EXISTING STRUCTURES NO. 3**

| LOCATION | | EACH | COMMENTS |
|---|---|---|---|
| STA 209+83 | US 6 | 1 | SEE SPECIAL PROVISIONS FOR DETAILS |
| | TOTAL | 1 | |

**50100600 REMOVAL OF EXISTING STRUCTURES NO. 4**

| LOCATION | | EACH | COMMENTS |
|---|---|---|---|
| STA 1006+00 | RT SLIP RAMP | 1 | SEE SPECIAL PROVISIONS FOR DETAILS |
| | TOTAL | 1 | |

**50100700 REMOVAL OF EXISTING STRUCTURES NO. 5**

| LOCATION | | EACH | COMMENTS |
|---|---|---|---|
| STA 10+76 | | 1 | SEE SPECIAL PROVISIONS FOR DETAILS |
| | TOTAL | 1 | |

**50104400 CONCRETE HEADWALL REMOVAL**

| LOCATION | | | EACH |
|---|---|---|---|
| STA 194+07 | RT | US 6 | 1 |
| STA 1007+00 | LT | SLIP RAMP | 2 |
| STA 2+70 | LT & RT | IL 84 | 2 |
| | | TOTAL | 5 |

**542A1075 PIPE CULVERTS, CLASS A, TYPE 2 30"**

| LOCATION | | FOOT | COMMENTS |
|---|---|---|---|
| STA 196+25 | 33' LT & 34' RT | 67 | US 6 |
| STA 198+75 | 58' LT & 49' RT | 107 | US 6 |
| STA 209+00.2 | 25' LT & 48' RT @ 30° SKEW | 73 | US 6 |
| STA 209+00.2 | 29' LT & 68' LT @ 30° SKEW | 39 | US 6 |
| STA 10+76.35 | 75' LT & 59' RT @ 41° SKEW | 134 | IL 84 |
| | | TOTAL 420 | |

**542A1093 PIPE CULVERTS, CLASS A, TYPE 2 48"**

| LOCATION | | FOOT |
|---|---|---|
| STA 203+25 | 35' LT & 34' RT | 69 |
| | TOTAL | 69 |

**542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"**

| LOCATION | | | FOOT | COMMENTS |
|---|---|---|---|---|
| STA 191+50 | RT | US 6 | 54 | PRIVATE ENTRANCE |
| STA 91+75 | LT | 400TH ST. | 87 | FIELD ENTRANCE |
| STA 3+50 | LT | IL 84 | 62 | PRIVATE ENTRANCE |
| | | | TOTAL 203 | |

**542D0223 PIPE CULVERTS, CLASS D, TYPE 1 18"**

| LOCATION | | | | | FOOT | COMMENTS |
|---|---|---|---|---|---|---|
| STA 206+25 | TO | 207+75 | LT | US 6 | 148 | |
| STA 207+77 | TO | 207+82 | LT | US 6 | 5 | |
| STA 208+98 | TO | 209+11 | LT | US 6 | 13 | |
| STA 95+19 | RT | 400TH ST. | | | 52 | PRIVATE ENTRANCE |
| | | | | | TOTAL 218 | |

**542D0229 PIPE CULVERTS, CLASS D, TYPE 1 24"**

| LOCATION | | | | | FOOT | COMMENTS |
|---|---|---|---|---|---|---|
| STA 198+77 | TO | 199+43 | RT | US 6 | 66 | PRIVATE ENTRANCE |
| | | | | | TOTAL 66 | |

**542D1075 PIPE CULVERTS, CLASS D, TYPE 2 30"**

| LOCATION | | FOOT | COMMENTS |
|---|---|---|---|
| STA 196+25 | LT | 164 | COLONA HEIGHTS |
| | TOTAL | 164 | |

**542D1081 PIPE CULVERTS, CLASS D, TYPE 2 36"**

| LOCATION | | FOOT | COMMENTS |
|---|---|---|---|
| STA 10+76.35 | 54' LT & 80' RT | 134 | COLONA HEIGHTS |
| | TOTAL | 134 | |

**542D5476 PIPE CULVERTS, CLASS D, TYPE 1EQUIVALENT ROUND SIZE 21"**

| LOCATION | | | FOOT | COMMENTS |
|---|---|---|---|---|
| STA 97+00 | RT | 400TH ST. | 53 | PRIVATE ENTRANCE |
| | | TOTAL | 53 | |

**542D5503 PIPE CULVERTS, CLASS D, TYPE 1EQUIVALENT ROUND SIZE 48"**

| LOCATION | | | FOOT | COMMENTS |
|---|---|---|---|---|
| STA 14+30 | RT | IL 84 | 50 | PRIVATE ENTRANCE |
| | | TOTAL | 50 | |

**54213450 END SECTIONS 15"**

| LOCATION | | | EACH | COMMENTS |
|---|---|---|---|---|
| STA 191+50 | 35' RT | US 6 | 2 | PRIVATE ENTRANCE |
| STA 91+75 | 36' LT | 400TH ST. | 2 | FIELD ENTRANCE |
| STA 3+50 | 45' LT | IL 84 | 2 | PRIVATE ENTRANCE |
| | | TOTAL | 6 | |

**54213453 END SECTIONS 18"**

| LOCATION | | | EACH | COMMENTS |
|---|---|---|---|---|
| STA 206+25 | 36' LT | US 6 | 1 | |
| STA 95+19 | 33' RT | 400TH ST. | 2 | PRIVATE ENTRANCE |
| | | TOTAL | 3 | |

**54214296 END SECTIONS, EQUIVALENT ROUND-SIZE 21"**

| LOCATION | | | EACH | COMMENTS |
|---|---|---|---|---|
| STA 97+00 | RT | 400TH ST. | 2 | PRIVATE ENTRANCE |
| | | TOTAL | 2 | |

**54215408 CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 8"**

| LOCATION | | EACH | COMMENTS |
|---|---|---|---|
| STA 203+33 | RT | 1 | LOCATION TO BE DETERMINED IN THE FIELD |
| | TOTAL | 1 | |

**54260311 TRANSVERSABLE PIPE GRATES**

| LOCATION | | | FOOT | COMMENTS |
|---|---|---|---|---|
| STA 198+75 | RT | US 6 | 11' | DROP BOX NO.2 - 3 @ 3'-8" |
| STA 198+75 | LT | US 6 | 14'-10" | 30" PIPE CULVERT END SECTION - 1@14'-10" |
| STA 196+25 | RT | US 6 | 8' | DROP BOX NO.1 - 3 @ 2'-8" |
| STA 203+25 | LT | US 6 | 47'-9" | 48" PIPE CULVERT END SECTION - 2@21'-4" AND 1@ 5'-1" |
| STA 208+75 | RT | US 6 | 8' | DROP BOX NO.3 - 3 @ 2'-8" |
| STA 209+00 | LT | US 6 | 14'-10" | 30" PIPE CULVERT END SECTION - 1@14'-10" |
| STA 10+28 | LT | IL 84 | 8' | DROP BOX NO.4 - 3 @ 2'-8" |
| STA 10+76 | RT | IL 84 | 14'-10" | 30" PIPE CULVERT END SECTION - 1@14'-10" |
| STA 10+61 | LT | COLONA HEIGHTS | 10' | DROP BOX NO.5 - 2 @ 4'-8" |
| | | | TOTAL 137'-3" | |

**54261430 CONCRETE END SECTION, STANDARD 542001, 30", 1:4**

| LOCATION | | EACH | COMMENTS |
|---|---|---|---|
| STA 198+75 | LT | 1 | US 6 |
| STA 209+00 | LT | 1 | US 6 |
| STA 10+76.35 | RT | 1 | IL 84 |
| | TOTAL | 3 | |

**54261448 CONCRETE END SECTION, STANDARD 542001, 48", 1:4**

| LOCATION | | EACH |
|---|---|---|
| STA 203+25 | LT & RT | 2 |
| | TOTAL | 2 |

**60100060 CONCRETE HEADWALL FOR PIPE DRAINS**

| LOCATION | | | EACH |
|---|---|---|---|
| STA 190+00 | RT | US 6 | 1 |
| STA 193+00 | LT & RT | US 6 | 2 |
| STA 196+25 | LT & RT | US 6 | 2 |
| STA 199+50 | RT | US 6 | 1 |
| STA 200+00 | LT | US 6 | 1 |
| STA 202+00 | RT | US 6 | 1 |
| STA 208+75 | RT | US 6 | 1 |
| STA 217+75 | LT & RT | US 6 | 2 |
| STA 1000+00 | RT | SLIP RAMP | 1 |
| STA 1004+25 | RT | SLIP RAMP | 1 |
| STA 1010+25 | RT | SLIP RAMP | 1 |
| STA 1014+00 | RT | SLIP RAMP | 1 |
| STA 4+50 | LT | IL 84 | 1 |
| STA 7+50 | LT | IL 84 | 1 |
| STA 11+75 | LT & RT | IL 84 | 2 |
| | | TOTAL | 19 |

* 5789 & 5861