SCHEDULE OF QUANTITIES

60100925 PIPE DRAINS 8"

LOCATION		FOOT	COMMENTS
STA 203+33 RT		35	LOCATION TO BE DETERMINED IN THE FIELD
	TOTAL	35	

60107600 PIPE UNDERDRAINS 4"

LOCATION					FOOT
STA 190+00	TO	204+00	RT	US 6	1400
STA 190+00	TO	203+00	LT	US 6	1300
STA 206+00	TO	217+75	RT	US 6	1175
STA 212+75	TO	217+75	LT	US 6	500
STA 1000+00	TO	1014+00	RT	SLIP RAMP	1400
STA 1+50	TO	11+75	LT	IL 84	1025
STA 8+00	TO	11+75	RT	IL 84	375
				TOTAL	7175

60108100 PIPE UNDERDRAINS 4" (SPECIAL)

LOCATION			FOOT
STA 190+00	RT	US 6	20
STA 193+00	RT	US 6	15
STA 193+00	LT	US 6	15
STA 196+25	RT	US 6	20
STA 196+25	LT	US 6	20
STA 199+50	RT	US 6	15
STA 200+00	LT	US 6	15
STA 202+00	RT	US 6	18
STA 208+75	RT	US 6	20
STA 217+75	LT	US 6	20
STA 217+75	RT	US 6	15
STA 1000+00	RT	SLIP RAMP	20
STA 1004+25	RT	SLIP RAMP	20
STA 1010+25	RT	SLIP RAMP	20
STA 1014+00	RT	SLIP RAMP	20
STA 4+50	LT	IL 84	15
STA 7+50	LT	IL 84	15
STA 11+75	LT	IL 84	18
STA 11+75	RT	IL 84	20
		TOTAL	341

60218400 MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID

LOCATION			EACH
STA 207+75	24.44' LT	US 6	1
		TOTAL	1

60221100 MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID

LOCATION			EACH
STA 209+13.6	23.11' LT	US 6	1
		TOTAL	1

60221700 MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE

LOCATION			EACH
STA 196+25	35' LT	US 6	1
		TOTAL	1

60600095 CLASS SI CONCRETE (OUTLET)

LOCATION			CU YD	COMMENTS
STA 209+00	RT	US 6	1.25	INLET
STA 216+75	RT	US 6	4.58	OUTLET
			TOTAL 5.83	

60608582 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24

LOCATION				FOOT	COMMENTS
STA 209+00	TO	216+75	RT	775	US 6
			TOTAL	775	

61100500 EXPLORATION TRENCH 52" DEPTH

LOCATION			FOOT	COMMENTS
STA 203+25	RT	US 6	150	LOCATION TO BE DETERMINED IN THE FIELD
		TOTAL	150	

61133200 FIELD TILE JUNCTION VAULTS 3' DIA.

LOCATION		EACH	COMMENTS
STA 203+33 RT		1	LOCATION TO BE DETERMINED IN THE FIELD
	TOTAL	1	

63200310 GUARDRAIL REMOVAL

LOCATION				FOOT	COMMENTS
STA 192+40	TO	195+55	LT	315	US 6
			TOTAL	315	

63500105 DELINEATORS

LOCATION		EACH	COMMENTS
STA 196+25	RT	1	US 6
STA 198+75	LT & RT	2	US 6
STA 203+25	LT & RT	2	US 6
STA 209+00	LT & RT	2	US 6
STA 10+76.35	LT & RT	2	IL 84
STA 10+61	LT & RT	2	COLONA HEIGHTS
	TOTAL	11	

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY-MARKERS

LOCATION			EACH	COMMENTS
STA 198+50	69.43' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 198+60	100' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 198+90	100' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 199+00	67.80' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 208+25	94.02' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 210+50	120' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 211+00	80' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 213+50	80' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 214+00	95' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 214+50	90' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 214+75	75' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 216+00	75' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 216+93.0	70' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 217+75	70' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 218+00	60.62' LT	US 6	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 2+67.67	80' LT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 4+00	90' LT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 5+00	95' LT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 6+50	110' LT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 8+00	97.30' LT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 8+50	61.17' RT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 9+00	80' RT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 11+00	85' RT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 11+25	95' RT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 12+00	75' RT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 13+00	75' RT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 15+50	50' RT	IL 84	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 90+00	35.87' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 90+00	24.13' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 90+25	40' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 90+50	55' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 91+25	65' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 91+25	60' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 92+00	55' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 92+00	55' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 93+00	55' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 93+25	80' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 93+50	85' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 94+25	80' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 94+25	65' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 94+50	75' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 94+75	130' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 95+25	165' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 95+50	160' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 95+50	80' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 96+00	115' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 96+00	75' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 96+50	55' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 96+75	95' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 97+25	45' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 97+65.93	65' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 98+25	90' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 98+75	75' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 99+25.41	80' RT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
STA 99+31.59	75' LT	400TH ST	1	SEE GENERAL NOTE FOR INSTALLATION METHOD
		TOTAL	55	

66700305 PERMANENT SURVEY MARKERS, TYPE II

LOCATION	EACH	COMMENTS
TO BE DETERMINED IN FIELD	1	LOCATION DETERMINED BY DISTRICT OFFICE-CHIEF OF SURVEYS
TOTAL	1	

* 5789 & 5861