

SCHEDULE OF QUANTITIES

78009000 MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS

LOCATION		SQ.FT	COMMENTS
STA 201+73	US 6	15.6	1- LT Turn Arrow
STA 202+48	US 6	15.6	1- LT Turn Arrow
STA 203+23	US 6	15.6	1- LT Turn Arrow
STA 203+98	US 6	15.6	1- LT Turn Arrow
STA 205+69	US 6	15.6	1- LT Turn Arrow
STA 206+45	US 6	15.6	1- LT Turn Arrow
STA 207+20	US 6	15.6	1- LT Turn Arrow
STA 207+95	US 6	15.6	1- LT Turn Arrow
STA 1+60	IL 84	15.6	1- RT Turn Arrow
STA 2+34	IL 84	15.6	1- RT Turn Arrow
STA 3+10	IL 84	15.6	1- RT Turn Arrow
STA 3+85	IL 84	15.6	1- RT Turn Arrow
STA 1002+95	SLIP RAMP	15.6	1- RT Turn Arrow
STA 1003+64	SLIP RAMP	15.6	1- RT Turn Arrow
STA 1004+34	SLIP RAMP	15.6	1- RT Turn Arrow
STA 1005+04	SLIP RAMP	15.6	1- RT Turn Arrow
<hr/>			
249.6			

78100100 RAISED REFLECTIVE PAVEMENT MARKERS

LOCATION		EACH	COMMENTS
STA 190+00	TO 204+33 US 6	84	
STA 205+40	TO 217+75 US 6	74	
STA 0+80	TO 11+75 IL 84	28	
<hr/>			
TOTAL TWO-WAY:			186
STA 201+53	TO 204+31 US 6	15	
STA 205+41	TO 208+15 US 6	15	
STA 207+69	TO 210+03 US 6	24	
STA 0+79	TO 4+03 IL 84	17	
STA 2+00	TO 4+77 IL 84	30	
STA 1005+18	TO 1007+72 SLIP RAMP	8	
<hr/>			
TOTAL ONE-WAY:			109
<hr/>			
TOTAL			295

Two-way amber @ 40' centers, 20' centers per std.
Two-way amber @ 40' centers, 20' centers per std.
Two-way amber @ 40' centers

One-way crystal @ 20' centers per std.
One-way crystal @ 20' centers per std.
One-way crystal @ 20' centers per std. Gore Area
One-way crystal @ 20' centers per std.
One-way crystal @ 20' centers per std. Gore Area
One-way amber @ 40' centers per std.

78009004 MODIFIED URETHANE PAVEMENT MARKING - LINE 4"

LOCATION		FOOT	COMMENTS
STA 190+00	TO 195+89 US 6	1,178	Double Solid Centerline
STA 195+89	TO 204+34 US 6	2,636	Double Solid Island
STA 205+40	TO 213+80 US 6	2,631	Double Solid Island
STA 213+80	TO 217+75 US 6	790	Double Solid Centerline
STA 0+79	TO 11+75 IL 84	2,192	Double Solid Centerline
STA 90+25	TO 99+83 400 th St.	1,916	Double Solid Centerline
STA 1005+07	TO 1007+90 SLIP RAMP	310	LT Edge Line
<hr/>			
TOTAL YELLOW:			11,653
STA 190+00	TO 204+60 US 6	1,506	LT Edge Line
STA 190+00	TO 204+71 US 6	1,558	RT Edge Line
STA 205+16	TO 207+69 US 6	254	White
STA 204+95	TO 217+75 US 6	1,317	White
STA 212+78	TO 215+10 US 6	259	White
STA 215+36	TO 217+75 US 6	264	White
STA 1+38	TO 11+75 IL 84	1,035	White
STA 0+52	TO 1+98 IL 84	148	White
STA 8+60	TO 11+75 IL 84	316	White
STA 4+78	TO 8+59 IL 84	127	White
STA 1000+00	TO 1014+50 SLIP RAMP	1,449	White
STA 90+25	TO 98+93 400 th St.	868	White
STA 90+25	TO 99+46 400 th St.	921	White
<hr/>			
TOTAL WHITE:			10,022
<hr/>			
TOTAL			21,675

Double Solid Centerline
Double Solid Island
Double Solid Island
Double Solid Centerline
Double Solid Centerline
Double Solid Centerline
LT Edge Line

LT Edge Line
RT Edge Line
LT Edge Line
RT Edge Line
LT Edge Line
LT Edge Line
RT Edge Line
LT Edge Line
RT Edge Line
Skip Dash End of Gore Area
RT Edge Line
LT Edge Line
RT Edge Line

X0323660 DROP BOX NO.1

LOCATION		EACH	COMMENTS
STA 195+00	RT	1	US 6
<hr/>			
TOTAL			1

X0323661 DROP BOX NO.2

LOCATION		EACH	COMMENTS
STA 198+75	RT	1	US 6
<hr/>			
TOTAL			1

X0323662 DROP BOX NO.3

LOCATION		EACH	COMMENTS
STA 208+75	RT	1	US 6
<hr/>			
TOTAL			1

X0323663 DROP BOX NO.4

LOCATION		EACH	COMMENTS
STA 10+28	LT	1	IL 84
<hr/>			
TOTAL			1

X0323664 DROP BOX NO.5

LOCATION		EACH	COMMENTS
STA 10+61	LT	1	COLONA HEIGHTS
<hr/>			
TOTAL			1

X4402805 ISLAND REMOVAL

LOCATION		SQ.FT	COMMENTS
STA 204+60	CL	212	NW QUADRANT OF IL 84 & US 6
<hr/>			
TOTAL			212

78009008 MODIFIED URETHANE PAVEMENT MARKING - LINE 8"

LOCATION		FOOT	COMMENTS
STA 199+34	TO 201+53 US 6	73	White
STA 201+53	TO 204+31 US 6	278	White
STA 205+41	TO 208+14 US 6	273	White
STA 208+14	TO 210+39 US 6	75	White
STA 204+61	TO 204+71 US 6	181	White
STA 207+69	TO 210+02 US 6	466	White
STA 1+98	TO 4+78 IL 84	477	White
STA 1+02	TO 4+03 IL 84	301	White
STA 4+03	TO 6+26 IL 84	74	White
<hr/>			
TOTAL			2,198

Turkey Tracks
Turn Bay Line Solid
Turn Bay Line Solid
Turkey Tracks
Island Outside Lines
Gore Area Outside Lines
Gore Area Outside Lines
Turn Bay Line Solid
Turkey Tracks

Z0020900 ESTABLISHING AND REFERENCING LAND SECTION MARKERS

LOCATION		EACH	COMMENTS
STA 204+86.0	63.6' RT	1	
<hr/>			
TOTAL			1

Z0023600 FILLING EXISTING CULVERT

LOCATION		EACH	COMMENTS
STA 194+07	US 6	1	
STA 200+77	US 6	1	
STA 1006+00	SLIP RAMP	1	
<hr/>			
TOTAL			3

78009012 MODIFIED URETHANE PAVEMENT MARKING - LINE 12"

LOCATION		FOOT	COMMENTS
STA 207+85	TO 209+75 US 6	85	WHITE
STA 204+56	LT US 6	244	WHITE
STA 2+07	TO 4+19 IL 84	80	WHITE
<hr/>			
TOTAL WHITE:			409
STA 196+17	TO 201+25 US 6	157	YELLOW
STA 208+24	TO 213+62 US 6	157	YELLOW
<hr/>			
TOTAL YELLOW:			314
<hr/>			
TOTAL			723

Gore Area
Island
Gore Area

Island Median
Island Median

Z0025500 PROPERTY MARKERS

LOCATION		EACH	COMMENTS
STA 195+85	LT US 6	1	
STA 199+57	LT US 6	1	
STA 209+55	RT US 6	1	
STA 215+22	LT US 6	1	
STA 216+40	RT US 6	1	
STA 6+06	RT IL 84	1	
<hr/>			
TOTAL			6

78009024 MODIFIED URETHANE PAVEMENT MARKING - LINE 24"

LOCATION		FOOT	COMMENTS
STA 204+33	US 6	36	White
STA 205+40	US 6	24	White
STA 99+84	400 th St.	27	White
STA 0+75	IL 84	18	White
STA 0+78	IL 84	12	White
<hr/>			
TOTAL			117

E.B. Stop Bar
W.B. Stop Bar
N.B. Stop Bar
S.B. Turn Lane Stop Bar
S.B. Stop Bar

Z0054500 ROCK FILL

LOCATION		INCHES	AREA SQ.FT	TON
STA 196+25		12"	440	33
STA 198+75		12"	675	51
STA 203+25		36"	785	179
STA 209+13.60		12"	750	57
STA 10+76.35		36"	803	183
<hr/>				
TOTAL				503

Z0065765 SLOTTED DRAIN 18" WITH VARIABLE SLOT

LOCATION		FOOT	COMMENTS
STA 207+82	TO 208+98 US 6	116	
<hr/>			
TOTAL			116

* 5789 & 5861

FILE NAME =	USER NAME = cushmenbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwork\pwork\cushmenbw\d0333009\201709-shit-schedule.dgn	DRAWN -	REVISED -	*			2R-1	HENRY	235	21	
PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -	CONTRACT NO. 64J43							
PLOT DATE = Wed Aug 06 09:01:42 2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
SCALE:		SHEET NO.	OF SHEETS	STA.	TO STA.					