

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY RURAL	BRIDGE RURAL
				0004	0014
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	945	945	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	117.5	117.5	
20200100	EARTH EXCAVATION	CU YD	323	323	
20400800	FURNISHED EXCAVATION	CU YD	986	986	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	99		99
25000300	SEEDING, CLASS 3	ACRE	0.5	0.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	46	46	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	46	46	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	46	46	
25100630	EROSION CONTROL BLANKET	SQ YD	2497	2497	
28000305	TEMPORARY DITCH CHECKS	FOOT	40	40	
28000400	PERIMETER EROSION BARRIER	FOOT	800	800	
28100207	STONE RIPRAP, CLASS A4	TON	358	358	
28100209	STONE RIPRAP, CLASS A5	TON	88		88

14

* SPECIALTY ITEMS

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\work\gisdot\carpentard\100103254\286047-hl-500.dgn	286047-hl-500.dgn	DRAWN -	REVISED -					613	(80 BR)BR	BUREAU	63	3
PLOT SCALE = 1/8"=1'-0"	1/8"=1'-0"	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 66A17		
PLOT DATE = 8/6/2014	8/6/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							

Rev.