

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | |
|----------|--|-------|----------------|-------------------|--------------|
| | | | | ROADWAY | RURAL BRIDGE |
| | | | | 0004 | 0014 |
| | | | | RURAL | 053-0157 |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 281 | 281 | |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | 34 | 34 | |
| 20101000 | TEMPORARY FENCE | FOOT | 67 | 67 | |
| 20200100 | EARTH EXCAVATION | CU YD | 823 | 823 | |
| 20300100 | CHANNEL EXCAVATION | CU YD | 30 | 30 | |
| 25000210 | SEEDING, CLASS 2A | ACRE | 0.7 | 0.7 | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 63 | 63 | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 63 | 63 | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 63 | 63 | |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 3367 | 3367 | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 140 | 140 | |
| 28000305 | TEMPORARY DITCH CHECKS | FOOT | 46 | 46 | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 320 | 320 | |
| 28100107 | STONE RIPRAP, CLASS A4 | SQ YD | 300 | | 300 |

* SPECIALTY ITEMS

| | | | | | | | | | | | | | |
|--|-----------------------|------------|-----------|---|---|-----------|------------|----|--------------------|---------|--------|--------------|-----------|
| FILE NAME = | USER NAME = lukkeridp | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | | F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| et\pwwork\pwwork\lukkeridp\08179225\036618-ent-500.dgn | | DRAWN - | REVISED - | | 370 | 102 BR BR | LIVINGSTON | 65 | 3 | | | | |
| PLOT SCALE = 100.0000' / 1" | | CHECKED - | REVISED - | | SCALE: SHEET NO. 1 OF 3 SHEETS STA. TO STA. | | | | CONTRACT NO. 66A18 | | | | |
| PLOT DATE = 0/14/2014 | | DATE - | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | | | | |