

SI = SPECIALTY ITEMS				CONSTRUCTION CODE							
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%
				ROADWAY 0003	BOX CULVERT 0040 SN 047-2022	BOX CULVERT 0040 SN 047-2030	BOX CULVERT 0040 SN 047-2032	BOX CULVERT 0040 SN 047-2033	TRAFFIC SIGNALS 0021	HIGHWAY LIGHTING 0021	
SI	81028390 UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	10						10		
SI	81028750 UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA.	FOOT	145							145	
SI	81028770 UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 3" DIA.	FOOT	230							230	
SI	81100600 CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	48						48		
SI	81400700 HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	15						15		
SI	81400720 DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1						1		
SI	81603040 UNIT DUCT, 600V, 2-1/C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	4545							4545	
SI	81702150 ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	150							150	
SI	81702450 ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	4503						4503		
SI	82102400 LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	20						4	16	
SI	82500340 LIGHTING CONTROLLER, PEDESTAL MOUNTED, 480VOLT, 60AMP	EACH	1							1	
SI	83010500 LIGHT POLE, ALUMINUM, 50 FT. M.H., 12 FT. MAST ARM	EACH	16							16	
SI	83600300 LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	112							112	
SI	83800205 BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	16							16	
PH											
DESIGNED LDZ DRAWN SRH/RMD CHECKED DJD DATE 7/01/2014				STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				IL RTE. 47 SUMMARY OF QUANTITIES			
SCALE: N/A				SHEET 17 OF 22 SHEETS				STA. N/A TO STA. N/A			
F.A.P. RTE. 326				SECTION 109, 110R-1				COUNTY KENDALL			
TOTAL SHEET NO. 20				CONTRACT NO. 66884				ILLINOIS FED. AID PROJECT			