

PAVEMENT MARKING													
STATION	TO	STATION	LETTERS & SYMBOLS	MODIFIED URETHANE LINES								PREF. PLASTIC 6" TYPE B INL	
				4"				8"		12"			24"
				SOLID WHITE	SOLID YELLOW	DOUBLE YELLOW	SOLI WHITE	DOTTED WHITE	SOLID WHITE	SOLID YELLOW	SOLID WHITE		SKIP DASH WHITE
		EDGE OF PAV'T	EDGE OF PAV'T	CL & MEDIAN	LANE LINE	LINE	MED / DIAG	MED / DIAG	LINE	CENTERLINE			
		SQ FT											
IL 47													
6260+81	TO	6310+64	46.8	10070	9962		270	150	125		2482		
6310+64	TO	6345+61	93.6	6975	6808		559	149	260		1692		
6345+61	TO	6424+60	327.6	15798	15574		2070	531	301	257	3911		
6424+60	TO	6450+94	252.0	5299	4814		2117	385	432	62	1249		
6450+94	TO	6467+97	158.4	3368	3097		1622	226	411	60	758		
6467+97	TO	6503+91	93.6	7146	6986		588	152	301		1733		
6503+91	TO	6530+44	58.8	5280	6288		534	114	268	477	1293		
6530+44	TO	6556+93	99.6	5318	5170		1185	113	539		1290		
6556+93	TO	6583+44	140.4	5294	5488		864	225	298	240	1274		
6583+44	TO	6635+82	311.7	10487	7735	5485	1596	241	198	914	1952		
WHITEWILLOW RD													
601+17	TO	608+15	46.8	1405		1432	266	69		27			
609+83	TO	616+00	46.8	1233		1265	266	69		27			
JOLIET RD													
701+00	TO	709+11	93.6	1662		1668	160	102		31			
QUARRY RD													
800+18	TO	801+95		259		327				21			
TOWNHALL RD													
900+50	TO	907+08		491		538				19			
US 52													
1000+00	TO	1007+96	124.8	1598		2791	265	61		170	35		
1010+04	TO	1018+00	124.8	1598		2791	265	61		169	35		
CHICAGO RD													
1102+50	TO	1108+77	46.8	1354		1346	262	75		41			
1111+22	TO	1117+34	46.8	1323		1315	262	69		41			
LISBON CENTER RD													
1201+50	TO	1208+08	93.6	1338		1316	238	69		24			
PLATTVILLE RD													
1300+92	TO	1309+05	124.8	1625		1666	529	70		28			
NEWARK RD													
1402+00	TO	1408+08	93.6	1227		1259	264	69		29			
HELMAR RD													
1501+03	TO	1508+09	46.8	1423		1453	264	69		28			
1509+91	TO	1516+50	46.8	1328		1368	264	69		30			
		TOTAL	2518.5		190839		17848		5359	537	17634		

RAISED REFLECTIVE PAVEMENT MARKERS				
LOCATION			1-WAY CRYSTAL	2-WAY AMBER
STATION	TO	STATION	EACH	
IL 47				
6260+81	TO	6310+64	257	
6310+64	TO	6345+61	183	
6345+61	TO	6424+60	449	
6424+60	TO	6450+94	162	
6450+94	TO	6467+97	101	
6467+97	TO	6503+91	190	
6503+91	TO	6530+44	135	
6530+44	TO	6556+93	148	
6556+93	TO	6583+44	149	
6583+44	TO	6635+82	229	91
WHITEWILLOW RD				
601+17	TO	608+59	8	
609+41	TO	616+00	8	
JOLIET RD				
701+00	TO	709+60	5	
US 52				
1000+00	TO	1008+48	7	42
1009+52	TO	1018+00	8	42
CHICAGO RD				
1102+50	TO	1109+56	8	
1110+44	TO	1117+34	8	
LISBON CENTER RD				
1201+50	TO	1208+60	7	
PLATTVILLE RD				
1300+40	TO	1309+05	14	
NEWARK RD.				
1402+00	TO	1408+60	7	
HELMAR RD				
1501+03	TO	1508+60	7	
1509+40	TO	1516+50	7	
SUB-TOTAL			2097	175
TOTAL			2272	

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL			
LOCATION			1-WAY CRYSTAL
STATION	TO	STATION	EACH
IL 47			
6622+20.59	TO	6635+87.31	42
US 52			
995+00.00	TO	1000+00.00	13
1018+00.00	TO	1023+00.00	12
TOTAL			67

ISLAND PAVEMENT REMOVAL		
STATION	OFFSET	SQ YD
US 52		
1007+93.2	33.1' RT	16
1007+99.3	35.6' LT	17
1008+61.7	35.9' RT	18
1008+68.1	32.9' LT	16
TOTAL		67

BUILDING REMOVAL					
NUMBER	STATION +/-	SIDE	OFFSET +/-	TYPE	L SUM
IL 47					
1	6383+18.00	RT	75	HOUSE	1
2	6384+57.00	RT	100	BARN	1
3	6447+90.00	RT	65	HOUSE	1
4	6449+55.00	RT	80	GARAGE	1
5	6449+56.00	RT	72	GARAGE	1
6	6450+12.00	RT	35	HOUSE	1
7	6452+26.00	RT	55	COMMERCIAL	1
8	6495+30.00	RT	75	HOUSE	1
9	6503+37.00	RT	100	HOUSE	1
10	6569+67.00	RT	75	HOUSE	1
11	6571+86.00	RT	60	BARN	1
12	6572+80.00	RT	100	GARAGE	1
LISBON CENTER RD					
13	1205+81.00	LT	65	HOUSE	1
TOTAL					13

SEE SPECIAL PROVISION.

PAVEMENT MARKING REMOVAL - STAGING							
STATION	TO	STATION	LINES				L & S
			4"	6"	8"	12"	
			SQ FT				
IL 47							
6259+50	TO	6277+00	1711	53	50	307	84
TOTAL			2205				

GROOVING FOR RECESSED PAVEMENT MARKING									
STATION	TO	STATION	LETTERS, NUMBERS, & SYMBOLS	5"	7"	9"		13"	25"
				SOLID LINE	SKIP DASH CENTER LINE	SOLID LANE LINE	DOTTED LINE	SOLID MED / DIAG	SOLID LINE
			SQ FT						
IL 47									
6260+81	TO	6310+64	46.8	20033	2482	270	150	125	
6310+64	TO	6345+61	93.6	13783	1692	559	149	260	
6345+61	TO	6424+60	327.6	31372	3911	2070	531	558	
6424+60	TO	6450+94	252.0	10113	1249	2117	385	432	62
6450+94	TO	6467+97	158.4	6465	758	1622	226	411	60
6467+97	TO	6503+91	93.6	14132	1733	588	152	301	
6503+91	TO	6530+44	58.8	11568	1293	534	114	745	
6530+44	TO	6556+93	99.6	10488	1290	1185	113	539	
6556+93	TO	6583+44	140.4	10782	1274	864	225	538	
6583+44	TO	6635+82	311.7	23707	1952	1596	241	1112	
US 52									
1000+00	TO	1007+96	124.8	4389		265	61	170	35
1010+04	TO	1018+00	124.8	4388		265	61	169	35
TOTAL				1832	161219	17634	14343	5359	191

FILE NAME =	USER NAME = bdecreane	DESIGNED - LDZ	REVISED -
V:\3195\66884 (North Section)\CADD Sheets\0366884-shr-schedule-26.dgn		DRAWN - SGM	REVISED -
	PLOT SCALE = 2.000' / 1" =	CHECKED - DJD	REVISED -
SHT.PLAN	PLOT DATE = 7/14/2014	DATE - 7/01/2014	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL. RTE. 47 SCHEDULES OF QUANTITIES			
SCALE: N/A	SHEET 26	OF 28 SHEETS	STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(109, 110)R-1	KENDALL	619	66
CONTRACT NO. 66884				
ILLINOIS FED. AID PROJECT				