FINAL SURVEY	NOTE BOOK	
	SURVEYED	
	PLOTTED	
	TEMPLATE	
	AREAS	
	AREAS CHECKED	
NO.	BY	DATE

ORIGINAL SURVEY	NOTE BOOK	
	SURVEYED	
	PLOTTED	
	TEMPLATE	
	AREAS	
	AREAS CHECKED	
NO.	BY	DATE

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

630 625 620 615

EX. EASEMENT — EX. ℄ — EX. ROW — EX. ROW 628.05 — 626.76 — 628.05 — PR ROW

1:4.6 — 1:4 — 1:8 — 1:8 — 1:4 — 1:3

S.D. 619.40

ST1 C = 90
ST1 F = 235
ST1 UC = 0
ST1 TSE = 78

EX. GAS

O. TELE.

ST3 C = 160
ST3 F = 93
ST3 UC = 0
ST3 TSE = 23

S.D. 619.60

6433 + 00.00

635 630 625 620 615

EX. EASEMENT — EX. ℄ — PRIVATE AGGREGATE ENTRANCE — EX. ROW — EX. ROW 628.29 — 626.91 — 628.29 — PR ROW

3.66% — 1:8 — 1:8 — 1:4 — 1:3

PR 30" CLASS D

ST1 C = 84
ST1 F = 240
ST1 UC = 0
ST1 TSE = 77

EX. GAS

O. TELE.

ST3 C = 9
ST3 F = 137
ST3 UC = 0
ST3 TSE = 23

S.D. 619.83

6432 + 23.87

630 625 620

EX. EASEMENT — EX. ℄ — EX. ROW — EX. ROW 628.37 — 626.98 — 628.37 — PR ROW

1:29.7 — 1:4 — 1:8 — 1:8 — 1:4 — 1:3

S.D. 619.70

ST1 C = 84
ST1 F = 248
ST1 UC = 0
ST1 TSE = 77

EX. GAS

O. TELE.

PR 12" SS

ST3 C = 152
ST3 F = 99
ST3 UC = 0
ST3 TSE = 24

S.D. 619.90

6432 + 00.00

PAVEMENT REMOVAL

TOPSOIL STRIPPING & EARTH EXCAVATION = TSE

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

FILE NAME = V:\3195\66B84 (North Section)\CADD Sheets\D366B84-sht-xssht-IL47.dgn	USER NAME = bdecraene	DESIGNED - HLC	REVISED -
		DRAWN - HLC	REVISED -
	PLOT SCALE = 20.0000 ' / in.	CHECKED - CAS	REVISED -
$MODELNAME$	PLOT DATE = 7/14/2014	DATE - 7/01/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. RTE. 47 CROSS SECTIONS

SCALE: H=10 V=5 | SHEET 65 OF 150 SHEETS | STA. 6432+00.00 TO STA. 6433+00.00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(109,110) R-1	KENDALL	619	484
		CONTRACT NO. 66B84		
	ILLINOIS	FED. AID PROJECT		